Item No		Unit	Quantity	Rate	Amount

SECTION NO. 1

BILL NO. 1
PRELIMINARIES

BUILDING AGREEMENT AND PRELIMINARIES

The **JBCC** Principal Building Agreement (Edition 6.2 - May 2018) prepared by the Joint Building Contracts Committee shall be the applicable building agreement, amended as hereinafter described

The **JBCC** Principal Building Agreement **contract data** form an integral part of this **agreement**

The **JBCC** General Preliminaries (May 2018) published by the Joint Building Contracts Committee for use with the **JBCC** Principal Building Agreement (Edition 6.2 - May 2018) shall be deemed to be incorporated in these **bills of quantities**, amended as hereinafter described

The **contractor** is deemed to have referred to the abovementioned documents for the full intent and meaning of each clause

The clauses in the abovementioned documents are hereinafter referred to by clause number and heading only

Where any item is not relevant to this **agreement** such item is marked N/A signifying "not applicable"

Where standard clauses or alternatives are not entirely applicable to this **agreement** such amendments, modifications, corrections or supplements as will apply are given under each relevant clause heading and such amendments, modifications, corrections or supplements shall take precedence notwithstanding anything to the contrary contained in the abovementioned documents

Carried Forward R **Not Priced**

Brought Forward		R	**Not Priced**

PREAMBLES FOR TRADES

The General Preambles for Trades 2017 published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these **bills of quantities** and no claims arising from brevity of description of items fully described in the said General Preambles will be entertained

Supplementary preambles and/or specifications are incorporated in these **bills of quantities** to satisfy the requirements of this project. Such supplementary preambles and/or specifications shall take precedence over the provisions of the General Preambles

The **contractor's** prices for all items throughout these **bills of quantities** shall take account of and include where applicable for all of the obligations, requirements and specifications given in the General Preambles and in any supplementary preambles and/or specifications

STRUCTURE OF THIS PRELIMINARIES BILL

Section A : A recital of the headings of the individual clauses in the aforementioned **JBCC** Principal Building Agreement

Section B : A recital of the headings of the individual clauses in the aforementioned **JBCC** General Preliminaries

Section C : Any special clauses to meet the particular circumstances of the project

PRICING OF PRELIMINARIES

Should the **contractor** select Option A in the **contract data** for the adjustment of **preliminaries**, the amounts entered against the relevant items in these **preliminaries** are to be divided into one or more of the three categories provided namely fixed (F), value related (V) and time related (T)

SECTION A: PRINCIPAL BUILDING AGREEMENT

Carried Forward		R	**Not Priced**

	Brought Forward			R	**Not Priced**
	Interpretation (A1-A7)				
1	Clause 1.0 - Definitions and interpretation **Pricing of bills of quantities** The **contractor** is to allow opposite each item for all costs in connection therewith. All prices to include, unless otherwise stated, for all materials, fabrication, conveyance and delivery, unloading, storing, unpacking, hoisting, labour, setting, fitting and fixing in position, cutting and waste (except where to be measured in accordance with the standard system of measurement), patterns, models and templates, plant, temporary works, returning of packaging, duties, taxes (other than Value Added Tax), imposts, establishment charges, overheads, profit and all other obligations arising out of this **agreement**. Value Added Tax (VAT) is to be separately stated on the summary page of these **bills of quantities** Items left unpriced will be deemed to be covered in prices against other items throughout these **bills of quantities** and no claim for any extras arising out of the **contractor's** omission to price any item will be entertained Prices for all **construction equipment**, temporary works, services and other items shall include for the supply, maintenance, operating cost and subsequent removal and making good as necessary **Abbreviated descriptions** The items in these **bills of quantities** utilise abbreviated descriptions. It is the intention that the abbreviated descriptions be fully described when read with the applicable measuring system and the relevant preambles and/or specifications. However, should the full intent and meaning of any description not be clear, the **contractor** shall, before submission of his tender, call for a written directive from the **principal agent**, failing which it shall be assumed that the **contractor** has allowed in his pricing for materials and workmanship in terms of international best practice				
	Carried Forward			R	**Not Priced**

	Brought Forward		R	**Not Priced**
	Legal status of contractor If the **contractor** constitutes a joint venture, consortium or other unincorporated grouping of two or more persons then: 1. These persons are deemed to be jointly and severally liable to the **employer** for the performance of this **agreement** 2. These persons shall notify the **employer** of their leader who has assigned authority to bind the **contractor** and each of these persons 3. The **contractor** shall not alter its composition or legal status without the prior written consent of the **employer** F:..... V:..... T:.....	Item		200 000.00
2	Clause 2.0 - **Law**, regulations and **notices** F:..... V:..... T:.....	Item		**Not Priced**
3	Clause 3.0 - Offer and acceptance F:..... V:..... T:.....	Item		**Not Priced**
4	Clause 4.0 - Cession and assignment F:..... V:..... T:.....	Item		**Not Priced**
5	Clause 5.0 - Documents **Value Added Tax** Provision is made in the summary page of these **bills of quantities** for the inclusion of Value Added Tax (VAT)			
	Carried Forward		R	200 000.00

Brought Forward			R	200 000.00
Priced document as specification Clause 5.4 is deemed to be deleted The **principal agent** shall decide which portion of the **priced document** may be used as a specification of **materials and goods** or methods, if any **Electronic issue of drawings** All drawings for this project will be issued electronically and the **contractor** shall be deemed to have received such drawings on the date that such drawings have been dispatched electronically [5.6] F:..... V:..... T:.....		Item		**Not Priced**
Carried Forward			R	200 000.00

	Brought Forward			R	200 000.00
6	Clause 6.0 - **Employer's agents** 6.1. Development Manager: Rhulani Chauke 6.2. Agent Service: Architect KNV Architects 6.3. Agent Service: Quantity Surveyor Evidence 6.4. Agent Service: Civil Engineer TBA 6.5. Agent Service: Structural Engineer: TBA 6.6. Agent Service: Electrical Engineer 6.7. Agent Service: Mechanical, Wet services and Fire Engineer 6.8. Agent Service: Health and Safety TBA 6.9. Agent Service: Environmental Health TBA **6.1 Delegated authority** The authority of the **principal agent** to issue **contract instructions** [17.1] and perform duties for specific aspects of the **works** is delegated to **agents** as follows [6.2]. This does not preclude the **principal agent** from issuing such **contract instructions**:				
	Carried Forward			R	200 000.00

Brought Forward		R	200 000.00
6.2. Architect			
6.2.1 Duties [6.2] : The architect is responsible for the architectural design, functional design and quality inspection of the **works**			
6.2.2 **Contract instructions** [6.2; 17.1] :			
6.2.2.1 Rectification of discrepancies, errors in description or quantity or omission of items in the **agreement** other than in the **JBCC** Principal Building Agreement			
6.2.2.2 Alteration to design, standards or quantity of the **works** provided that such **contract instructions** shall not substantially change the scope of the **works**			
6.2.2.3 The **site** [13.0]			
6.2.2.4 Compliance with the **law**, regulations and bylaws [2.1]			
6.2.2.5 Provision and testing of samples of **materials and goods** and/or of finishes and assemblies of elements of the **works**			
6.2.2.6 Opening up of work for inspection, removal or re-execution [23.2.4; 26.4.2]			
6.2.2.7 Removal or re-execution of work			
6.2.2.8 Removal or substitution of any **materials and goods**			
6.2.2.9 Protection of the **works**			
6.2.2.10 Making good physical loss and repairing damage to the **works** [23.2.2]			
6.2.2.11 Rectification of **defects** [21.2]			
Carried Forward		R	200 000.00

	Brought Forward		R	200 000.00
6.2.2.12	A **list for practical completion** specifying outstanding or defective work to be rectified to achieve **practical completion**, a **list for completion** and a **list for final completion** specifying outstanding or defective work to be rectified to achieve **final completion**			
6.2.2.13	Expenditure of **budgetary allowances**, **prime cost amounts** and **provisional sums**			
6.2.2.14	Appointment of a **subcontractor** [14.0; 15.0]			
6.2.2.15	Work by **direct contractors** [16.0]			
6.2.2.16	On suspension or termination, protection of the **works**, removal of **construction equipment** and surplus **materials and goods** [29.0]			
6.3.	Quantity surveyor			
6.3.1	Duties [6.2] :			
	The quantity surveyor is responsible for all measurements, valuations, financial assessments and all other quantity surveying and cost control functions of the **works**			
6.3.2	**Contract instructions** [6.2; 17.1] :			
6.4.	Civil engineer			
6.4.1	Duties [6.2] :			
	The civil engineer is responsible for all aspects of civil and structural engineering design and quality inspection of the **works**			
6.4.2	**Contract instructions** [6.2; 17.1] :			
6.4.2.1	Rectification of discrepancies, errors in description or quantity or omission of items in the **agreement** other than in the **JBCC** Principal Building Agreement			
	Carried Forward		R	200 000.00

	Brought Forward		R	200 000.00
6.4.2.2	Alteration to design, standards or quantity of the **works** provided that such **contract instructions** shall not substantially change the scope of the **works**			
6.4.2.3	The **site** [13.0]			
6.4.2.4	Compliance with the **law**, regulations and by laws [2.1]			
6.4.2.5	Provision and testing of samples of **materials and goods** and/or of finishes and assemblies of elements of the **works**			
6.4.2.6	Opening up of work for inspection, removal or re-execution [23.2.4; 26.4.2]			
6.4.2.7	Removal or re-execution of work			
6.4.2.8	Removal or substitution of any **materials and goods**			
6.4.2.9	Protection of the **works**			
6.4.2.10	Making good physical loss and repairing damage to the **works** [23.2.2]			
6.4.2.11	Rectification of **defects** [21.2]			
6.4.2.12	A **list for practical completion** specifying outstanding or defective work to be rectified to achieve **practical completion**, a **list for completion** and a **list for final completion** specifying outstanding or defective work to be rectified to achieve **final completion**			
6.4.2.13	Expenditure of **budgetary allowances**, **prime cost amounts** and **provisional sums**			
6.5.	Structural engineer			
	Carried Forward		R	200 000.00

	Brought Forward		R	200 000.00
6.5.1 Duties [6.2] : The structural engineer is responsible for all aspects of civil and structural engineering design and quality inspection of the **works** 6.5.2 **Contract instructions** [6.2; 17.1] : 6.5.2.1 Rectification of discrepancies, errors in description or quantity or omission of items in the **agreement** other than in the **JBCC** Principal Building Agreement 6.5.2.2 Alteration to design, standards or quantity of the **works** provided that such **contract instructions** shall not substantially change the scope of the **works** 6.5.2.3 The **site** [13.0] 6.5.2.4 Compliance with the **law**, regulations and by laws [2.1] 6.5.2.5 Provision and testing of samples of **materials and goods** and/or of finishes and assemblies of elements of the **works** 6.5.2.6 Opening up of work for inspection, removal or re-execution [23.2.4; 26.4.2] 6.5.2.7 Removal or re-execution of work 6.5.2.8 Removal or substitution of any **materials and goods** 6.5.2.9 Protection of the **works** 6.5.2.10 Making good physical loss and repairing damage to the **works** [23.2.2] 6.5.2.11 Rectification of **defects** [21.2]				
	Carried Forward		R	200 000.00

	Brought Forward		R	200 000.00
6.5.2.12	A **list for practical completion** specifying outstanding or defective work to be rectified to achieve **practical completion**, a **list for completion** and a **list for final completion** specifying outstanding or defective work to be rectified to achieve **final completion**			
6.5.2.13	Expenditure of **budgetary allowances**, **prime cost amounts** and **provisional sums**			
6.6.	Mechanical, wet services and fire engineer			
6.6.1	Duties [6.2] :			
	The mechanical, wet services and fire engineer is responsible for all aspects of mechanical engineering design and quality inspection of the **works** and, where appointed by the **employer** for quantity surveying services in respect of the mechanical installations, for all measurements, valuations, financial assessments and all other quantity surveying and cost control functions			
6.6.2	**Contract instructions** [6.2; 17.1] :			
6.6.2.1	Rectification of discrepancies, errors in description or quantity or omission of items in the **agreement** other than in the **JBCC** Principal Building Agreement			
6.6.2.2	Alteration to design, standards or quantity of the **works** provided that such **contract instructions** shall not substantially change the scope of the **works**			
6.6.2.3	Compliance with the **law**, regulations and bylaws [2.1]			
6.6.2.4	Provision and testing of samples of **materials and goods** and/or of finishes and assemblies of elements of the **works**			
6.6.2.5	Opening up of work for inspection, removal or re-execution [23.2.4; 26.4.2]			
6.6.2.6	Removal or re-execution of work			
	Carried Forward		R	200 000.00

	Brought Forward		R	200 000.00
	6.6.2.7 Removal or substitution of any **materials and goods**			
	6.6.2.8 Protection of the **works**			
	6.6.2.9 Making good physical loss and repairing damage to the **works** [23.2.2]			
	6.6.2.10 Rectification of **defects** [21.2]			
	6.6.2.11 A **list for practical completion** specifying outstanding or defective work to be rectified to achieve **practical completion**, a **list for completion** and a **list for final completion** specifying outstanding or defective work to be rectified to achieve **final completion**			
	6.6.2.12 Expenditure of **budgetary allowances**, **prime cost amounts** and **provisional sums**			
	6.7. Electrical engineer			
	6.7.1 Duties [6.2] :			
	The electrical engineer is responsible for all aspects of electrical engineering design and quality inspection of the **works** and, where appointed by the **employer** for quantity surveying services in respect of the electrical installations, for all measurements, valuations, financial assessments and all other quantity surveying and cost control functions			
	6.7.2 **Contract instructions** [6.2; 17.1] :			
	6.7.2.1 Rectification of discrepancies, errors in description or quantity or omission of items in the **agreement** other than in the **JBCC** Principal Building Agreement			
	6.7.2.2 Alteration to design, standards or quantity of the **works** provided that such **contract instructions** shall not substantially change the scope of the **works**			
	6.7.2.3 Compliance with the **law**, regulations and bylaws [2.1]			
	Carried Forward		R	200 000.00

	Brought Forward		R	200 000.00
6.7.2.4	Provision and testing of samples of **materials and goods** and/or of finishes and assemblies of elements of the **works**			
6.7.2.5	Opening up of work for inspection, removal or re-execution [23.2.4; 26.4.2]			
6.7.2.6	Removal or re-execution of work			
6.7.2.7	Removal or substitution of any **materials and goods**			
6.7.2.8	Protection of the **works**			
6.7.2.9	Making good physical loss and repairing damage to the **works** [23.2.2]			
6.7.2.10	Rectification of **defects** [21.2]			
6.7.2.11	A **list for practical completion** specifying outstanding or defective work to be rectified to achieve **practical completion**, a **list for completion** and a **list for final completion** specifying outstanding or defective work to be rectified to achieve **final completion**			
6.7.2.12	Expenditure of **budgetary allowances**, **prime cost amounts** and **provisional sums**			
6.8.	Health and safety consultant			
6.8.1	Duties [6.2] :			
	The health and safety consultant is responsible for all aspects of health and safety of the **works**. Without derogating from the generality thereof, the health and safety consultant will perform the following specific functions and duties in respect of the health and safety aspects of the **works**. He shall:			
6.8.1.1	Act as the **employer's agent** in terms of the Construction Regulations issued in terms of the Occupational Health and Safety Act,1993 as amended			
	Carried Forward		R	200 000.00

	Brought Forward			R	200 000.00
	6.8.1.2 Prepare and update the health and safety specification for the **works**				
	6.8.1.3 Agree with the **contractor** the health and safety plan for the **works**				
	6.8.1.4 Carry out regular audits to ensure adherence to the safety plan and compliance with the act and regulations				
	6.8.1.5 Stop the execution of the **works** where the agreed specification or plan is not adhered to				
	6.9. Environmental Health consultant				
	6.9.1 Duties [6.2] :				
	The Environmental health consultant is responsible for all aspects of environmental health of the **works**. Without derogating from the generality thereof, the environmental health consultant will perform the following specific functions and duties in respect of the environment health aspects of the **works** and the construction site environmental plan				
	6.8.1.1 Act as the **employer's agent** in terms of the Construction Regulations issued in terms of the National Health Act, 2003				
	F:..... V:..... T:.....		Item		**Not Priced**
7	Clause 7.0 - Design responsibility				
	F:..... V:..... T:.....		Item		**Not Priced**
	Insurances and securities (A8-A11)				
8	Clause 8.0 - **Works** risk				
	F:..... V:..... T:.....		Item		**Not Priced**
	Carried Forward			R	200 000.00

	Brought Forward			R	200 000.00
9	Clause 9.0 - Indemnities				
	F:..... V:..... T:.....		Item		**Not Priced**
10	Clause 10.0 - Insurances				
	F:..... V:..... T:.....		Item		**Not Priced**
11	Clause 11.0 - **Securities**				
	Guarantee for payment				
	The **employer** shall not provide to the **contractor** a **guarantee for payment** in the amount of N/A .....Rand (R N/A.....) [11.5.1]. The **contractor** shall consequently waive his lien or right of continuing possession of the **works** [11.10]				
	Extension of waiver of lien				
	The **contractor** shall ensure that a waiver of lien is included in all subcontracts and that the **works** executed on the **site** are kept free of all liens and other encumbrances at all times [11.10]				
	F:..... V:..... T:.....		Item		**Not Priced**
	<u>Execution (A12 - A17)</u>				
12	Clause 12.0 - Obligations of the **parties**				
	Office accommodation				
	The **contractor** shall provide, maintain and remove on **practical completion** air conditioned office accommodation with suitable tables and chairs for meetings to be held on the **site**. Such offices shall be kept clean and fit for use at all times [12.2.18]				
	Carried Forward			R	200 000.00

	Brought Forward			R	200 000.00
	Notice board The **contractor** shall erect in a position approved by the **principal agent**, maintain and remove on **practical completion** a notice board recommended by the South African Institute of Architects and as approved by the **principal agent** listing the names and logos of the **employer**, the **contractor** and the professional consultants. No subcontractor or supplier notice boards may be erected unless permission is granted by the **principal agent** for such notice boards to be erected [12.2.18]				
	Statutory and other notices The **contractor** shall submit and/or comply with all statutory and other notices that may be required by any local or other authority in order not to cause any delay to the commencement of the **works** by the **contractor**. The **contractor** shall pay all deposits or fees in this regard It is, however, specifically recorded that the **employer** shall be responsible for the timeous approval of building plans by any local or other authorities and the payment of any fees or charges related thereto				
	F:..... V:..... T:.....		Item		**Not Priced**
13	Clause 13.0 - Setting out				
	F:..... V:..... T:.....		Item		**Not Priced**
14	Clause 14.0 - Nominated **subcontractors**				
	F:..... V:..... T:.....		Item		**Not Priced**
15	Clause 15.0 - Selected **subcontractors**				
	F:..... V:..... T:.....		Item		**Not Priced**
	Carried Forward			R	200 000.00

	Brought Forward			R	200 000.00
16	Clause 16.0 - **Direct contractors**				
	Attendance on direct contractors				
	In respect of **direct contractors** the **contractor** shall:				
	1. Designate an area for the **direct contractor** to establish a temporary office and workshop and storage of equipment and materials				
	2. Allow the use of personnel welfare facilities, where provided				
	3. Provide water, lighting and single phase electric power to a position within 50m of the place where the direct contract work is to be carried out, other than fuel or power for commissioning of any installation				
	4. Permit the **direct contractor** to use erected scaffolding, hoisting facilities, etc provided by the **contractor**, in common with others having the like right, while it remains erected on the **site** [16.1]				
	F:..... V:..... T:.....		Item		**Not Priced**
17	Clause 17.0 - **Contract instructions**				
	Site instructions				
	Instructions issued on **site** are to be recorded in a site instruction book which is to be supplied and maintained on **site** by the **contractor**				
	F:..... V:..... T:.....		Item		**Not Priced**
	<u>Completion (A18 - A24)</u>				
18	Clause 18.0 - Interim completion		N/A		
19	Clause 19.0 - **Practical completion**				
	F:..... V:..... T:.....		Item		**Not Priced**
	Carried Forward			R	200 000.00

	Brought Forward			R	200 000.00
20	Clause 20.0 - Completion in **sections**				
	F:..... V:..... T:.....		Item		**Not Priced**
21	Clause 21.0 - **Defects** liability period and **final completion**				
	F:..... V:..... T:.....		Item		**Not Priced**
22	Clause 22.0 - **Latent defects** liability period				
	F:..... V:..... T:.....		Item		**Not Priced**
23	Clause 23.0 - Revision of the date for **practical completion**				
	Substitution of materials and goods				
	The removal or substitution of any **materials and goods** which do not conform to the specification or the **contract drawings** shall not constitute grounds for the extension of the **construction period** nor for the adjustment of the **contract value** [17.1.8; 23.1 & 2]				
	F:..... V:..... T:.....		Item		**Not Priced**
24	Clause 24.0 - **Penalty** for late or non-completion				
	F:..... V:..... T:.....		Item		**Not Priced**
	<u>Payment (A25 - A27)</u>				
25	Clause 25.0 - Payment				
	Carried Forward			R	200 000.00

	Brought Forward			R	200 000.00
	Prices submitted Where prices are submitted by the **contractor** or **subcontractor** during the progress of the **works** in respect of **contract instructions** or in regard to a claim under the terms of this **agreement** and notwithstanding the fact that such prices may be used in an interim **payment certificate**, there is to be no presumption of acceptance. Should the **principal agent** wish to accept any such prices prior to the issue of the **certificate of final completion**, it shall be in writing F:..... V:..... T:.....		Item		**Not Priced**
26	Clause 26.0 - Adjustment of the **contract value** and **final account** **Fluctuations in costs** All fluctuations in costs, with the exception of fluctuations in the rate of Value Added Tax, shall be for the account of the **contractor** [26.9.5] **Cost of claims** All costs incurred by the **contractor** in the preparation of claims shall be borne by the **contractor**. This provision shall not preclude an adjudicator or an arbitrator appointed in terms of this **agreement** [30.6 & 7] from making a determination on costs **Claims from subcontractors** The **contractor** shall review, assess and adjudicate any claims received by him from any **subcontractor** and thereafter submit same to the **principal agent** with a recommendation in order to assist the **principal agent** in adjudicating the claim [26.6] F:..... V:..... T:.....		Item		**Not Priced**
	Carried Forward			R	200 000.00

	Brought Forward			R	200 000.00
27	Clause 27.0 - Recovery of expense and/or loss				
	F:..... V:..... T:.....		Item		**Not Priced**
	Suspension and termination (A28 - A29)				
28	Clause 28.0 - Suspension by the **contractor**				
	F:..... V:..... T:.....		Item		**Not Priced**
29	Clause 29.0 - Termination				
	F:..... V:..... T:.....		Item		**Not Priced**
	Dispute resolution (A30)				
30	Clause 30.0 - Dispute resolution				
	F:..... V:..... T:.....		Item		**Not Priced**
31	**Agreement**				
	The required information of the **parties** and the amount of the **contract sum** shall be inserted in the **agreement** for signature of the **agreement** by the **parties**				
	F:..... V:..... T:.....		Item		**Not Priced**
32	**Contract data**				
	Tenderer's selections				
	Before submission of his tender the **contractor** is to complete the tenderer's selections in the **contract data**				
	F:..... V:..... T:.....		Item		**Not Priced**
	SECTION B: GENERAL PRELIMINARIES				
	Carried Forward			R	200 000.00

	Brought Forward		R	200 000.00
	Definitions and interpretation (B1)			
33	Clause 1.1 - Definitions F:..... V:..... T:.....	Item		**Not Priced**
34	Clause 1.2 - Interpretation F:..... V:..... T:.....	Item		**Not Priced**
	Documents (B2)			
35	Clause 2.1 - Checking of documents F:..... V:..... T:.....	Item		**Not Priced**
36	Clause 2.2 - Provisional **bills of quantities** **Multiple procurement** These **bills of quantities** are in multiple procurement format ie the "wet trades" - earthworks, concrete, formwork and reinforcement, precast concrete, masonry, waterproofing and sub-surface drainage - are provisionally measured and the subsequent trades are **budgetary allowances** and/or **provisional sums** F:..... V:..... T:.....	Item		**Not Priced**
37	Clause 2.3 - Availability of **construction information** F:..... V:..... T:.....	Item		**Not Priced**
38	Clause 2.4 - Ordering of **materials and goods** F:..... V:..... T:.....	Item		**Not Priced**
	Carried Forward		R	200 000.00

	Brought Forward			R	200 000.00
	Previous work and adjoining properties (B3)				
39	Clause 3.1 - Previous work - dimensional accuracy F:..... V:..... T:.....		Item		**Not Priced**
40	Clause 3.2 - Previous work - **defects** F:..... V:..... T:.....		Item		**Not Priced**
41	Clause 3.3 - Inspection of adjoining properties F:..... V:..... T:.....		Item		**Not Priced**
	The site (B4)				
42	Clause 4.1 - Handover of **site** in stages F:..... V:..... T:.....		Item		**Not Priced**
43	Clause 4.2 - Enclosure of the **works**		Item		**Not Priced**
44	Clause 4.3 - Geotechnical and other investigations F:..... V:..... T:.....		Item		**Not Priced**
45	Clause 4.4 - Encroachments F:..... V:..... T:.....		Item		**Not Priced**
46	Clause 4.5 - Existing premises occupied F:..... V:..... T:.....		Item		**Not Priced**
47	Clause 4.6 - Services - known F:..... V:..... T:.....		Item		**Not Priced**
	Carried Forward			R	200 000.00

	Brought Forward			R	200 000.00
	Management of contract (B5)				
48	Clause 5.1 - Management of the **works**				
	F:..... V:..... T:.....		Item		**Not Priced**
49	Clause 5.2 - Progress meetings				
	F:..... V:..... T:.....		Item		**Not Priced**
50	Clause 5.3 - Technical meetings				
	F:..... V:..... T:.....		Item		**Not Priced**
	Samples, shop drawings and manufacturer's instructions (B6)				
51	Clause 6.1 - Samples of materials				
	F:..... V:..... T:.....		Item		**Not Priced**
52	Clause 6.2 - Workmanship samples				
	F:..... V:..... T:.....		Item		**Not Priced**
53	Clause 6.3 - Shop drawings				
	F:..... V:..... T:.....		Item		**Not Priced**
54	Clause 6.4 - Compliance with manufacturer's instructions				
	F:..... V:..... T:.....		Item		**Not Priced**
	Deposits and fees (B7)				
55	Clause 7.1 - Deposits and fees				
	F:..... V:..... T:.....		Item		**Not Priced**
	Carried Forward			R	200 000.00

	Brought Forward			R	200 000.00
	Temporary services (B8)				
56	Clause 8.1 - Water				
	F:..... V:..... T:.....		Item		**Not Priced**
57	Clause 8.2 - Electricity				
	F:..... V:..... T:.....		Item		**Not Priced**
58	Clause 8.3 - Ablution and welfare facilities				
	F:..... V:..... T:.....		Item		**Not Priced**
59	Clause 8.4 - Communication facilities				
	F:..... V:..... T:.....		Item		**Not Priced**
	Prime cost amounts (B9)				
60	Clause 9.1 - Responsibility for **prime cost amounts**				
	F:..... V:..... T:.....		Item		**Not Priced**
	Attendance on subcontractors (B10)				
61	Clause 10.1 - General attendance				
	F:..... V:..... T:.....		Item		**Not Priced**
62	Clause 10.2 - Special attendance				
	F:..... V:..... T:.....		Item		**Not Priced**
	Carried Forward			R	200 000.00

	Brought Forward		R	200 000.00
	General (B11)			
63	Clause 11.1 - Protection of the **works** F:..... V:..... T:.....	Item		**Not Priced**
64	Clause 11.2 - Protection/isolation of existing **works** and **works** occupied in **sections** F:..... V:..... T:.....	Item		**Not Priced**
65	Clause 11.3 - Security of the **works** F:..... V:..... T:.....	Item		**Not Priced**
66	Clause 11.4 - Notice before covering work F:..... V:..... T:.....	Item		**Not Priced**
67	Clause 11.5 - Disturbance **Disturbance** All work is to be carried out in such a manner as to cause no unacceptable or unreasonable dust, noise, vibrations, nuisance, inconvenience, annoyance and the like to the public, others, other properties and traffic in so far as they exceed the permissible limitations set by government legislation or by the local authority. Any delays, stoppages and the like arising from or in order to comply with the above will not constitute grounds for an adjustment to the **construction period** or **contract value** whatsoever F:..... V:.....T:.....	Item		**Not Priced**
68	Clause 11.6 - Environmental disturbance			
	Carried Forward		R	200 000.00

	Brought Forward		R	200 000.00
	Controlling all forms of pollution The **contractor** shall be responsible for and take all precautions in controlling by whatever means necessary all forms of pollution emanating from the **site** during the **construction period** due inter alia to noise, artificial light, wind-blown sand, dust, deposits of mud, etc The **contractor** is to ensure that all roads which border the **site** and are used by the **contractor** during the execution of the **works** are kept clean and free of any dirt or debris caused by the execution of the **works** **Environmental management plan** The **employer** has prepared an environmental management plan (EMP) (refer to Annexure D-2 for a copy of the relevant plan). The **contractor** shall price opposite this item for compliance with all the requirements of such EMP			
	F:..... V:.....T:.....	Item		**Not Priced**
69	Clause 11.7 - **Works** cleaning and clearing			
	F:..... V:..... T:.....	Item		**Not Priced**
70	Clause 11.8 - Vermin			
	F:..... V:..... T:.....	Item		**Not Priced**
71	Clause 11.9 - Overhand work			
	F:..... V:..... T:.....	Item		**Not Priced**
72	Clause 11.10 - Tenant installations			
	F:..... V:..... T:.....	Item		**Not Priced**
	Carried Forward		R	200 000.00

Section No. 1
Bill No.1 PRELIMINARIES

HOUSE MALULEKE

	Brought Forward			R	200 000.00
73	Clause 11.11 - Advertising F:..... V:..... T:.....		Item		**Not Priced**
	SECTION C: SPECIFIC PRELIMINARIES				
74	Warranties for materials and workmanship Where warranties for materials and/or workmanship are called for, the **contractor** shall obtain a written warranty, addressed to the **employer**, from the entity supplying the materials and/or executing the work and shall deliver same to the **principal agent** on **final completion** of the contract The warranty shall state that workmanship, materials and installation are warranted for a specific period from the date of **practical completion** and that any **defects** that may arise during the specified period shall be made good at the expense of the entity supplying the materials and/or doing the work, upon written **notice** to do so The warranty will not be enforced if the work is damaged by **defects** in the execution of the **works**, in which case the responsibility for replacement shall rest entirely with the **contractor** F:..... V:..... T:.....		Item		**Not Priced**
75	Overtime Should overtime be required to be worked for any reason whatsoever, the cost of such overtime is to be borne by the **contractor** unless the **principal agent** has specifically authorised, prior to execution thereof, that costs for such overtime are to be borne by the **employer** F:..... V:.....T:.....		Item		**Not Priced**
	Carried Forward			R	200 000.00

Section No. 1
Bill No.1 PRELIMINARIES

HOUSE MALULEKE

	Brought Forward			R	200 000.00
76	Cooperation of the **contractor** for cost management It is specifically agreed that the **contractor** accepts the obligation of assisting the **principal agent** in implementing proper cost management. The **contractor** will be advised by the **principal agent** of all cost management procedures which will be implemented to ensure that the **contract value** does not exceed the budget F:..... V:.....T:.....		Item		**Not Priced**
77	Overloading The **contractor** shall take all necessary steps to ensure that no damage occurs due to overloading of any portion of the **works** or temporary works eg scaffolding, etc. The **contractor** shall submit details of his proposed loading, storage, plant erection, etc to the **principal agent** for approval prior to proceeding with such loading, storing or erecting and shall comply with and pay for the **principal agent's** requirements in connection with the provision of temporary support work, etc. Any damage caused to the **works** by overloading shall be made good by the **contractor** at his sole expense F:..... V:.....T:.....		Item		**Not Priced**
78	Propping of floors below The **contractor** is advised that propping of floors below may be required if he wishes to use any areas of completed suspended reinforced concrete slabs for vehicle access, storage of **materials and goods** and location of plant, scaffolding, etc. The location of these areas and any necessary propping shall be approved by the **principal agent** and the cost thereof shall be borne by the **contractor** F:..... V:.....T:.....		Item		**Not Priced**
	Carried Forward			R	200 000.00

	Brought Forward			R	200 000.00
79	Testing of flat roof waterproofing for watertightness Flat roof waterproof areas shall be flooded and kept "ponded" for at least forty eight (48) hours as a test to ensure the watertightness of the waterproofing and before any further construction work is carried out above the waterproofing F:..... V:.....T:.....		Item		**Not Priced**
80	Health and safety The **contractor** shall: 1. Comply with the health and safety specification for the **works** 2. Prepare and agree with the health and safety consultant the health and safety plan for the **works** 3. Cooperate with the health and safety consultant in all respects 4. Manage the compliance of all subcontractors with the regulations and with the health and safety plan and specification 5. Conform to the conditions contained in the **employer's** health and safety specification F:..... V:..... T:.....		Item		**Not Priced**
81	Green star building certification F:..... V:.....T:.....		Item		**Not Priced**
82	Broad based black economic empowerment (BBBEE) Tenders submitted will be evaluated taking into account their empowerment rating The **employer** will be monitoring the broad based black economic empowerment (BBBEE) status of the **contractor** throughout the execution of the **works**				
	Carried Forward			R	200 000.00

	Brought Forward			R	200 000.00
	The **contractor** is to submit to the **principal agent** on an annual basis a schedule of spend, split into vendors engaged as **subcontractors** and suppliers indicating their BBBEE rating including proof of the said rating				
	F:..... V:.....T:.....		Item		**Not Priced**
83	Advertising rights				
	The **employer** may elect to contract with advertising agencies for the erection of advertising hoardings, banners, wraps or the like for the duration of the contract. The **contractor** shall not prevent such an arrangement and will assist in the facilitation of same. The position and type of advertising structure to be agreed with the **principal agent** so as not to hinder the **contractor** in meeting his obligations under this **agreement**				
	F:..... V:.....T:.....		Item		**Not Priced**
84	Confidentiality				
	The **contractor** undertakes to maintain in confidence any and all information regarding this project and shall obtain appropriate similar undertakings from all **subcontractors** and suppliers. Such information shall not be used in any way except in connection with the execution of the **works**				
	No information regarding this project shall be published or disclosed without the prior written consent of the **employer**				
	F:..... V:.....T:.....		Item		**Not Priced**
	Carried Forward			R	200 000.00

	Brought Forward			R	200 000.00
85	Media releases All rights of publication of articles in the media, together with any advertising relating thereto or in any way connected with this project, shall vest with the **employer** The **contractor** together with his **subcontractors** shall not, without the prior written consent of the **employer**, cause any statement or advertisement connected with this project to be printed, screened or aired by the media F:..... V:.....T:.....	Item			**Not Priced**
	Allow provision for signage on the contractor's crane for the developers logo				
86	F:..... V:..... T:.....	Item			**Not Priced**
	SUMMARY OF CATEGORIES				
87	Category : Fixed R..... Category : Value R..... Category : Time R.....	Item			**Not Priced**
	Carried to Final Summary			R	200 000.00

Section No. 1
Bill No.1 PRELIMINARIES

HOUSE MALULEKE

Item No		Unit	Quantity	Rate	Amount
	SECTION NO. 2				
	BILL NO. 1				
	EARTHWORKS (PROVISIONAL)				
	STANDARD PREAMBLES				
	The contractor is referred to the Model Preambles for Trades (2008 edition) as issued the Association of South African Quantity Surveyors before pricing this bill				
	SUPPLEMENTARY PREAMBLES				
	NATURE OF GROUND				
	The nature of the ground is assumed to be loose sandy material, therefore "earth", but possibly interspersed with "hard rock" or "soft rock".				
	CARTING AWAY OF EXCAVATED MATERIAL				
	Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or alternatively, from stock piles situated on the building site.				
	PRICES				
	Prices for all filling and carting away of surplus material must make allowance for bking.				
	EXCAVATION, FILLING, ETC OTHER THAN BULK				
	Excavation in earth not exceeding 2m deep				
1	Trenches	m3	140	95.00	13 300.00
	Extra over trench and hole excavations in earth for excavation in				
2	Soft rock	m3	6	250.00	1 500.00
3	Hard Rock	m3	3	500.00	1 500.00
	Carried Forward			R	16 300.00

	Brought Forward			R	16 300.00
	Extra over all excavations for carting away				
4	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor	m3	507	40.00	20 280.00
	Risk of collapse of excavations				
5	Sides of trench and hole excavations not exceeding 1,5m deep	m2	1 694	20.00	33 880.00
	Keeping excavations free of water				
6	Keeping excavations free of water		Item		20 000.00
	FILLING ETC				
	Earth filling supplied by the contractor, compacted to 93% Mod AASHTO density				
7	Under floors,steps, pavings, etc	m3	315	85.00	26 775.00
8	Backfilling to trenches, holes, etc	m3	163	98.00	15 974.00
	Compaction of surfaces				
9	Levelling and compaction of ground surface under foundations, surface beds etc including scarifying for a depth of 150mm, breaking down oversize material and adding suitable material where necessary and compacting to 93% Mod AASHTO density	m2	315	25.00	7 875.00
	Prescribed density tests on filling				
10	Tests to determine the degree of compaction, etc. of ground or filling	No	5	800.00	4 000.00
	SOIL POISONING				
	Soil insecticide				
11	Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming	m2	315	20.00	6 300.00
12	To bottoms and sides of trenches etc	m2	6	20.00	120.00
	Carried Forward to Summary of Section 2			R	151 504.00

Section No. 2
Bill No.1 Earthwork

HOUSE MALULEKE

Item No		Unit	Quantity	Rate	Amount

SECTION 2

BILL NO. 2

CONCRETE, FORMWORK AND REINFORCEMENT

STANDARD PREAMBLES

The contractor is referred to the Model Preambles for Trades (2008 edition) as issued the Association of South African Quantity Surveyors before pricing this bill

SUPPLEMENTARY PREAMBLES

Cost of tests

The costs of making, storing and testing of concrete test cubes as required under clause 7 "Tests" of SABS 1200 G shall include the cost of providing cube moulds necessary for the purpose, for testing costs and for submitting reports on the tests to the architect. The testing shall be undertaken by an independent firm or institution nominated by the contractor to the approval of the architect. (Test cubes are measured separately).

Formwork

Descriptions of formwork shall be deemed to include use and waste only (except where described as "left in" or "permanent"), for fitting together in the required forms, wedging, plumbing and fixing to true angles and surfaces as necessary to ensure easy release during stripping and for reconditioning as necessary before re-use.

The vertical strutting shall be carried down to such construction as is sufficiently strong to afford the required support without damage and shall remain in position until the newly constructed work is able to support itself.

Carried Forward R **Not Priced**

				R	Not Priced
	Brought Forward				
	Formwork to soffits of solid slabs etc shall be deemed to be to slabs not exceeding 250mm thick unless otherwise described Formwork to sides of bases, pile caps, ground beams, etc will only be measured where it is prescribed by the engineer for design reasons. Formwork necessitated by irregularity or collapse of excavated faces will not be measured and the cost thereof shall be deemed to be included in the allowance for taking the risk of collapse of the sides of the excavations, provision for which is made in "Earthworks"				
	REINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES				
	25MPa/20mm concrete				
1	Foundations	m3	42	1 650.00	69 300.00
2	Surface beds	m3	28	1 550.00	43 400.00
	REINFORCED CONCRETE CAST ON/IN FORMWORK ETC				
	30MPa/20mm Concrete				
3	Slabs including beams and inverted beams	m3	47	2 000.00	94 000.00
4	Stairs and landings	m3	30	2 000.00	60 000.00
	TEST BLOCKS				
5	Making and testing 150 x 150 x 150mm concrete strength test cube	No	21	500.00	10 500.00
	CONCRETE SUNDRIES				
	Carried Forward			R	277 200.00

	Brought Forward			R	277 200.00
	Finishing top surfaces of concrete smooth with a power float				
6	Ground slab, ramps, etc	m2	315	35.00	11 025.00
	ROUGH FORMWORK				
	Rough formwork to sides				
7	Edges, risers, ends and reveals not exceeding 300mm high or wide (Provisional)	m	89	100.00	8 900.00
	Smooth formwork to soffits and sides				
8	Slabs propped up to a height not exceeding 3.5m	m2	315	217.50	68 512.50
	MOVEMENT JOINTS, ETC				
	REINFORCEMENT (PROVISIONAL)				
	Steel reinforcement to structural concrete work (including spacers)				
9	Various Diameter bars	t	14.00	16 000.00	224 000.00
	Fabric reinforcement				
10	Type 193 fabric reinforcement in concrete surface beds etc	m2	315	75.00	23 625.00
	Carried Forward to Summary of Section 2			R	613 262.50

Section No. 2
Bill No.2 Concrete, Formwork and Reinforcement

HOUSE MALULEKE

Item No		Unit	Quantity	Rate	Amount
	SECTION 2				
	BILL NO. 3				
	MASONRY				
	Note:				
	BRICKWORK				
	SUPERSTRUCTURE				
	Brickwork of NFPE bricks (17MPa nominal compressive strength) in class I mortar in loadbearing walls etc				
1	One brick wall in Foundation against the excavated material	m2	545	430.00	234 350.00
	BRICKWORK				
	Brickwork of NFPE bricks (17MPa nominal compressive strength) in class I mortar in loadbearing walls etc				
2	Half brick walls in beamfilling	m2	17	245.00	4 165.00
3	Half brick wall	m2	236	245.00	57 820.00
4	One brick wall	m2	1 190	430.00	511 700.00
	BRICKWORK SUNDRIES				
	Joint forming material in movement joints				
5	10mm Bitumen impregnated soft board built in vertically between / through brick skins	m	8	85.00	680.00
	Brick reinforcement and hoop iron ties				
6	75mm Wide reinforcement built in horizontally in superstructure	m	200	8.00	1 600.00
	Carried Forward			R	810 315.00

	Brought Forward			R	810 315.00
7	150mm Wide reinforcement built in horizontally in superstructure	m	1 501	15.00	22 515.00
	FIBRE-CEMENT WINDOW SILLS				
8	10 x 150mm Wide Internal window sills set flat and slightly projecting	m	55	90.00	4 950.00
	Galvanised hoop iron cramps, ties, etc				
	Carried Forward to Summary of Section 2			R	837 780.00

Section No. 2
Bill No.3 Masonry

HOUSE MALULEKE

Item No			Quantity	Rate	Amount
	SECTION 2				
	BILL NO.4				
	WATERPROOFING				
	Note:				
	Waterproofing of roofs, basements, etc shall be laid under a ten year guarantee. Waterproofing to roofs shall be laid to even falls to outlets etc with necessary ridges, hips and valleys. Descriptions of sheet or membrane waterproofing shall be deemed to include additional labour to turn-ups and turn-downs				
	DAMP PROOFING OF WALLS AND FLOORS				
	One layer of 375 micron type B black polyethylene sheeting dampproof course with 200mm laps				
1	In walls	m2	709	25.00	17 725.00
	One layer of 250 micron green polyethylene sheeting complying with SANS 952, Type C in widest practicable widths with all joints lapped and sealed with pressure sensitive tape jointing				
2	Under surface beds	m2	290	20.00	5 800.00
3	On Walls	m2	2	25.00	50.00
	WATERPROOFING TO ROOFS, BASEMENTS, ETC				
	4 mm "Derbigum SP4" fully bonded waterproofing:				
4	On concrete floors	m2	129	450.00	58 050.00
	Carried Forward			R	81 625.00

	Brought Forward			R	81 625.00
	30mm thick insulation boarding (Isoboard® or similar approved)				
5	On Concrete Slab	m2	215	550.00	118 250.00
	JOINT SEALANTS, ETC				
	Clear silicone sealant				
6	Between white glazed tiles and sanitary fittings/timber fittings(provisional)	m	1 960	18.00	35 280.00
	Carried Forward to Summary of Section 2			R	235 155.00

Section No. 2
Bill No.4 Waterproofing

HOUSE MALULEKE

Item No		Unit	Quantity	Rate	Amount
	SECTION NO. 2				
	BILL NO. 5				
	ROOF COVERINGS, ETC:				
	SUPPLEMENTARY PREAMBLES				
	Note:				
	The Tenderer is referred to the relevant Clause in the separate document "Model Preambles for Trades" (2008 Edition) and to the Supplementary Preambles which are incorporated hereunder.				
	Items, materials or methods to be used specified by trade names or catalogue numbers are only an indication of the quality required. Items, materials or methods of similar quality may be used with prior approval from the Principal Agent.				
	The Contractor is to submit to the consultant Architect a certificate signed by the Merchant, stating that the galvanized roof covering supplied complies with the required thickness specified				
	All holes through profiled metal sheeting are to be drilled				
	PROFILED METAL SHEETING AND ACCESSORIES				
	"COLOURED ROOF SHEETING OR SIMILAR AND APPROVED				
	IBR 686 CHROMADEK ROOF PITCH: 26°, ROOF OVERHANG: 700mm spelter galvanised sheet steel or similar to match existing profile fixed to timber/steel purlins or rails				
1	Roof covering with pitch not exceeding 26 degrees	m2	350	385.00	134 750.00
2	Ridge capping 450mm girth	m	193	195.00	37 635.00
3	Hip capping 450mm girth	m	45	195.00	8 775.00
4	Side wall flashing 450mm girth	m	18	195.00	3 510.00
	Carried Forward			R	184 670.00

	Brought Forward			R	184 670.00
5	Gable trim 250mm girth	m	10	195.00	1 950.00
6	Apex flashing 450mm girth	m	6	195.00	1 170.00
	ROOF AND WALL INSULATION				
	30mm thick insulation boarding (Isoboard® or similar approved) , laid tight over purlins and fixed concurrent with roof covering with 1.6mm double galvanised steel straining wires at 300mm centres and tied down top and bottom after tensioning with hoop iron ties, lay insulation with 100mm overlaps, all in accordance with manufacturers recommendations.				
7	Insulation laid taut over rafters (at approximately 600mm centres) and fixed concurrent with tiling battens, purlins, etc	m2	350	110.00	38 500.00
	Carried Forward to Summary of Section 2			R	226 290.00

Section No. 2
Bill No.5 Roof Coverings, etc

HOUSE MALULEKE

Item No		Unit	Quantity	Rate	Amount
	SECTION 2				
	BILL NO.6				
	CARPENTRY AND JOINERY				
	SUPPLEMENTARY PREAMBLES				
	Note:				
	1. The Tenderer is advised to refer to the Model Preambles and SABS 1200 before pricing this Bill				
	2. All boards, rails, frames, etc. shall include all associate mitres, trimming to size, temporary holding in position and fixing complete				
	3. All timber must be protected from rot attack by fungi and insects by having been treated in accordance with SABS 1200				
	FASCIAS AND BARGE BOARDS:				
	"Everite" medium density plain nutec-cement				
1	15 x 225mm Fascia or barge board countersunk screwed to support and Steel roof members (elsewhere measured) with one brass screw at maximum 750mm centres and jointed with and including standard aluminium half-round cover strips at all joints.	m	88	70.00	6 160.00
	DOORS, ETC				
	Solid Core door, Framed, Ledged and Braced with V-joint boarding, flush back				
2	Door overall size 813 x 2 032mm high	No	24	3 000.00	72 000.00
	Carried Forward			R	78 160.00

	Brought Forward			R	78 160.00
	ROLLER SHUTTER DOORS				
3	Custom made Motorised horizontal slated Timber Garage Door Size 2440x1981	No	1	3 000.00	3 000.00
4	Custom made Motorised horizontal slated Timber Garage Door Size 5200x1981	No	1	7 500.00	7 500.00
	SKIRTINGS				
	ROOFS ETC				
	Plate nailed timber roof truss construction				
5	Truss construction to double pitched roof with hipped or gable ends and 2100mm high extreme including wall plates, trusses, jack rafters, permanent bracing including 38 x 52mm purlins/battens at not exceeding 1500mm centres for IBR roofing sheets	m2	280	450.00	126 000.00
	Sawn softwood				
6	38 x 114 mm Wall plates	m	90	95.00	8 550.00
	Carried Forward to Summary of Section 2			R	223 210.00

Section No. 2
Bill No.6 Carpentry and Joinery

HOUSE MALULEKE

Item No		Unit	Quantity	Rate	Amount
	SECTION 2				
	BILL NO. 7				
	METALWORK				
	SUPPLEMENTARY PREAMBLES				
	Proprietary Products In Descriptions				
	Proprietary products shall be used as specified. Substitute products of similar quality and specification may only be used with prior approval by the Principal Agent				
	Referencing				
	Where items are given with type references, these references are to the drawings attached at the back of these Bills of Quantities.				
	PRESSED STEEL DOOR FRAMES				
	1.2mm Double rebated frames suitable for half brick walls				
1	Frame for door size 875 x 2085mm	No	24	1 000.00	24 000.00
	1,2mm Double Rebated Frames Suitable For A 220mm Thick Brick Wall Complete With Butts, Etc And Including Setting Up, Building In, Filling Back Of Frame With Cement Mortar, Etc				
2	Frame for door size 900 x 2085mm	No	1	1 200.00	1 200.00
3	Frame for double door size 5200 x 1981mm	No	1	1 300.00	1 300.00
	ALUMINIUM WINDOWS, ETC.				
	ALUMINIUM WINDOWS, ETC.				
	Carried Forward			R	26 500.00

	Brought Forward			R	26 500.00
	60mm Powder coated, bronze aluminium framing NKCASA casement type for 16mm combinations as supplied by HBS systems or equally approved and to be fixed as per manufacturer's specifications glazed with 8.38mm (Double Glazing) clear float safety glazing Including Ironmongery) Note: Final manufacturing dimensions to be obtained from on-site measurements. Windows				
4	W01 (Main Building), 3614 x 4372mm high overall, as per architects drawings	No	1	5 800.00	5 800.00
5	W02 (MB), 2000 x 4578mm high overall, as per architects drawings	No	2	5 000.00	10 000.00
6	W03 (MB), 3158 x 2000mm high overall, as per architects drawings	No	1	4 000.00	4 000.00
7	W04 (MB), 3280 x 1633mm high overall, as per architects drawings	No	1	4 000.00	4 000.00
8	W05 (MB), 450 x 2380mm high overall, as per architects drawings	No	2	2 800.00	5 600.00
9	W06 (MB), 814 x 2380mm high overall, as per architects drawings	No	1	3 200.00	3 200.00
10	W07 (MB), 531 x 2380mm high overall, as per architects drawings	No	2	3 000.00	6 000.00
11	W08 (MB), 900 x 2380mm high overall, as per architects drawings	No	2	3 300.00	6 600.00
12	W09 (MB), 1000 x 1200mm high overall, as per architects drawings	No	4	2 950.00	11 800.00
13	W10 (MB), 1400 x 1200mm high overall, as per architects drawings	No	8	3 000.00	24 000.00
14	W11 (MB), 1800 x 1800mm high overall, as per architects drawings	No	4	3 000.00	12 000.00
	Carried Forward			R	119 500.00

Section No. 2
Bill No.7 Metalwork

HOUSE MALULEKE

	Brought Forward			R	119 500.00
15	W12 (MB), 400 x 1200mm high overall, as per architects drawings	No	1	2 500.00	2 500.00
16	W13 (MB), 600 x 1100mm high overall, as per architects drawings	No	3	2 500.00	7 500.00
17	W14 (MB), 1700 x 600mm high overall, as per architects drawings	No	2	2 800.00	5 600.00
18	W15 (MB), 600 x 1800mm high overall, as per architects drawings	No	2	2 700.00	5 400.00
19	W16 (MB), 900 x 2125mm high overall, as per architects drawings	No	2	2 950.00	5 900.00
20	W17 (MB), 2644 x 1950mm high overall, as per architects drawings	No	2	3 200.00	6 400.00
21	W18 (MB), 705 x 2125mm high overall, as per architects drawings	No	2	2 800.00	5 600.00
22	W19 (MB), 814 x 2125mm high overall, as per architects drawings	No	1	2 800.00	2 800.00
23	W20 (MB), 1345 x 1870mm high overall, as per architects drawings	No	1	3 000.00	3 000.00
24	W21 (MB), 1220 x 1870mm high overall, as per architects drawings	No	1	3 000.00	3 000.00
25	W22 (MB), 5200 x 400mm high overall, as per architects drawings	No	1	3 000.00	3 000.00
26	W23 (MB), 2440 x 370mm high overall, as per architects drawings	No	1	3 000.00	3 000.00
27	W24 (MB), 4000 x 450mm high overall, as per architects drawings	No	1	2 800.00	2 800.00
	<u>Doors</u>				
28	D01, (Main Building) (MB) 1652 x 2541mm high overall, as per architects drawings	No	1	4 000.00	4 000.00
	Carried Forward			R	180 000.00

Section No. 2
Bill No.7 Metalwork

HOUSE MALULEKE

	Brought Forward			R	180 000.00
29	D03, (Main Building) (MB) 2700 x 2380mm high overall, as per architects drawings	No	18	6 500.00	117 000.00
30	D04, (Main Building) (MB) 900 x 2110mm high overall, as per architects drawings	No	3	3 800.00	11 400.00
31	D05, (Main Building) (MB) 2000 x 2380mm high overall,as per architects drawings	No	1	4 500.00	4 500.00
32	D06, (Main Building) (MB) 2700 x 2125mm high overall, as per architects drawings	No	1	6 500.00	6 500.00
33	D07, (Main Building) (MB) 2000 x 2125mm high overall,as per architects drawings	No	4	5 800.00	23 200.00
	Carried Forward to Summary of Section 2			R	342 600.00

Section No. 2
Bill No.7 Metalwork

HOUSE MALULEKE

Item No			Quantity	Rate	Amount
	SECTION 2				
	BILL NO.8				
	CEILINGS AND PARTITIONING				
	SUPPLEMENTARY PREAMBLES				
	The Tenderer is referred to the relevant Clause in the separate document "Model Preambles for Trades" (2008 Edition) and to the Supplementary Preambles which are incorporated hereunder.				
	Items, materials or methods to be used specified by trade names or catalogue numbers are only an indication of the quality required. Items, materials or methods of similar quality may be used with prior approval from the Principal Agent.				
	Descriptions:				
	Items described as "nailed" shall be deemed to be fixed with hardened steel nails or pins or shot pinned to brickwork or concrete				
	CEILINGS, ETC:				
	NAILED UP CEILINGS:				
	4mm "Everite Cladit" or other approved fibre cement board with and including pre-primed H-type pressed steel jointing strips				
1	Ceilings including 38 x 38mm sawn softwood brandering at 400mm centres in one direction in eaves soffits.	m2	330	140.00	46 200.00
	SUSPENDED CEILINGS				
	Carried Forward			R	46 200.00

	Brought Forward			R	46 200.00
	1200 x 600 x 12,5mm "Fissured Vinyl Clad Gypsum Ceilin Board" ceiling panels fitted in and including "Don T38" exp grid suspension system including main and cross tees, necessary hangers, grids, etc				
2	Suspended ceilings not exceeding 1m below timber trusse	m2	215	260.00	55 900.00
	Shadow line wall angle cornice to suspended ceilings				
3	25mm recessed wall angle plugged	m	170	110.00	18 700.00
	Carried Forward to Summary of Section 2			R	120 800.00

Section No. 2
Bill No.8 Ceilings and Partitioning

HOUSE MALULEKE

Item No		Unit	Quantity	Rate	Amount
	SECTION 2				
	BILL NO. 9				
	FLOOR COVERINGS, WALL LININGS, ETC.				
	SUPPLEMENTARY PREAMBLES				
	Fixing				
	Floor coverings, wall linings, etc. shall, where applicable, be fixed with adhesive as recommended by the manufacturers of the flooring, linings, etc				
	FLOOR COVERINGS				
	Timber Decking				
	Timber Decking				
1	On floors	m2	67	405.00	27 135.00
	Carried Forward to Summary of Section 2			R	27 135.00

Section No. 2
Bill No.9 Floor Covering

HOUSE MALULEKE

Item No		Unit	Quantity	Rate	Amount
	SECTION 2				
	BILL NO.10				
	IRONMONGERY				
	SUPPLEMENTARY PREAMBLES				
	Notes :				
	Unless otherwise stated herein, all items in this bill shall be deemed to fall into Work Group No. 132 for CPAP formula purposes				
	Finishes to ironmongery				
	HINGES, BOLTS, ETC.				
	"Union"				
1	"CZ80941" WC indicator bolt with keep fixed to timber	No	24	100.00	2 400.00
2	"8052-150NP" flush bolt with keep fixed to timber	No	24	100.00	2 400.00
	LOCKS				
	"Union"				
3	"CZ682-24SC/2261-76SC" or other equal and approved four lever lockset with striking plate fixed to metal	No	24	105.00	2 520.00
	HANDLES				
	"Dorma"				
4	"dks-ss-161" Stainless steel kickplate size 813 x 300mm fixed to timber	No	24	120.00	2 880.00
	"BATHROOM FITTINGS"				
	Carried Forward			R	10 200.00

	Brought Forward			R	10 200.00
	"Chairman Industries"				
5	20 mm Chromium plated shower curtain rail 1000 mm long with and including stop end brackets and fixing in position to walls	No	6	1 200.00	7 200.00
	Carried Forward to Summary of Section 2			R	17 400.00

Section No. 2
Bill No.9 Ironmongery

HOUSE MALULEKE

Item No		Unit	Quantity	Rate	Amount
	SECTION 2				
	BILL NO.11				
	PLASTERING				
	Note:				
	SCREEDS				
	Screeds on concrete				
1	25mm Thick on floors	m2	510	85.00	43 350.00
2	Average 50mm thick on shower floors to falls and currents	m2	2	100.00	200.00
	INTERNAL PLASTER				
	Cement plaster on brickwork				
3	On walls	m2	232	85.00	19 720.00
4	On narrow widths.	m2	140	135.00	18 900.00
	EXTERNAL PLASTER				
	Cement plaster on brickwork				
5	On walls	m2	2 182	85.00	185 470.00
	Carried Forward to Summary of Section 2			R	267 640.00

Section No. 2
Bill No.10 Plastering

HOUSE MALULEKE

Item No		Unit	Quantity	Rate	Amount
	SECTION 2				
	BILL NO.11				
	PLUMBING FITTINGS				
	Note:				
	RAINWATER DISPOSAL				
1	Allow the sum of R 25 000,00 (Twenty Five Thousand Rands) for the Supply and Installation of Rain water Disposal down pipes and gutters		Item		25 000.00
	THE FOLLOWING IN SANITARY FITTINGS, ETC				
2	Allow the amount of R 150000 (One Hundred and Fifty Thousand Thousand Rands Only) for sanitary fittings ,set up complete		Item		150 000.00
	Carried Forward to Summary of Section 2			R	175 000.00

Section No. 2
Bill No.11 Plumbing and Drainage

HOUSE MALULEKE

Item No		Unit	Quantity	Rate	Amount
	SECTION 2				
	BILL NO.12				
	TILING				
	Note:				
	WALL TILES				
	300 x 900 x 8mm Porcelain fixed with adhesive to plaster (plaster elsewhere) including flush pointed with tinted grout				
1	On walls	m2	24	550.00	13 200.00
2	In narrow widths	m2	2	550.00	1 100.00
	FLOOR TILES				
	600 x 600 x 9mm Thick porcelain tiles (PC Amount R350/m2) in matt finish, laid to approved pattern and fixed with adhesive to screed (screed elsewhere) including flush pointed with tinted grout				
3	On floors	m2	510	410.00	209 100.00
4	Skirting 100mm high	m	274	410.00	112 340.00
	ALUMINIUM AND PVC TRIMS, ETC.				
5	`Genesis ESA 150' natural anodised aluminium straight edge protector 12mm high at junction of differing floor finishes, plugged and screwed	m	31	85.00	2 635.00
	Aluminium corner protectors, stair nosings, expansion joint strips, etc				
6	Corner protectors	m	12	85.00	1 020.00
	Carried Forward to Summary of Section 2			R	339 395.00

Section No. 2
Bill No.12 Tiling

HOUSE MALULEKE

Item No		Unit	Quantity	Rate	Amount
	SECTION 2				
	BILL NO.13				
	PAINTWORK				
	SUPPLEMENTARY PREAMBLES				
	Note:				
	ON INTERNAL FLOATED PLASTER SURFACES				
	Prepare surfaces and remove all loose material, apply one coat 'Plascon Merit Plaster Primer' and two coats 'Plascon Velvaglo Polyurethane Enamel' paint internally				
1	On internal walls	m2	708	95.00	67 260.00
2	Ditto, in narrow width not exceeding 300 mm wide	m2	2	105.00	210.00
3	Ceilings and beams	m2	510	95.00	48 450.00
	ON EXTERNAL FLOATED PLASTER SURFACES				
	One coat alkali resistant primer and two coats premium quality polyurethane enamel paint				
4	Walls	m2	1 936	95.00	183 920.00
5	Ditto, in narrow width not exceeding 300 mm wide	m2	16	105.00	1 680.00
	ON FIBRE-CEMENT				
	Two finishing coats 'Plascon Polvin Super Acryllic PVA (EPL)' paint				
6	On Ceiling	m2	220	85.00	18 700.00
7	On fibre-cement fascia boards before fixing	m2	45	85.00	3 825.00
	PAINT ON WOOD				
	Carried Forward			R	324 045.00

	Brought Forward			R	324 045.00
	Three coats superior quality clear gloss varnish				
8	On general surfaces of doors	m2	91	85.00	7 735.00
9	On timber floors	m2	24	85.00	2 040.00
	ON FLUSH PLASTERED CEILINGS, COLUMNS ETC.				
	Universal under coat and two coats plascon acrylic - emulsion				
10	Ceilings, etc.	m2	510	105.00	53 550.00
	PAINT ON METAL				
	Spot priming defects in pre primed surfaces with zinc chromate primer and applying one undercoat and two coat high gloss enamel paint on steel				
11	On Security gates	m2	26	105.00	2 730.00
	Carried Forward to Summary of Section 2			R	390 100.00

Section No. 2
Bill No.13 Paintwork

HOUSE MALULEKE

SECTION SUMMARY - BUILDING WORKS

Bill No		Page No		Amount
1	Bill No.1 Earthwork	33		151 504.00
2	Bill No.2 Concrete, Formwork and Reinforcement	36		613 262.50
3	Bill No.3 Masonry	38		837 780.00
4	Bill No.4 Waterproofing	40		235 155.00
5	Bill No.5 Roof Coverings, etc	42		226 290.00
6	Bill No.6 Carpentry and Joinery	44		223 210.00
7	Bill No Metalwork	48		342 600.00
8	Bill No.8 Ceilings and Partitioning	50		120 800.00
9	Bill No.9 Floor Covering	51		27 135.00
10	Bill No.9 Ironmongery	53		17 400.00
11	Bill No.10 Plastering	54		267 640.00
12	Bill No.11 Plumbing and Drainage	55		175 000.00
13	Bill No.12 Tiling	56		339 395.00
14	Bill No.13 Paintwork	58		390 100.00
	Carried to Final Summary		R	3 967 271.50

Section No. 2

HOUSE MALULEKE

Item No		Quantity	Rate	Amount
	SECTION 3			
	BILL NO.1			
	PROVISIONAL SUMS			
	Note:			
	1. The following budgetary allowances are for work to be designed by the Architect, executed by the Contractor and measured and valued by the Quantity Surveyor in terms of Clause 28 of the Conditions of the Contract.			
	2. All Provisional Sums are nett and do not include a 5% cash discount to the Contractor.			
	3. Under no circumstances may any Provisional Sum be extended at an amount lower than the amount stated.			
	4. Unless specific percentage mark-ups for profit and attendance are indicated in the Rate column, the amount priced by the Contractor for profit and attendance against each Provisional Sum shall be deemed to be lump sum prices and shall not be adjusted unless the scope of the sub-contract varies significantly.			
	Electrical Works			
1	Provide the sum of R 100 000,00 (One Hundred and Fifty Thousand Rand Only) for Electrical Works	Item		100 000.00
2	Profit	2.50%	100 000.00	2 500.00
3	Allow for general attendance	2.50%	100 000.00	2 500.00
	Mechanical Works			
4	Provide the sum of R 50 000,00 (Fifty Thousand Rand) for Mechanical Works	Item		50 000.00
	Carried Forward		R	155 000.00

	Brought Forward		R	155 000.00
5	Profit	2.50%	50 000.00	1 250.00
6	Allow for general attendance	2.50%	50 000.00	1 250.00
	Swimming Pool			
7	Provide the sum of R 50 000 (Fifty Thousand Rand) for Swimming pool	Item		50 000.00
8	Profit	2.50%	50 000.00	1 250.00
9	Allow for general attendance	2.50%	50 000.00	1 250.00
	Wall Cladding			
10	Provide the sum of R 50 000 (Fifty Thousand Rand) for Wall Cladding	Item		50 000.00
11	Profit	2.50%	50 000.00	1 250.00
12	Allow for general attendance	2.50%	50 000.00	1 250.00
	Carried to Final Summary		R	262 500.00

Section No. 3
Provisional Sums

HOUSE MALULEKE

FINAL SUMMARY

Section No		Page No		Amount
1	Preliminaries	31		200 000.00
2	Building Works	59		3 967 271.50
3	PROVISIONAL SUMS	61		262 500.00
	Sub-total		R	4 429 771.50
	Allow a contingency amount of R80 000.00 (Eighty Thousand) to be used as directed by the Architect.		R	80 000.00
	VAT		R	676 465.73
	Sub-total		R	5 186 237.23
	Carried to Form of Tender		R	5 186 237.23

HOUSE MALULEKE