Aathiv builds and designs

	BUDGET
Budget designation	PROPOSED CONSTRUCTION OF RESIDENTIAL BUILDING (G+2)
Date	21/02/2026
Document number	AATHIV BUILDS

Abstract Sheet : PROPOSED CONSTRUCTION OF RESIDENTIAL BUILDING (G+2)					
Item no.	**Description**	**Quantity**	**Unit**	**Rate**	**Amount**
1	**PROPOSED RSIDENTIAL BUILDING**				
1.1	**FOUNDATION WORKS (UPTO FFL)**				
1.1.1	F-Earth work for Footing (Shalow Excavation)	6,035.750	Cft	11.00	66,393.25
1.1.2	F-Msand filling in Flooring - 10"	715.667	Cft	72.00	51,528.02
1.1.3	F-PCC 1:4:8 for FOOTING 4"	284.543	Cft	147.00	41,827.82
1.1.4	F-RCC M20 (1:1.5:3) for Footing	997.140	CFT	397.65	3,96,512.72
1.1.5	F-RCC M20 (1:1.5:3) COLUMN Upto E.B BOTTOM	59.040	CFT	1,384.60	81,746.78
1.1.6	F-Earth work for Earth beam (Manual excavation)	222.541	Cft	20.00	4,450.82
1.1.7	F-Refilling Excavated Earth In Foundation	4,210.000	Cft	4.00	16,840.00
1.1.8	F-Msand filling in Earth beam - 2"	74.328	Cft	72.00	5,351.62
1.1.9	F-PCC 1:4:8 for Earth beam -4"	146.877	Cft	147.00	21,590.92
1.1.10	F-RCC M20(1:1.5:3) Earth Beam	238.437	CFT	620.97	1,48,062.22
1.1.11	F-RCC M20 (1:1.5:3) COLUMN Upto FFL	46.126	CFT	1,384.60	63,866.06
1.1.12	F-RCC M20(1:1.5:3) Basement Belt	95.376	CFT	451.47	43,059.40
1.1.13	F-9" FLY ASH BRICK WORK (CM1:6) FOR BASEMENT	238.437	Cft	211.00	50,310.21
1.1.14	F-BASEMENT PLASTERING WITH BITUMEN COAT - 2C	1,434.480	Sft	45.00	64,551.60
1.1.15	F-Refilling Excavated earth in basement	2,047.000	Cft	4.00	8,188.00
1.1.16	F-Filling with Brought out Well gravel for necessary area	383.327	Cft	35.00	13,416.45
1.1.17	F-Msand filling in Flooring - 2"	201.854	Cft	72.00	14,533.49
1.1.18	F-PCC 1:4:8 for Floorings -4"	398.873	Cft	199.00	79,375.73
1.2	**STILT/GROUND FLOOR**				
1.2.1	**SUPER STRUCTURE RCC WORK**				
1.2.1.1	GF- RCC - M20 (1:1.5:3)For Column	161.439	Cft	1,385.00	2,23,593.01
1.2.1.2	GF- RCC - M20 (1:1.5:3)For Sill - 3"	22.993	Cft	451.00	10,369.84
1.2.1.3	GF- RCC - M20 (1:1.5:3)For Lintel	45.987	Cft	685.00	31,501.10
1.2.1.4	GF- RCC - M20 (1:1.5:3)For Kitchen Table top,Low roof,Loft and Sunshade	36.000	Sft	217.00	7,812.00
1.2.1.5	GF- RCC - M20 (1:1.5:3)For Staircase	152.375	Sft	420.00	63,997.50
1.2.1.6	GF- RCC - M20 Roof Beam using RMC	264.687	Cft	895.00	2,36,894.87
1.2.1.7	GF- RCC - M20 Roof slab using RMC	406.123	Cft	563.00	2,28,647.25
1.2.2	**MASONRY WORK**				
1.2.2.1	GF- 9" Brick work - Red brick with CM 1:6 Upto Roof level	583.825	Cft	267.00	1,55,881.28
1.2.2.2	GF- 4.5" Brick work - Red brick with CM 1:4 Upto Roof level	194.253	Sft	119.00	23,116.11
1.2.3	**PLASTREING WORK**				

Abstract Sheet : PROPOSED CONSTRUCTION OF RESIDENTIAL BUILDING (G+2)					
Item no.	**Description**	**Quantity**	**Unit**	**Rate**	**Amount**
1.2.3.1	GF-Celing Plastering - 12mm thik - 1:4	1,324.692	Sft	47.00	62,260.52
1.2.3.2	GF-Internal Plastering - 18mm thik - 1:5	1,619.000	Sft	44.00	71,236.00
1.2.3.3	GF-External Plastering - 18mm thik - 1:5	1,328.580	Sft	46.00	61,114.68
1.2.4	**GRILL WORKS**				
1.2.4.1	GF-Staircase SS Hand rail works	27.000	Rft	1,003.00	27,081.00
1.2.5	**DOOR WORKS**				
1.2.5.1	GF-Teak door for Main door	24.500	Sft	2,328.00	57,036.00
1.2.5.2	GF-Wood frame with flush door shutter for Bed room door	42.000	Sft	920.00	38,640.00
1.2.5.3	GF-UPVC door for Toilet	35.000	Sft	713.00	24,955.00
1.2.6	**JOINERY WORKS**				
1.2.6.1	GF-UPVC Winodw with safey grill	156.000	Sft	695.00	1,08,420.00
1.2.6.2	GF-UPVC Ventilator with excahust	4.000	Sft	600.00	2,400.00
1.2.7	**FLOORING WORKS:**				
1.2.7.1	GF- Staircase Italian marble	226.500	Sft	759.00	1,71,913.50
1.2.7.2	GF-Parking tile flooring for Portico	779.875	Sft	155.00	1,20,880.63
1.2.7.3	GF-Hall and Room flooring	181.417	Sft	155.00	28,119.64
1.2.7.4	GF-Toilet anti skid tile flooring	29.250	Sft	155.00	4,533.75
1.2.7.5	GF-Toilet full wall tile	202.500	Sft	150.00	30,375.00
1.2.8	**PAINTING WORKS:**				
1.2.8.1	GF-Inner celing (White wash - 2 coat, primer-1, Emultion-2)	1,324.000	Sft	21.00	27,804.00
1.2.8.2	GF-inner wall (Putty - 2 coat, Primer-1 coat, Emultion - 2 coat)	1,619.000	Sft	30.00	48,570.00
1.2.8.3	GF-Exterier wall (White wash - 2 coat, Primer-1 coat, Emultion - 2 coat)	1,328.000	Sft	31.00	41,168.00
1.2.8.4	GF-Grill Painting(Zinc.primer-2 + Enamal paint 2)	186.000	Sft	25.00	4,650.00
1.2.8.5	GF-Main door polish work painting	57.750	Sft	114.00	6,583.50
1.2.9	**ELECTRICAL & PLUMBING WORKS**				
1.2.9.1	GF-supply and fixing of Electrical Subcontract works	1,274.000	Sft	152.00	1,93,648.00
1.2.9.2	GF-supply and fixing of plumbing Subcontract works	1,274.000	Sft	210.00	2,67,540.00
1.3	**FIRST FLOOR**				
1.3.1	**SUPER STRUCTURE RCC WORK**				
1.3.1.1	FF- RCC - M20 (1:1.5:3)For Column	161.719	Cft	1,385.00	2,23,980.82
1.3.1.2	FF- RCC - M20 (1:1.5:3)For Sill - 3"	39.731	Cft	451.00	17,918.68
1.3.1.3	FF - RCC - M20 (1:1.5:3)For Lintel	79.464	Cft	685.00	54,432.84
1.3.1.4	GF- RCC - M20 (1:1.5:3)For Kitchen Table top,Low roof,Loft and Sunshade	178.000	Sft	217.00	38,626.00
1.3.1.5	FF - RCC - M20 (1:1.5:3)For Staircase	152.375	Sft	420.00	63,997.50
1.3.1.6	FF - RCC - M20 Roof Beam using RMC	264.687	Cft	895.00	2,36,894.87
1.3.1.7	FF - RCC - M20 Roof slab using RMC	428.792	Cft	563.00	2,41,409.90
1.3.2	**MASONRY WORK**				
1.3.2.1	FF- 9" Brick work - Red brick with CM 1:6 Upto Roof level	873.379	Cft	267.00	2,33,192.19
1.3.2.2	FF- 4.5" Brick work - Red brick with CM 1:4 Upto Roof level	447.590	Sft	119.00	53,263.21

Abstract Sheet : PROPOSED CONSTRUCTION OF RESIDENTIAL BUILDING (G+2)					
Item no.	**Description**	**Quantity**	**Unit**	**Rate**	**Amount**
1.3.3	**PLASTREING WORK**				
1.3.3.1	FF-Celing Plastering - 12mm thik - 1:4	1,314.115	Sft	47.00	61,763.41
1.3.3.2	FF-Internal Plastering - 18mm thik - 1:5	4,309.760	Sft	44.00	1,89,629.44
1.3.3.3	FF-External Plastering - 18mm thik - 1:5	1,500.000	Sft	46.00	69,000.00
1.3.4	**GRILL WORKS**				
1.3.4.1	FF-Staircase SS Hand rail works	27.000	Rft	1,003.00	27,081.00
1.3.4.2	FF- Balcony Grill Work	93.520	Sft	262.50	24,549.00
1.3.4.3	FF-SS Handrail with Glass	21.000	Rft	2,200.00	46,200.00
1.3.5	**DOOR WORKS**				
1.3.5.1	FF-Teak door for Main door	21.000	Sft	2,328.00	48,888.00
1.3.5.2	FF-Wood frame with flush door shutter for Bed room door	73.500	Sft	920.00	67,620.00
1.3.5.3	FF- UPVC Sliding Door	42.000	Sft	550.00	23,100.00
1.3.5.4	GF-UPVC door for Toilet	21.000	Sft	570.00	11,970.00
1.3.6	**JOINERY WORKS**				
1.3.6.1	FF-French UPVC Winodw with safey grill	144.000	Sft	1,725.00	2,48,400.00
1.3.6.2	FF-UPVC Winodw with safey grill	147.500	Sft	695.00	1,02,512.50
1.3.6.3	FF-UPVC Ventilator with excahust	4.000	Sft	600.00	2,400.00
1.3.7	**FLOORING WORKS:**				
1.3.7.1	FF-Staircase Italian marble	189.125	Sft	759.00	1,43,545.88
1.3.7.2	FF-Italian marble Flooring	882.442	Sft	759.00	6,69,773.48
1.3.7.3	FF-Toilet anti skid tile flooring	125.385	Sft	155.00	19,434.68
1.3.7.4	FF-Toilet full wall tile	176.280	Sft	150.00	26,442.00
1.3.7.5	FF-Kitchen above table top full wall tile	132.000	Sft	150.00	19,800.00
1.3.7.6	FF-Black Granite for Kitchen table top	91.500	Sft	259.00	23,698.50
1.3.7.7	FF-Kitchen fiber Sink Supply and fixing	1.000	Nos	5,600.00	5,600.00
1.3.7.8	FF- kitchen table top cudupah slab fixing with floor dimmy	114.375	Sft	150.00	17,156.25
1.3.8	**PAINTING WORKS:**				
1.3.8.1	GF-Inner celing (White wash - 2 coat, primer-1, Emultion-2)	1,314.000	Sft	21.00	27,594.00
1.3.8.2	GF-inner wall (Putty - 2 coat, Primer-1 coat, Emultion - 2 coat)	3,996.000	Sft	30.00	1,19,880.00
1.3.8.3	GF-Exterier wall (White wash - 2 coat, Primer-1 coat, Emultion - 2 coat)	1,500.000	Sft	31.00	46,500.00
1.3.8.4	GF-Grill Painting(Zinc.primer-2 + Enamal paint 2)	528.000	Sft	25.00	13,200.00
1.3.8.5	FF-Main door polish work painting	57.750	Sft	114.00	6,583.50
1.3.9	**ELECTRICAL & PLUMBING WORKS**				
1.3.9.1	FF-supply and fixing of Electrical Subcontract works	1,274.000	Sft	152.00	1,93,648.00
1.3.9.2	FF-supply and fixing of plumbing Subcontract works	1,274.000	Sft	210.00	2,67,540.00
1.4	**SECOND FLOOR**				
1.4.1	**SUPER STRUCTURE RCC WORK**				
1.4.1.1	SF - RCC - M20 (1:1.5:3)For Column	147.656	Cft	1,385.00	2,04,503.56
1.4.1.2	SF - RCC - M20 (1:1.5:3)For Sill - 3"	43.779	Cft	451.00	19,744.33
1.4.1.3	SF - RCC - M20 (1:1.5:3)For Lintel	87.554	Cft	685.00	59,974.49

Abstract Sheet : PROPOSED CONSTRUCTION OF RESIDENTIAL BUILDING (G+2)					
Item no.	**Description**	**Quantity**	**Unit**	**Rate**	**Amount**
1.4.1.4	GF- RCC - M20 (1:1.5:3)For Kitchen Table top,Low roof,Loft and Sunshade	122.000	Sft	217.00	26,474.00
1.4.1.5	SF - RCC - M20 (1:1.5:3)For Staircase	152.375	Sft	420.00	63,997.50
1.4.1.6	SF - RCC - M20 Roof Beam using RMC	264.687	Cft	895.00	2,36,894.87
1.4.1.7	SF - RCC - M20 Roof slab using RMC	406.123	Cft	563.00	2,28,647.25
1.4.2	**MASONRY WORK**				
1.4.2.1	SF - 9" Brick work - Red brick with CM 1:6 Upto Roof level	847.430	Cft	267.00	2,26,263.81
1.4.2.2	SF - 4.5" Brick work - Red brick with CM 1:4 Upto Roof level	828.890	Sft	119.00	98,637.91
1.4.3	**PLASTREING WORK**				
1.4.3.1	SF - Celing Plastering - 12mm thik - 1:4	1,340.355	Sft	47.00	62,996.69
1.4.3.2	SF - Internal Plastering - 18mm thik - 1:5	4,579.100	Sft	44.00	2,01,480.40
1.4.3.3	SF - External Plastering - 18mm thik - 1:5	1,500.000	Sft	46.00	69,000.00
1.4.4	**GRILL WORKS**				
1.4.4.1	SF - Staircase SS Hand rail works	27.000	Rft	1,003.00	27,081.00
1.4.4.2	SF-SS Handrail with Glass	33.000	Rft	2,200.00	72,600.00
1.4.4.3	SF- Balcony Grill Work	62.000	Sft	262.50	16,275.00
1.4.5	**DOOR WORKS**				
1.4.5.1	SF - Wood frame with flush door shutter for Bed room door	84.000	Sft	920.00	77,280.00
1.4.5.2	SF- UPVC Sliding Door	17.500	Sft	550.00	9,625.00
1.4.5.3	GF-UPVC door for Toilet	105.000	Sft	570.00	59,850.00
1.4.6	**JOINERY WORKS**				
1.4.6.1	SF-UPVC Winodw with safey grill	129.000	Sft	695.00	89,655.00
1.4.6.2	SF-UPVC Ventilator with excahust	12.000	Sft	600.00	7,200.00
1.4.7	**FLOORING WORKS:**				
1.4.7.1	SF-Lether finished granite Flooring	16.125	Sft	275.00	4,434.38
1.4.7.2	SF-Hall and Room flooring	744.146	Sft	155.00	1,15,342.63
1.4.7.3	SF-Anti skid tile flooring	235.828	Sft	155.00	36,553.34
1.4.7.4	SF-Toilet full wall tile	565.560	Sft	150.00	84,834.00
1.4.8	**PAINTING WORKS:**				
1.4.8.1	GF-Inner celing (White wash - 2 coat, primer-1, Emultion-2)	1,340.000	Sft	21.00	28,140.00
1.4.8.2	GF-inner wall (Putty - 2 coat, Primer-1 coat, Emultion - 2 coat)	4,610.000	Sft	30.00	1,38,300.00
1.4.8.3	GF-Exterier wall (White wash - 2 coat, Primer-1 coat, Emultion - 2 coat)	1,500.000	Sft	31.00	46,500.00
1.4.8.4	GF-Grill Painting(Zinc.primer-2 + Enamal paint 2)	282.000	Sft	25.00	7,050.00
1.4.9	**ELECTRICAL & PLUMBING WORKS**				
1.4.9.1	SF-supply and fixing of Electrical Subcontract works	1,274.000	Sft	152.00	1,93,648.00
1.4.9.2	SF-supply and fixing of plumbing Subcontract works	1,274.000	Sft	210.00	2,67,540.00
1.5	**THIRED/TERRAES FLOOR**				
1.5.1	**SUPER STRUCTURE RCC WORK**				
1.5.1.1	TRF- RCC - M20 (1:1.5:3)For Column	46.126	Cft	1,385.00	63,884.51
1.5.1.2	TRF- RCC - M20 (1:1.5:3)For Lintel - 6"	27.377	Cft	685.00	18,753.25

Abstract Sheet : PROPOSED CONSTRUCTION OF RESIDENTIAL BUILDING (G+2)					
Item no.	**Description**	**Quantity**	**Unit**	**Rate**	**Amount**
1.5.1.3	TRF- RCC M20 (1:1.5:3) For parapet coping concrete	37.502	Cft	464.00	17,400.93
1.5.1.4	GF- RCC - M20 (1:1.5:3)For Kitchen Table top,Low roof,Loft and Sunshade	32.000	Sft	217.00	6,944.00
1.5.1.5	TRF - RCC - M20 Roof Beam using RMC	82.127	Cft	895.00	73,503.67
1.5.1.6	TRF- RCC - M20 Roof slab using RMC	180.759	Cft	563.00	1,01,767.32
1.5.2	**MASONRY WORK**				
1.5.2.1	TRF- 9" Brick work - Red brick with CM 1:6 Upto Roof level	626.635	Cft	267.00	1,67,311.54
1.5.3	**PLASTREING WORK**				
1.5.3.1	TRF-Celing Plastering - 12mm thik - 1:4	379.910	Sft	47.00	17,855.77
1.5.3.2	TRF-Internal Plastering - 18mm thik - 1:5	805.350	Sft	44.00	35,435.40
1.5.3.3	TRF-External Plastering - 18mm thik - 1:5	1,562.250	Sft	46.00	71,863.50
1.5.4	**JOINERY WORKS**				
1.5.4.1	TRF-UPVC Winodw with safey grill	118.500	Sft	695.00	82,357.50
1.5.4.2	TRF- UPVC Sliding Door	35.000	Sft	550.00	19,250.00
1.5.5	**GRILL WORKS**				
1.5.5.1	TRF-Grill Door	21.000	Sft	425.00	8,925.00
1.5.6	**PAINTING WORKS**				
1.5.6.1	GF-Inner celing (White wash - 2 coat, Primer-1 coat, Emultion - 2 coat)	380.000	Sft	21.00	7,980.00
1.5.6.2	GF-inner wall (Putty - 2 coat, Primer-1 coat, Emultion - 2 coat)	844.000	Sft	30.00	25,320.00
1.5.6.3	TRF-Exterier wall (White wash - 2 coat, Primer-1 coat, Emultion - 2 coat)	1,562.000	Sft	31.00	48,422.00
1.5.6.4	TRF-Wood /Grill painting (Primer-1 + stn.enamal-2)	160.500	Sft	26.00	4,173.00
1.5.7	**ELECTRICAL & PLUMBING WORKS**				
1.5.7.1	TRF-supply and fixing of Electrical Subcontract works	300.875	Sft	100.00	30,087.50
1.5.8	**WEATHERING COURSE WORKS**				
1.5.8.1	TRF-Screed concrete with power trawel finishing for wethering floor	302.188	Cft	144.00	43,515.07
1.5.8.2	TRF-Water proof for Terrace flooring	1,208.750	Sft	17.00	20,548.75
1.5.8.3	TRF-Cool Roof tile flooring for Terrace	1,208.750	Sft	155.00	1,87,356.25
1.5.8.4	GF-1500 litr Capacity Sintex Tank	4,000.000	liter	6.00	24,000.00
2	**ADDITIONAL WORKS**				
2.1	SUMP - 10000 LIT	10,000.000	LIT	20.00	2,00,000.00
2.2	Bio septic tank	1,000.000	Lit	50.00	50,000.00
2.3	Soak pit	3.000	nos	19,950.00	59,850.00
2.4	COMPOUND WALL	60.000	RFT	2,700.00	1,62,000.00
2.5	Main Gate	48.000	Sft	1,700.00	81,600.00
2.6	Bathroom shower cubicle	3.000	Ls	35,000.00	1,05,000.00
2.7	Elevation and Fabrication	1.000	Ls	4,00,000.00	4,00,000.00
3	**PMC FEE**				
3.1	PMC Consusult Fee	1.000	LS	0,00,000.00	20,00,000.00
		mount without taxes :		**INR**	**1,41,55,201.06**

Amount in words : Fourteen million one hundred fifty-five thousand two hundred one point six