Aathiv builds and designs

Report -02 -FLOORWISE MATERIAL SUMMARY

ID : **VC-BOQ-122-01**

Designation : **PROPOSED CONSTRUCTION OF RESIDENTIAL BUILDING (G+2)**

DESCRIPTION	UNIT	TOTAL QTY	RATE	AMOUNT (Rs)	TOTAL AMOUNT
PROPOSED RSIDENTIAL BUILDING					
FOUNDATION WORKS (UPTO FFL)					
CEMENT	BAG	418.374	335.00	1,40,155.16	
PLASTICIZER	KG	6.066	80.00	485.27	
3/4" (20MM) AGGREGATE	Cft	1,923.329	45.00	86,549.81	
M SAND (BLACK)	Cft	2,162.451	55.00	1,18,934.82	
P SAND (PLASTER)	Cft	153.920	65.00	10,004.78	
Well Gravel	Cft	479.159	23.00	11,020.65	
FLYASH BRICK (9" X 3" X 4")	NO	3,338.118	8.00	26,704.94	
TMT STEEL FE 500	KG	3,376.728	80.00	2,70,138.20	
BINDING WIRE	KG	101.302	100.00	10,130.18	
ADMIXTURE	KG	85.271	80.00	6,821.70	
WATERPROOFING CHEMICAL For Basement	Ltr	4.160	150.00	624.00	
Bitumen waterproofing Paint	Lit	38.301	0.00	0.00	
COVER BLOCK	NO	713.042	2.00	1,426.08	
LDPE SHEET	Sqft	1,208.705	2.00	2,417.41	
Providing and Applying Antitermite Treatment	Sqft	1,208.705	12.00	14,504.46	
S/c- Footing/raft Shuttering material Cost	Sft	997.140	15.00	14,957.10	
S/c- Column Shuttering material Cost	Sft	473.247	20.00	9,464.94	
S/c- Earth/Plinth beam Shuttering material Cost	Sft	596.092	20.00	11,921.85	
S/c- DPC/Sill/Coping Shuttering material Cost	Sft	238.440	15.00	3,576.60	
L/C Earth work Excavation upto 5' to 10' depth	Cft	222.541	20.00	4,450.82	
L/C for Msand / Quary dust filling	Cft	991.849	11.00	10,910.34	
L/C Earth Refilling with leveling & consolidation	Cft	6,640.327	3.00	19,920.98	
Labour charges for laying LDPE sheet	Sqft	1,208.705	3.00	3,626.11	
L/C for laying concrete for P.C.C	Cft	830.293	35.00	29,060.26	
L/C for laying concrete for Footing	Cft	997.140	40.00	39,885.60	
L/C for laying concrete for Column	Cft	105.166	60.00	6,309.96	
L/c for laying concrete for Earth beam	Cft	238.437	45.00	10,729.67	
L/c for laying concrete for Basement belt	Cft	95.376	50.00	4,768.80	
L/C for reinforcement work	KG	3,376.728	25.00	84,418.19	
L/c- Footing/raft Shuttering	Sft	997.140	20.00	19,942.80	
L/c- Column Shuttering	Sft	473.247	17.00	8,045.20	
L/c- Earth/Plinth beam Shuttering	Sft	596.092	20.00	11,921.85	
L/c- DPC/Sill/Coping Shuttering	Sft	238.440	20.00	4,768.80	
L/c for 9" brick masonry	Cft	238.437	50.00	11,921.85	
L/c for external plaster	Sft	1,434.480	25.00	35,862.00	

DESCRIPTION	UNIT	TOTAL QTY	RATE	AMOUNT (Rs)	TOTAL AMOUNT
L/c for Bitumen waterproofing Painting work - 1 coat	Sft	2,868.960	2.00	5,737.92	
OH/C CURING WORK	LS	3,939.329	3.00	11,817.99	
OH/C SUNDRISE & TOOLS	LS	23,753.462	1.00	23,753.46	
OH/C CONSUMABLES	LS	3,607.155	2.00	7,214.31	
Rental charges of Vibrator for Concreting work	N/day	4.739	500.00	2,369.55	
Rental charges of Concrete mixer for Concreting work	N/day	7.479	2,500.00	18,697.75	
Rental charges of Earthwork Machinery	hr	40.440	1,300.00	52,571.35	
Rentel charges for Earth rammer for Compaction	N/day	0.383	2,400.00	919.92	**11,69,463.43**
STILT/GROUND FLOOR					
SUPER STRUCTURE RCC WORK					
CEMENT	BAG	64.916	335.00	21,746.99	
3/4" (20MM) AGGREGATE	Cft	243.397	45.00	10,952.85	
M SAND (BLACK)	Cft	121.698	55.00	6,693.41	
READYMIX CONCRETE M 20 GRADE	Cft	670.810	160.00	1,07,329.60	
TMT STEEL FE 500	KG	4,247.046	80.00	3,39,763.68	
BINDING WIRE	KG	127.411	100.00	12,741.14	
ADMIXTURE	KG	19.204	80.00	1,536.33	
COVER BLOCK	NO	1,061.762	2.00	2,123.52	
S/c- Column Shuttering material Cost	Sft	726.476	20.00	14,529.51	
S/c- DPC/Sill/Coping Shuttering material Cost	Sft	57.483	15.00	862.24	
S/c- Lintel Shuttering material Cost	Sft	114.968	25.00	2,874.19	
S/c- Loft / sunshade /kitchen table Shuttering material Cost	Sft	36.000	25.00	900.00	
S/c- Staircase Shuttering material Cost	Sft	228.563	50.00	11,428.13	
S/c- Roof beam Shuttering material Cost	Sft	899.936	30.00	26,998.07	
S/c- Roof Slab Shuttering material Cost	Sft	990.534	20.00	19,810.68	
L/C for laying concrete for Column	Cft	161.439	60.00	9,686.34	
L/c for laying concrete for Staircase	Cft	62.474	50.00	3,123.69	
L/c for laying concrete for Lintel	Cft	81.987	45.00	3,689.42	
L/c for laying concrete for Sill	Cft	22.993	45.00	1,034.69	
L/C for RMC Concrete laying using Pump	Cft	670.810	15.00	10,062.15	
L/C for reinforcement work	KG	4,247.046	25.00	1,06,176.15	
L/c- Column Shuttering	Sft	726.476	17.00	12,350.08	
L/c- Loft / sunshade /kitchen table Shuttering	Sft	36.000	23.00	828.00	
L/c- Staircase Shuttering	Sft	228.563	60.00	13,713.75	
L/c- Lintel Shuttering	Sft	114.968	25.00	2,874.19	
Labour charges for shuttering of Sill	Sft	57.483	0.00	0.00	
L/c- Roof Slab Shuttering	Sft	990.534	25.00	24,763.35	
L/c- Roof Beam Shuttering	Sft	899.936	17.00	15,298.91	
CONCRETE PUMP	Cft	670.810	5.00	3,354.05	
OH/C CURING WORK	LS	1,241.979	3.00	3,725.94	
OH/C SUNDRISE & TOOLS	LS	1,403.418	1.00	1,403.42	
OH/C CONSUMABLES	LS	1,403.418	2.00	2,806.84	
OH/C Lead and Lift	LS	670.810	5.00	3,354.05	

DESCRIPTION	UNIT	TOTAL QTY	RATE	AMOUNT (Rs)	TOTAL AMOUNT
Rental charges of Vibrator for Concreting work	N/day	3.216	500.00	1,608.10	
Rental charges of Concrete mixer for Concreting work	N/day	1.002	2,500.00	2,506.25	**8,02,649.71**
MASONRY WORK					
CEMENT	BAG	34.925	335.00	11,699.71	
M SAND (BLACK)	Cft	295.075	55.00	16,229.14	
RED BRICK (9" X 3" X 4")	NO	9,193.378	12.00	1,10,320.54	
L/c for 9" brick masonry	Cft	583.825	50.00	29,191.25	
L/c for 4.5" brick masonry	Sft	194.253	35.00	6,798.86	
OH/C CURING WORK	LS	778.078	3.00	2,334.23	
OH/C SUNDRISE & TOOLS	LS	778.078	1.00	778.08	
OH/C CONSUMABLES	LS	778.078	2.00	1,556.16	**1,78,907.97**
PLASTREING WORK					
CEMENT	BAG	60.431	335.00	20,244.42	
P SAND (PLASTER)	Cft	430.596	65.00	27,988.75	
L/c for Internal ceiling plaster	Sft	1,324.692	25.00	33,117.30	
L/c for Internal Wall plaster	Sft	1,619.000	23.00	37,237.00	
L/c for external plaster	Sft	1,328.580	25.00	33,214.50	
L/c for pointing for plastering work	Sft	1,324.692	3.00	3,974.08	
OH/C CURING WORK	LS	4,272.272	3.00	12,816.82	
OH/C SUNDRISE & TOOLS	LS	4,272.272	1.00	4,272.27	
OH/C CONSUMABLES	LS	4,272.272	2.00	8,544.54	
Providing and fixing of Scaffolding Cost	Sft	4,272.272	3.00	12,816.82	**1,94,226.50**
GRILL WORKS					
Providing & fabricating work for SS Hand Railing	Rft	27.000	1,000.00	27,000.00	
OH/C SUNDRISE & TOOLS	LS	27.000	1.00	27.00	
OH/C CONSUMABLES	LS	27.000	2.00	54.00	**27,081.00**
DOOR WORKS					
Teak Wood Door Frame	Cft	3.273	3,500.00	11,456.20	
Teak Door Shutter	Cft	4.091	3,500.00	14,320.25	
Wood Door/window Frame (Padauh, Neam, Vengai)	Cft	2.806	2,000.00	5,611.20	
Redymade Flush Door Shutter	Sqft	42.000	285.00	11,970.00	
Door lense	Nos	1.166	350.00	408.17	
6" Hinges	Nos	18.970	500.00	9,484.85	
8" Handle Front	Nos	3.266	2,500.00	8,165.50	
6" Handle Back	Nos	3.266	1,000.00	3,266.20	
Main door Lock	Nos	1.166	12,000.00	13,994.40	
8" Tower bolt	Nos	3.266	750.00	2,449.65	
Door stoper	Nos	3.266	350.00	1,143.17	
Frame Clamps	Nos	18.970	100.00	1,896.97	
Nails and other consumables for Wooderen works	Ls	3.266	1,000.00	3,266.20	
S&F WPC Door Frame with shutter	Sft	43.750	570.00	24,937.50	
L/c For Woodern frame fixing and paking (Door, Window)	Sft	66.500	50.00	3,325.00	

Aathiv builds and designs

DESCRIPTION	UNIT	TOTAL QTY	RATE	AMOUNT (Rs)	TOTAL AMOUNT
L/c For Woodern Shutter and fitting fixing carpentry works	Sqft	24.500	200.00	4,900.00	**1,20,595.26**
JOINERY WORKS					
Supply & Fixing of UPVC Sliding window	Sft	156.000	470.00	73,320.00	
Supply & Fixing of UPVC Ventilator with Louver and exhaust	Sft	4.000	600.00	2,400.00	
Providing & fabricating and fixing work for M.S. Grill	Kg	234.000	150.00	35,100.00	**1,10,820.00**
FLOORING WORKS					
CEMENT	BAG	45.822	335.00	15,350.47	
M SAND (BLACK)	Cft	238.202	55.00	13,101.12	
Jiont grouting filler for Grainte and tile works	KG	30.175	45.00	1,357.88	
Parking / Portico Cement Tile	Sft	857.862	100.00	85,786.25	
VITRIFIED TILE 12" X 12"	Sft	32.175	100.00	3,217.50	
VITRIFIED TILE 24" X 24"	Sft	199.559	100.00	19,955.87	
VITRIFIED WALL TILE	Sft	222.750	100.00	22,275.00	
MARBLE ITALIAN	SQFT	249.150	600.00	1,49,490.00	
L/c for Step Granite laying Work	Sqft	249.150	40.00	9,966.00	
L/c for Granite Full Nosing work	Rft	90.600	70.00	6,342.00	
L/c for Pointing and Clening in flooring surface	Sft	1,442.192	3.00	4,326.58	
L/c for vertified tile laying work	Sft	210.667	20.00	4,213.34	
L/c Portico tile Laying	Sft	779.875	20.00	15,597.50	
L/c Wall Tile Laying	Sft	202.500	20.00	4,050.00	
OH/C SUNDRISE & TOOLS	LS	1,193.042	1.00	1,193.04	**3,56,222.55**
PAINTING WORKS					
White cement	Kg	145.860	17.00	2,479.62	
Interior Primer	Ltr	25.015	120.00	3,001.86	
Exterior Primer	Ltr	18.326	200.00	3,665.28	
Interior Emultion	Ltr	53.857	500.00	26,928.45	
Exterior Emultion	Ltr	32.403	600.00	19,441.92	
Interior wall putty	kg	161.900	25.00	4,047.50	
Zinchromate primer	Lit	1.321	120.00	158.47	
Enamal Paint	Lit	2.660	300.00	797.94	
Melamine teak wood Polish	Lit	1.444	150.00	216.57	
4" Brush	NO	4.698	250.00	1,174.53	
9" Roller	NO	0.971	260.00	252.56	
Crack putty plate	NO	4.271	25.00	106.77	
6" Putty plate	NO	1.281	85.00	108.91	
8" Putty plate	NO	0.486	100.00	48.57	
12" Putty plate	NO	0.486	130.00	63.14	
18 no Flat brush	NO	0.093	100.00	9.30	
20 no Flat brush	NO	0.093	120.00	11.16	
POLISH PAPER - Emerry sheet - 100	NO	0.930	20.00	18.60	
POLISH PAPER - Emerry sheet - 180	NO	8.095	20.00	161.90	
THINNER	LTR	1.321	90.00	118.85	
Waste cloth	Kg	4.791	80.00	383.29	
POP	Kg	2.947	25.00	73.68	

Aathiv builds and designs

DESCRIPTION	UNIT	TOTAL QTY	RATE	AMOUNT (Rs)	TOTAL AMOUNT
Labour charges for Celing Surface Cleaning work	Sft	1,324.000	1.00	1,324.00	
Labour charges for Wall Surface Cleaning work	Sft	2,947.000	1.00	2,947.00	
L/c for Ext.paint White cement per coat	Sft	2,656.000	2.15	5,710.40	
L/c for Ext.paint Wall primer per coat	Sft	1,328.000	2.15	2,855.20	
L/c for Ext.paint Emultion per coat	Sft	2,656.000	2.20	5,843.20	
L/c for Int.paint White cement per coat	Sft	1,324.000	2.10	2,780.40	
L/c for In.Paint Celing primer per coat	Sft	1,324.000	2.10	2,780.40	
L/c for Int.paint Wall primer per coat	Sft	1,619.000	2.10	3,399.90	
L/c for In.Paint Zink primer per coat	Sft	186.000	5.25	976.50	
L/c for In.Paint Celing Emultion per coat	Sft	2,648.000	2.30	6,090.40	
L/c for In.Paint Wall Emultion per coat	Sft	3,238.000	2.30	7,447.40	
L/c for In.Paint Wall putty per coat	Sft	3,238.000	2.50	8,095.00	
L/c for In.Paint Enamal paint (Grill two side) per coat	Sft	372.000	7.00	2,604.00	
L/c for Pol. Melamine POLISH FINSIH	Sft	57.750	110.00	6,352.50	
OH/C SUNDRISE & TOOLS	LS	1,619.000	1.00	1,619.00	
Providing and fixing of Scaffolding Cost	Sft	1,619.000	3.00	4,857.00	**1,28,951.17**
ELECTRICAL & PLUMBING WORKS					
25mm HMS PVC Conduit Pipe (Slab & Walls)	Rft	573.300	25.00	14,332.50	
20mm HMS PVC Conduit Pipe (Point Wiring)	Rft	254.800	21.00	5,350.80	
1.0 sq.mm Wire (Light/Fan Points - Green/ Red/Black)	Coils	10.192	2,300.00	23,441.60	
1.5 sq.mm Wire (Primary Circuits/Sockets)	Coils	5.096	3,000.00	15,288.00	
2.5 sq.mm Wire (Power Points/Geyser)	Coils	3.822	5,200.00	19,874.40	
4.0 sq.mm Wire (Main Line/AC)	Coils	2.548	7,500.00	19,110.00	
12 Module Metal Box (Main Switch Board)	Nos	3.822	250.00	955.50	
8 Module Metal Box (Bedrooms/Kitchen)	Nos	5.096	180.00	917.28	
6 Module Metal Box (Utility/AC)	Nos	5.096	150.00	764.40	
3/2/1 Module Metal Box (Single points/ Calling bell)	Nos	15.288	80.00	1,223.04	
6A One-way Switch	Nos	57.330	65.00	3,726.45	
6A 3-pin Socket	Nos	22.932	120.00	2,751.84	
16A/25A Power Socket with Switch	Nos	7.644	350.00	2,675.40	
Fan Regulator (2-module step type)	Nos	6.370	250.00	1,592.50	
8-12 Way Double Door DB Box	Nos	1.274	8,000.00	10,192.00	
63A DP RCCB (30mA for safety)	Nos	1.274	2,200.00	2,802.80	
63A FP Isolator	Nos	1.274	950.00	1,210.30	
6A/10A/16A/25A Single Pole MCB	Nos	1.274	350.00	445.90	
PVC Junction Boxes (Deep/Surface)	Nos	57.330	25.00	1,433.25	
PVC Bend (25mm/20mm)	Nos	76.440	15.00	1,146.60	
Solvent Cement (100ml)	Nos	2.548	120.00	305.76	
Insulation Tape (Assorted colors)	Nos	12.740	30.00	382.20	
Flexible Pipe (for drops)	Rft	38.220	12.00	458.64	
Plumbing Work Subcontract Labour	Sft	1,274.000	50.00	63,700.00	
Plumbing Work Subcontract Material	Sft	1,274.000	160.00	2,03,840.00	

DESCRIPTION	UNIT	TOTAL QTY	RATE	AMOUNT (Rs)	TOTAL AMOUNT
L/C for Ele - Roof slab conduiting pipe laying works	Nos	6.370	1,000.00	6,370.00	
L/C for Ele - Wall Pipe and Mettal box fixing works	Nos	16.944	1,000.00	16,944.20	
L/C for Ele - Wiring works	Nos	12.740	1,000.00	12,740.00	
L/C for Ele - Swtiches & socket assamble and fixing works	Nos	10.574	1,000.00	10,574.20	
L/C for Ele - DB Board fixing & Wiring works	Nos	4.204	1,000.00	4,204.20	
L/C for Ele - Service connection and Testing works	Nos	4.204	1,000.00	4,204.20	
L/C for Ele - Light, fan, motor and orther fitting works	Nos	4.204	1,000.00	4,204.20	
L/C for Ele - other miscellaneous works	Nos	4.204	1,000.00	4,204.20	**4,61,366.36**
FIRST FLOOR					
SUPER STRUCTURE RCC WORK					
CEMENT	BAG	83.412	335.00	27,943.19	
3/4" (20MM) AGGREGATE	Cft	312.733	45.00	14,072.98	
M SAND (BLACK)	Cft	156.366	55.00	8,600.15	
READYMIX CONCRETE M 20 GRADE	Cft	693.479	160.00	1,10,956.64	
TMT STEEL FE 500	KG	4,556.165	80.00	3,64,493.24	
BINDING WIRE	KG	136.685	100.00	13,668.49	
ADMIXTURE	KG	24.673	80.00	1,973.86	
COVER BLOCK	NO	1,139.041	2.00	2,278.08	
S/c- Column Shuttering material Cost	Sft	727.736	20.00	14,554.71	
S/c- DPC/Sill/Coping Shuttering material Cost	Sft	99.328	15.00	1,489.91	
S/c- Lintel Shuttering material Cost	Sft	198.660	25.00	4,966.50	
S/c- Loft / sunshade /kitchen table Shuttering material Cost	Sft	178.000	25.00	4,450.00	
S/c- Staircase Shuttering material Cost	Sft	228.563	50.00	11,428.13	
S/c- Roof beam Shuttering material Cost	Sft	899.936	30.00	26,998.07	
S/c- Roof Slab Shuttering material Cost	Sft	1,045.824	20.00	20,916.47	
L/C for laying concrete for Column	Cft	161.719	60.00	9,703.14	
L/c for laying concrete for Staircase	Cft	62.474	50.00	3,123.69	
L/c for laying concrete for Lintel	Cft	257.464	45.00	11,585.88	
L/c for laying concrete for Sill	Cft	39.731	45.00	1,787.90	
L/C for RMC Concrete laying using Pump	Cft	693.479	15.00	10,402.19	
L/C for reinforcement work	KG	4,556.165	25.00	1,13,904.14	
L/c- Column Shuttering	Sft	727.736	17.00	12,371.50	
L/c- Loft / sunshade /kitchen table Shuttering	Sft	178.000	23.00	4,094.00	
L/c- Staircase Shuttering	Sft	228.563	60.00	13,713.75	
L/c- Lintel Shuttering	Sft	198.660	25.00	4,966.50	
Labour charges for shuttering of Sill	Sft	99.328	0.00	0.00	
L/c- Roof Slab Shuttering	Sft	1,045.824	25.00	26,145.59	
L/c- Roof Beam Shuttering	Sft	899.936	17.00	15,298.91	
CONCRETE PUMP	Cft	693.479	5.00	3,467.40	
OH/C CURING WORK	LS	1,457.143	3.00	4,371.43	
OH/C SUNDRISE & TOOLS	LS	1,618.862	1.00	1,618.86	
OH/C CONSUMABLES	LS	1,618.862	2.00	3,237.72	

Aathiv builds and designs

DESCRIPTION	UNIT	TOTAL QTY	RATE	AMOUNT (Rs)	TOTAL AMOUNT
OH/C Lead and Lift	LS	693.479	5.00	3,467.40	
Rental charges of Vibrator for Concreting work	N/day	3.571	500.00	1,785.60	
Rental charges of Concrete mixer for Concreting work	N/day	1.283	2,500.00	3,206.75	**8,77,042.77**
MASONRY WORK					
CEMENT	BAG	55.652	335.00	18,643.55	
M SAND (BLACK)	Cft	462.710	55.00	25,449.03	
RED BRICK (9" X 3" X 4")	NO	14,577.154	12.00	1,74,925.84	
L/c for 9" brick masonry	Cft	873.379	50.00	43,668.95	
L/c for 4.5" brick masonry	Sft	447.590	35.00	15,665.65	
OH/C CURING WORK	LS	1,320.969	3.00	3,962.91	
OH/C SUNDRISE & TOOLS	LS	1,320.969	1.00	1,320.97	
OH/C CONSUMABLES	LS	1,320.969	2.00	2,641.94	**2,86,278.84**
PLASTREING WORK					
CEMENT	BAG	101.214	335.00	33,906.82	
P SAND (PLASTER)	Cft	736.795	65.00	47,891.69	
L/c for Internal ceiling plaster	Sft	1,314.115	25.00	32,852.88	
L/c for Internal Wall plaster	Sft	4,309.760	23.00	99,124.48	
L/c for external plaster	Sft	1,500.000	25.00	37,500.00	
L/c for pointing for plastering work	Sft	1,314.115	3.00	3,942.35	
OH/C CURING WORK	LS	7,123.875	3.00	21,371.63	
OH/C SUNDRISE & TOOLS	LS	7,123.875	1.00	7,123.88	
OH/C CONSUMABLES	LS	7,123.875	2.00	14,247.75	
Providing and fixing of Scaffolding Cost	Sft	7,123.875	3.00	21,371.63	**3,19,333.11**
GRILL WORKS					
Providing & fabricating work for SS handrail with glass	Rft	21.000	2,200.00	46,200.00	
Providing & fabricating and fixing work for M.S. Grill	Kg	163.660	150.00	24,549.00	
Providing & fabricating work for SS Hand Railing	Rft	27.000	1,000.00	27,000.00	
OH/C SUNDRISE & TOOLS	LS	27.000	1.00	27.00	
OH/C CONSUMABLES	LS	27.000	2.00	54.00	**97,830.00**
DOOR WORKS					
Teak Wood Door Frame	Cft	2.806	3,500.00	9,819.60	
Teak Door Shutter	Cft	3.507	3,500.00	12,274.50	
Wood Door/window Frame (Padauh, Neam, Vengai)	Cft	4.910	2,000.00	9,819.60	
Redymade Flush Door Shutter	Sqft	73.500	285.00	20,947.50	
Door lense	Nos	1.000	350.00	349.86	
6" Hinges	Nos	26.947	500.00	13,473.60	
8" Handle Front	Nos	4.675	2,500.00	11,686.50	
6" Handle Back	Nos	4.675	1,000.00	4,674.60	
Main door Lock	Nos	1.000	12,000.00	11,995.20	
8" Tower bolt	Nos	4.675	750.00	3,505.95	
Door stoper	Nos	4.675	350.00	1,636.11	
Frame Clamps	Nos	26.947	100.00	2,694.72	

DESCRIPTION	UNIT	TOTAL QTY	RATE	AMOUNT (Rs)	TOTAL AMOUNT
Nails and other consumables for Wooderen works	Ls	4.675	1,000.00	4,674.60	
S&F WPC Door Frame with shutter	Sft	21.000	570.00	11,970.00	
Supply & Fixing of UPVC Sliding DOOR	Sft	42.000	550.00	23,100.00	
L/c For Woodern frame fixing and paking (Door, Window)	Sft	94.500	50.00	4,725.00	
L/c For Woodern Shutter and fitting fixing carpentry works	Sqft	21.000	200.00	4,200.00	**1,51,547.34**
JOINERY WORKS					
Supply & Fixing of UPVC Sliding window	Sft	147.500	470.00	69,325.00	
Supply & Fixing of UPVC Sliding window	Sft	144.000	1,500.00	2,16,000.00	
Supply & Fixing of UPVC Ventilator with Louver and exhaust	Sft	4.000	600.00	2,400.00	
Providing & fabricating and fixing work for M.S. Grill	Kg	437.250	150.00	65,587.50	**3,53,312.50**
FLOORING WORKS					
CEMENT	BAG	46.895	335.00	15,709.66	
M SAND (BLACK)	Cft	307.635	55.00	16,919.95	
Jiont grouting filler for Grainte and tile works	KG	65.005	45.00	2,925.24	
VITRIFIED TILE 12" X 12"	Sft	137.923	100.00	13,792.35	
VITRIFIED WALL TILE	Sft	339.108	100.00	33,910.80	
GRANITE BLACK	Sft	100.650	150.00	15,097.50	
MARBLE ITALIAN	SQFT	1,178.724	600.00	7,07,234.22	
STAINLESS STEEL SINK 24" X 20" X 8"	NO	1.000	5,000.00	5,000.00	
Cubord work for Cuddupha slab fixing,brick& plastering works	Sft	114.375	150.00	17,156.25	
L/c for Step Granite laying Work	Sqft	1,178.724	40.00	47,148.95	
L/c for Kitchen Table Top Granite laying	Sqft	100.650	35.00	3,522.75	
L/c for Granite Full Nosing work	Rft	465.227	70.00	32,565.88	
L/c for Pointing and Clening in flooring surface	Sft	1,713.039	3.00	5,139.12	
L/c for vertified tile laying work	Sft	125.385	20.00	2,507.70	
L/c Wall Tile Laying	Sft	308.280	20.00	6,165.60	
Labour charges for fixing sink	NO	1.000	600.00	600.00	
OH/C SUNDRISE & TOOLS	LS	433.665	1.00	433.66	**9,25,829.63**
PAINTING WORKS					
White cement	Kg	154.770	17.00	2,631.09	
Interior Primer	Ltr	45.135	120.00	5,416.20	
Exterior Primer	Ltr	20.700	200.00	4,140.00	
Interior Emultion	Ltr	97.173	500.00	48,586.50	
Exterior Emultion	Ltr	36.600	600.00	21,960.00	
Interior wall putty	kg	399.600	25.00	9,990.00	
Zinchromate primer	Lit	3.749	120.00	449.86	
Enamal Paint	Lit	7.550	300.00	2,265.12	
Melamine teak wood Polish	Lit	1.444	150.00	216.57	
4" Brush	NO	7.491	250.00	1,872.75	
9" Roller	NO	2.398	260.00	623.38	
Crack putty plate	NO	6.810	25.00	170.25	
6" Putty plate	NO	2.043	85.00	173.66	

Aathiv builds and designs

DESCRIPTION	UNIT	TOTAL QTY	RATE	AMOUNT (Rs)	TOTAL AMOUNT
8" Putty plate	NO	1.199	100.00	119.88	
12" Putty plate	NO	1.199	130.00	155.84	
18 no Flat brush	NO	0.264	100.00	26.40	
20 no Flat brush	NO	0.264	120.00	31.68	
POLISH PAPER - Emerry sheet - 100	NO	2.640	20.00	52.80	
POLISH PAPER - Emerry sheet - 180	NO	19.980	20.00	399.60	
THINNER	LTR	3.749	90.00	337.39	
Waste cloth	Kg	7.755	80.00	620.40	
POP	Kg	5.496	25.00	137.40	
Labour charges for Celing Surface Cleaning work	Sft	1,314.000	1.00	1,314.00	
Labour charges for Wall Surface Cleaning work	Sft	5,496.000	1.00	5,496.00	
L/c for Ext.paint White cement per coat	Sft	3,000.000	2.15	6,450.00	
L/c for Ext.paint Wall primer per coat	Sft	1,500.000	2.15	3,225.00	
L/c for Ext.paint Emultion per coat	Sft	3,000.000	2.20	6,600.00	
L/c for Int.paint White cement per coat	Sft	1,314.000	2.10	2,759.40	
L/c for In.Paint Celing primer per coat	Sft	1,314.000	2.10	2,759.40	
L/c for Int.paint Wall primer per coat	Sft	3,996.000	2.10	8,391.60	
L/c for In.Paint Zink primer per coat	Sft	528.000	5.25	2,772.00	
L/c for In.Paint Celing Emultion per coat	Sft	2,628.000	2.30	6,044.40	
L/c for In.Paint Wall Emultion per coat	Sft	7,992.000	2.30	18,381.60	
L/c for In.Paint Wall putty per coat	Sft	7,992.000	2.50	19,980.00	
L/c for In.Paint Enamal paint (Grill two side) per coat	Sft	1,056.000	7.00	7,392.00	
L/c for Pol. Melamine POLISH FINSIH	Sft	57.750	110.00	6,352.50	
OH/C SUNDRISE & TOOLS	LS	3,996.000	1.00	3,996.00	
Providing and fixing of Scaffolding Cost	Sft	3,996.000	3.00	11,988.00	**2,14,278.67**
ELECTRICAL & PLUMBING WORKS					
25mm HMS PVC Conduit Pipe (Slab & Walls)	Rft	573.300	25.00	14,332.50	
20mm HMS PVC Conduit Pipe (Point Wiring)	Rft	254.800	21.00	5,350.80	
1.0 sq.mm Wire (Light/Fan Points - Green/ Red/Black)	Coils	10.192	2,300.00	23,441.60	
1.5 sq.mm Wire (Primary Circuits/Sockets)	Coils	5.096	3,000.00	15,288.00	
2.5 sq.mm Wire (Power Points/Geyser)	Coils	3.822	5,200.00	19,874.40	
4.0 sq.mm Wire (Main Line/AC)	Coils	2.548	7,500.00	19,110.00	
12 Module Metal Box (Main Switch Board)	Nos	3.822	250.00	955.50	
8 Module Metal Box (Bedrooms/Kitchen)	Nos	5.096	180.00	917.28	
6 Module Metal Box (Utility/AC)	Nos	5.096	150.00	764.40	
3/2/1 Module Metal Box (Single points/ Calling bell)	Nos	15.288	80.00	1,223.04	
6A One-way Switch	Nos	57.330	65.00	3,726.45	
6A 3-pin Socket	Nos	22.932	120.00	2,751.84	
16A/25A Power Socket with Switch	Nos	7.644	350.00	2,675.40	
Fan Regulator (2-module step type)	Nos	6.370	250.00	1,592.50	
8-12 Way Double Door DB Box	Nos	1.274	8,000.00	10,192.00	
63A DP RCCB (30mA for safety)	Nos	1.274	2,200.00	2,802.80	

DESCRIPTION	UNIT	TOTAL QTY	RATE	AMOUNT (Rs)	TOTAL AMOUNT
63A FP Isolator	Nos	1.274	950.00	1,210.30	
6A/10A/16A/25A Single Pole MCB	Nos	1.274	350.00	445.90	
PVC Junction Boxes (Deep/Surface)	Nos	57.330	25.00	1,433.25	
PVC Bend (25mm/20mm)	Nos	76.440	15.00	1,146.60	
Solvent Cement (100ml)	Nos	2.548	120.00	305.76	
Insulation Tape (Assorted colors)	Nos	12.740	30.00	382.20	
Flexible Pipe (for drops)	Rft	38.220	12.00	458.64	
Plumbing Work Subcontract Labour	Sft	1,274.000	50.00	63,700.00	
Plumbing Work Subcontract Material	Sft	1,274.000	160.00	2,03,840.00	
L/C for Ele - Roof slab conduiting pipe laying works	Nos	6.370	1,000.00	6,370.00	
L/C for Ele - Wall Pipe and Mettal box fixing works	Nos	16.944	1,000.00	16,944.20	
L/C for Ele - Wiring works	Nos	12.740	1,000.00	12,740.00	
L/C for Ele - Swtiches & socket assamble and fixing works	Nos	10.574	1,000.00	10,574.20	
L/C for Ele - DB Board fixing & Wiring works	Nos	4.204	1,000.00	4,204.20	
L/C for Ele - Service connection and Testing works	Nos	4.204	1,000.00	4,204.20	
L/C for Ele - Light, fan, motor and orther fitting works	Nos	4.204	1,000.00	4,204.20	
L/C for Ele - other miscellaneous works	Nos	4.204	1,000.00	4,204.20	**4,61,366.36**
SECOND FLOOR					
SUPER STRUCTURE RCC WORK					
CEMENT	BAG	79.986	335.00	26,795.21	
3/4" (20MM) AGGREGATE	Cft	299.891	45.00	13,495.11	
M SAND (BLACK)	Cft	149.946	55.00	8,247.01	
READYMIX CONCRETE M 20 GRADE	Cft	670.810	160.00	1,07,329.60	
TMT STEEL FE 500	KG	4,364.875	80.00	3,49,189.97	
BINDING WIRE	KG	130.946	100.00	13,094.62	
ADMIXTURE	KG	23.660	80.00	1,892.83	
COVER BLOCK	NO	1,091.219	2.00	2,182.44	
S/c- Column Shuttering material Cost	Sft	664.452	20.00	13,289.04	
S/c- DPC/Sill/Coping Shuttering material Cost	Sft	109.448	15.00	1,641.71	
S/c- Lintel Shuttering material Cost	Sft	218.885	25.00	5,472.13	
S/c- Loft / sunshade /kitchen table Shuttering material Cost	Sft	122.000	25.00	3,050.00	
S/c- Staircase Shuttering material Cost	Sft	228.563	50.00	11,428.13	
S/c- Roof beam Shuttering material Cost	Sft	899.936	30.00	26,998.07	
S/c- Roof Slab Shuttering material Cost	Sft	990.534	20.00	19,810.68	
L/C for laying concrete for Column	Cft	147.656	60.00	8,859.36	
L/c for laying concrete for Staircase	Cft	62.474	50.00	3,123.69	
L/c for laying concrete for Lintel	Cft	209.554	45.00	9,429.93	
L/c for laying concrete for Sill	Cft	43.779	45.00	1,970.06	
L/C for RMC Concrete laying using Pump	Cft	670.810	15.00	10,062.15	
L/C for reinforcement work	KG	4,364.875	25.00	1,09,121.86	
L/c- Column Shuttering	Sft	664.452	17.00	11,295.68	
L/c- Loft / sunshade /kitchen table Shuttering	Sft	122.000	23.00	2,806.00	

Aathiv builds and designs

DESCRIPTION	UNIT	TOTAL QTY	RATE	AMOUNT (Rs)	TOTAL AMOUNT
L/c- Staircase Shuttering	Sft	228.563	60.00	13,713.75	
L/c- Lintel Shuttering	Sft	218.885	25.00	5,472.13	
Labour charges for shuttering of Sill	Sft	109.448	0.00	0.00	
L/c- Roof Slab Shuttering	Sft	990.534	25.00	24,763.35	
L/c- Roof Beam Shuttering	Sft	899.936	17.00	15,298.91	
CONCRETE PUMP	Cft	670.810	5.00	3,354.05	
OH/C CURING WORK	LS	1,376.549	3.00	4,129.65	
OH/C SUNDRISE & TOOLS	LS	1,524.205	1.00	1,524.21	
OH/C CONSUMABLES	LS	1,524.205	2.00	3,048.41	
OH/C Lead and Lift	LS	670.810	5.00	3,354.05	
Rental charges of Vibrator for Concreting work	N/day	3.445	500.00	1,722.65	
Rental charges of Concrete mixer for Concreting work	N/day	1.232	2,500.00	3,079.00	**8,40,045.44**
MASONRY WORK					
CEMENT	BAG	62.562	335.00	20,958.17	
M SAND (BLACK)	Cft	502.469	55.00	27,635.82	
RED BRICK (9" X 3" X 4")	NO	16,215.693	12.00	1,94,588.31	
L/c for 9" brick masonry	Cft	847.430	50.00	42,371.50	
L/c for 4.5" brick masonry	Sft	828.890	35.00	29,011.15	
OH/C CURING WORK	LS	1,676.320	3.00	5,028.96	
OH/C SUNDRISE & TOOLS	LS	1,676.320	1.00	1,676.32	
OH/C CONSUMABLES	LS	1,676.320	2.00	3,352.64	**3,24,622.87**
PLASTREING WORK					
CEMENT	BAG	105.428	335.00	35,318.38	
P SAND (PLASTER)	Cft	767.960	65.00	49,917.40	
L/c for Internal ceiling plaster	Sft	1,340.355	25.00	33,508.88	
L/c for Internal Wall plaster	Sft	4,579.100	23.00	1,05,319.30	
L/c for external plaster	Sft	1,500.000	25.00	37,500.00	
L/c for pointing for plastering work	Sft	1,340.355	3.00	4,021.07	
OH/C CURING WORK	LS	7,419.455	3.00	22,258.36	
OH/C SUNDRISE & TOOLS	LS	7,419.455	1.00	7,419.46	
OH/C CONSUMABLES	LS	7,419.455	2.00	14,838.91	
Providing and fixing of Scaffolding Cost	Sft	7,419.455	3.00	22,258.36	**3,32,360.12**
GRILL WORKS					
Providing & fabricating work for SS handrail with glass	Rft	33.000	2,200.00	72,600.00	
Providing & fabricating and fixing work for M.S. Grill	Kg	108.500	150.00	16,275.00	
Providing & fabricating work for SS Hand Railing	Rft	27.000	1,000.00	27,000.00	
OH/C SUNDRISE & TOOLS	LS	27.000	1.00	27.00	
OH/C CONSUMABLES	LS	27.000	2.00	54.00	**1,15,956.00**
DOOR WORKS					
Wood Door/window Frame (Padauh, Neam, Vengai)	Cft	5.611	2,000.00	11,222.40	
Redymade Flush Door Shutter	Sqft	84.000	285.00	23,940.00	
6" Hinges	Nos	23.940	500.00	11,970.00	
8" Handle Front	Nos	4.200	2,500.00	10,500.00	

DESCRIPTION	UNIT	TOTAL QTY	RATE	AMOUNT (Rs)	TOTAL AMOUNT
6" Handle Back	Nos	4.200	1,000.00	4,200.00	
8" Tower bolt	Nos	4.200	750.00	3,150.00	
Door stoper	Nos	4.200	350.00	1,470.00	
Frame Clamps	Nos	23.940	100.00	2,394.00	
Nails and other consumables for Wooderen works	Ls	4.200	1,000.00	4,200.00	
S&F WPC Door Frame with shutter	Sft	105.000	570.00	59,850.00	
Supply & Fixing of UPVC Sliding DOOR	Sft	17.500	550.00	9,625.00	
L/c For Woodern frame fixing and paking (Door, Window)	Sft	84.000	50.00	4,200.00	**1,46,721.40**
JOINERY WORKS					
Supply & Fixing of UPVC Sliding window	Sft	129.000	470.00	60,630.00	
Supply & Fixing of UPVC Ventilator with Louver and exhaust	Sft	12.000	600.00	7,200.00	
Providing & fabricating and fixing work for M.S. Grill	Kg	193.500	150.00	29,025.00	**96,855.00**
FLOORING WORKS					
CEMENT	BAG	49.894	335.00	16,714.46	
M SAND (BLACK)	Cft	230.166	55.00	12,659.11	
Jiont grouting filler for Grainte and tile works	KG	25.226	45.00	1,135.16	
VITRIFIED TILE 12" X 12"	Sft	259.411	100.00	25,941.08	
VITRIFIED TILE 24" X 24"	Sft	818.561	100.00	81,856.06	
VITRIFIED WALL TILE	Sft	622.116	100.00	62,211.60	
STAIRCASE LEATHER GRANITE	Sqft	17.738	160.00	2,838.00	
L/c for Step Granite laying Work	Sqft	17.738	40.00	709.50	
L/c for Granite Full Nosing work	Rft	6.450	70.00	451.50	
L/c for Pointing and Clening in flooring surface	Sft	1,563.271	3.00	4,689.81	
L/c for vertified tile laying work	Sft	979.974	20.00	19,599.48	
L/c Wall Tile Laying	Sft	565.560	20.00	11,311.20	
OH/C SUNDRISE & TOOLS	LS	1,545.534	1.00	1,545.53	**2,41,662.49**
PAINTING WORKS					
White cement	Kg	156.200	17.00	2,655.40	
Interior Primer	Ltr	50.575	120.00	6,069.00	
Exterior Primer	Ltr	20.700	200.00	4,140.00	
Interior Emultion	Ltr	108.885	500.00	54,442.50	
Exterior Emultion	Ltr	36.600	600.00	21,960.00	
Interior wall putty	kg	461.000	25.00	11,525.00	
Zinchromate primer	Lit	2.002	120.00	240.26	
Enamal Paint	Lit	4.033	300.00	1,209.78	
4" Brush	NO	8.195	250.00	2,048.75	
9" Roller	NO	2.766	260.00	719.16	
Crack putty plate	NO	7.450	25.00	186.25	
6" Putty plate	NO	2.235	85.00	189.98	
8" Putty plate	NO	1.383	100.00	138.30	
12" Putty plate	NO	1.383	130.00	179.79	
18 no Flat brush	NO	0.141	100.00	14.10	
20 no Flat brush	NO	0.141	120.00	16.92	
POLISH PAPER - Emerry sheet - 100	NO	1.410	20.00	28.20	

DESCRIPTION	UNIT	TOTAL QTY	RATE	AMOUNT (Rs)	TOTAL AMOUNT
POLISH PAPER - Emerry sheet - 180	NO	23.050	20.00	461.00	
THINNER	LTR	2.002	90.00	180.20	
Waste cloth	Kg	8.336	80.00	666.88	
POP	Kg	6.110	25.00	152.75	
Labour charges for Celing Surface Cleaning work	Sft	1,340.000	1.00	1,340.00	
Labour charges for Wall Surface Cleaning work	Sft	6,110.000	1.00	6,110.00	
L/c for Ext.paint White cement per coat	Sft	3,000.000	2.15	6,450.00	
L/c for Ext.paint Wall primer per coat	Sft	1,500.000	2.15	3,225.00	
L/c for Ext.paint Emultion per coat	Sft	3,000.000	2.20	6,600.00	
L/c for Int.paint White cement per coat	Sft	1,340.000	2.10	2,814.00	
L/c for In.Paint Celing primer per coat	Sft	1,340.000	2.10	2,814.00	
L/c for Int.paint Wall primer per coat	Sft	4,610.000	2.10	9,681.00	
L/c for In.Paint Zink primer per coat	Sft	282.000	5.25	1,480.50	
L/c for In.Paint Celing Emultion per coat	Sft	2,680.000	2.30	6,164.00	
L/c for In.Paint Wall Emultion per coat	Sft	9,220.000	2.30	21,206.00	
L/c for In.Paint Wall putty per coat	Sft	9,220.000	2.50	23,050.00	
L/c for In.Paint Enamal paint (Grill two side) per coat	Sft	564.000	7.00	3,948.00	
OH/C SUNDRISE & TOOLS	LS	4,610.000	1.00	4,610.00	
Providing and fixing of Scaffolding Cost	Sft	4,610.000	3.00	13,830.00	**2,20,546.72**
ELECTRICAL & PLUMBING WORKS					
25mm HMS PVC Conduit Pipe (Slab & Walls)	Rft	573.300	25.00	14,332.50	
20mm HMS PVC Conduit Pipe (Point Wiring)	Rft	254.800	21.00	5,350.80	
1.0 sq.mm Wire (Light/Fan Points - Green/ Red/Black)	Coils	10.192	2,300.00	23,441.60	
1.5 sq.mm Wire (Primary Circuits/Sockets)	Coils	5.096	3,000.00	15,288.00	
2.5 sq.mm Wire (Power Points/Geyser)	Coils	3.822	5,200.00	19,874.40	
4.0 sq.mm Wire (Main Line/AC)	Coils	2.548	7,500.00	19,110.00	
12 Module Metal Box (Main Switch Board)	Nos	3.822	250.00	955.50	
8 Module Metal Box (Bedrooms/Kitchen)	Nos	5.096	180.00	917.28	
6 Module Metal Box (Utility/AC)	Nos	5.096	150.00	764.40	
3/2/1 Module Metal Box (Single points/ Calling bell)	Nos	15.288	80.00	1,223.04	
6A One-way Switch	Nos	57.330	65.00	3,726.45	
6A 3-pin Socket	Nos	22.932	120.00	2,751.84	
16A/25A Power Socket with Switch	Nos	7.644	350.00	2,675.40	
Fan Regulator (2-module step type)	Nos	6.370	250.00	1,592.50	
8-12 Way Double Door DB Box	Nos	1.274	8,000.00	10,192.00	
63A DP RCCB (30mA for safety)	Nos	1.274	2,200.00	2,802.80	
63A FP Isolator	Nos	1.274	950.00	1,210.30	
6A/10A/16A/25A Single Pole MCB	Nos	1.274	350.00	445.90	
PVC Junction Boxes (Deep/Surface)	Nos	57.330	25.00	1,433.25	
PVC Bend (25mm/20mm)	Nos	76.440	15.00	1,146.60	
Solvent Cement (100ml)	Nos	2.548	120.00	305.76	
Insulation Tape (Assorted colors)	Nos	12.740	30.00	382.20	

DESCRIPTION	UNIT	TOTAL QTY	RATE	AMOUNT (Rs)	TOTAL AMOUNT
Flexible Pipe (for drops)	Rft	38.220	12.00	458.64	
Plumbing Work Subcontract Labour	Sft	1,274.000	50.00	63,700.00	
Plumbing Work Subcontract Material	Sft	1,274.000	160.00	2,03,840.00	
L/C for Ele - Roof slab conduiting pipe laying works	Nos	6.370	1,000.00	6,370.00	
L/C for Ele - Wall Pipe and Mettal box fixing works	Nos	16.944	1,000.00	16,944.20	
L/C for Ele - Wiring works	Nos	12.740	1,000.00	12,740.00	
L/C for Ele - Swtiches & socket assamble and fixing works	Nos	10.574	1,000.00	10,574.20	
L/C for Ele - DB Board fixing & Wiring works	Nos	4.204	1,000.00	4,204.20	
L/C for Ele - Service connection and Testing works	Nos	4.204	1,000.00	4,204.20	
L/C for Ele - Light, fan, motor and orther fitting works	Nos	4.204	1,000.00	4,204.20	
L/C for Ele - other miscellaneous works	Nos	4.204	1,000.00	4,204.20	**4,61,366.36**
THIRED/TERRAES FLOOR					
SUPER STRUCTURE RCC WORK					
CEMENT	BAG	25.588	335.00	8,571.88	
3/4" (20MM) AGGREGATE	Cft	95.943	45.00	4,317.45	
M SAND (BLACK)	Cft	47.972	55.00	2,638.45	
READYMIX CONCRETE M 20 GRADE	Cft	262.886	160.00	42,061.76	
TMT STEEL FE 500	KG	1,443.088	80.00	1,15,447.05	
BINDING WIRE	KG	43.293	100.00	4,329.27	
ADMIXTURE	KG	7.569	80.00	605.50	
COVER BLOCK	NO	356.084	2.00	712.17	
S/c- Column Shuttering material Cost	Sft	207.567	20.00	4,151.34	
S/c- Earth/Plinth beam Shuttering material Cost	Sft	93.755	20.00	1,875.10	
S/c- Lintel Shuttering material Cost	Sft	68.442	25.00	1,711.06	
S/c- Loft / sunshade /kitchen table Shuttering material Cost	Sft	32.000	25.00	800.00	
S/c- Roof beam Shuttering material Cost	Sft	279.232	30.00	8,376.95	
S/c- Roof Slab Shuttering material Cost	Sft	440.871	20.00	8,817.42	
L/C for laying concrete for Column	Cft	46.126	60.00	2,767.56	
L/c for laying concrete for Basement belt	Cft	37.502	50.00	1,875.10	
L/c for laying concrete for Lintel	Cft	59.377	45.00	2,671.96	
L/C for RMC Concrete laying using Pump	Cft	262.886	15.00	3,943.29	
L/C for reinforcement work	KG	1,443.088	25.00	36,077.20	
L/c- Column Shuttering	Sft	207.567	17.00	3,528.64	
L/c- Earth/Plinth beam Shuttering	Sft	93.755	20.00	1,875.10	
L/c- Loft / sunshade /kitchen table Shuttering	Sft	32.000	23.00	736.00	
L/c- Lintel Shuttering	Sft	68.442	25.00	1,711.06	
L/c- Roof Slab Shuttering	Sft	440.871	25.00	11,021.78	
L/c- Roof Beam Shuttering	Sft	279.232	17.00	4,746.94	
CONCRETE PUMP	Cft	262.886	5.00	1,314.43	
OH/C CURING WORK	LS	405.891	3.00	1,217.67	
OH/C SUNDRISE & TOOLS	LS	452.017	1.00	452.02	
OH/C CONSUMABLES	LS	452.017	2.00	904.03	

DESCRIPTION	UNIT	TOTAL QTY	RATE	AMOUNT (Rs)	TOTAL AMOUNT
OH/C Lead and Lift	LS	262.886	5.00	1,314.43	
Rental charges of Vibrator for Concreting work	N/day	1.259	500.00	629.70	
Rental charges of Concrete mixer for Concreting work	N/day	0.392	2,500.00	979.75	**2,82,182.06**
MASONRY WORK					
CEMENT	BAG	32.961	335.00	11,041.94	
M SAND (BLACK)	Cft	288.440	55.00	15,864.21	
RED BRICK (9" X 3" X 4")	NO	8,772.890	12.00	1,05,274.68	
L/c for 9" brick masonry	Cft	626.635	50.00	31,331.75	
OH/C CURING WORK	LS	626.635	3.00	1,879.91	
OH/C SUNDRISE & TOOLS	LS	626.635	1.00	626.64	
OH/C CONSUMABLES	LS	626.635	2.00	1,253.27	**1,67,272.40**
PLASTREING WORK					
CEMENT	BAG	39.099	335.00	13,098.33	
P SAND (PLASTER)	Cft	286.830	65.00	18,643.93	
L/c for Internal ceiling plaster	Sft	379.910	25.00	9,497.75	
L/c for Internal Wall plaster	Sft	805.350	23.00	18,523.05	
L/c for external plaster	Sft	1,562.250	25.00	39,056.25	
L/c for pointing for plastering work	Sft	379.910	3.00	1,139.73	
OH/C CURING WORK	LS	2,747.510	3.00	8,242.53	
OH/C SUNDRISE & TOOLS	LS	2,747.510	1.00	2,747.51	
OH/C CONSUMABLES	LS	2,747.510	2.00	5,495.02	
Providing and fixing of Scaffolding Cost	Sft	2,747.510	3.00	8,242.53	**1,24,686.63**
JOINERY WORKS					
Supply & Fixing of UPVC Sliding window	Sft	118.500	470.00	55,695.00	
Supply & Fixing of UPVC Sliding DOOR	Sft	35.000	550.00	19,250.00	
Providing & fabricating and fixing work for M.S. Grill	Kg	177.750	150.00	26,662.50	**1,01,607.50**
GRILL WORKS					
Providing & fabricating and fixing work for M.S. Trap door	Kg	52.500	170.00	8,925.00	**8,925.00**
PAINTING WORKS					
White cement	Kg	106.810	17.00	1,815.77	
Interior Primer	Ltr	10.404	120.00	1,248.48	
Exterior Primer	Ltr	21.556	200.00	4,311.12	
Interior Emultion	Ltr	22.399	500.00	11,199.60	
Exterior Emultion	Ltr	38.113	600.00	22,867.68	
Interior wall putty	kg	84.400	25.00	2,110.00	
Wood primer	Lit	1.332	120.00	159.86	
Enamal Paint	Lit	2.295	300.00	688.56	
2" Brush	NO	0.080	100.00	8.03	
3" Brush	NO	0.080	180.00	14.45	
4" Brush	NO	3.065	250.00	766.15	
9" Roller	NO	0.506	260.00	131.66	
Crack putty plate	NO	2.786	25.00	69.65	
6" Putty plate	NO	0.836	85.00	71.04	
8" Putty plate	NO	0.253	100.00	25.32	

Aathiv builds and designs

DESCRIPTION	UNIT	TOTAL QTY	RATE	AMOUNT (Rs)	TOTAL AMOUNT
12" Putty plate	NO	0.253	130.00	32.92	
POLISH PAPER - Emerry sheet - 180	NO	4.220	20.00	84.40	
POLISH PAPER - Emerry sheet - 220	NO	0.802	20.00	16.05	
THINNER	LTR	2.295	90.00	206.57	
Waste cloth	Kg	3.145	80.00	251.59	
POP	Kg	2.406	25.00	60.15	
Labour charges for Celing Surface Cleaning work	Sft	380.000	1.00	380.00	
Labour charges for Wall Surface Cleaning work	Sft	2,406.000	1.00	2,406.00	
L/c for Ext.paint White cement per coat	Sft	3,124.000	2.15	6,716.60	
L/c for Ext.paint Wall primer per coat	Sft	1,562.000	2.15	3,358.30	
L/c for Ext.paint Emultion per coat	Sft	3,124.000	2.20	6,872.80	
L/c for Int.paint White cement per coat	Sft	380.000	2.10	798.00	
L/c for In.Paint Celing primer per coat	Sft	380.000	2.10	798.00	
L/c for Int.paint Wall primer per coat	Sft	844.000	2.10	1,772.40	
L/c for In.Paint Wood primer per coat	Sft	160.500	5.25	842.63	
L/c for In.Paint Celing Emultion per coat	Sft	760.000	2.30	1,748.00	
L/c for In.Paint Wall Emultion per coat	Sft	1,688.000	2.30	3,882.40	
L/c for In.Paint Wall putty per coat	Sft	1,688.000	2.50	4,220.00	
L/c for In.Paint Enamal paint (door/window two side) 1 c	Sft	321.000	7.00	2,247.00	
OH/C SUNDRISE & TOOLS	LS	844.000	1.00	844.00	
Providing and fixing of Scaffolding Cost	Sft	844.000	3.00	2,532.00	**85,557.18**
ELECTRICAL & PLUMBING WORKS					
Electrical Work Subcontract Labour	Sft	300.875	50.00	15,043.75	
Electrical Work Subcontract Material	Sft	300.875	50.00	15,043.75	**30,087.50**
WEATHERING COURSE WORKS					
CEMENT	BAG	40.735	335.00	13,646.19	
M SAND (BLACK)	Cft	203.674	55.00	11,202.09	
BRICK BATS (Brick jally)	Cft	344.494	50.00	17,224.72	
Jiont grouting filler for Grainte and tile works	KG	19.098	45.00	859.42	
Cool Roof Tile (White)	Sft	1,329.625	100.00	1,32,962.50	
LIME POWDER	Cft	114.831	70.00	8,038.20	
Providing & applying waterproofing treatment for Terrace	Sft	1,329.625	15.00	19,944.38	
WATER TANK (Sintex)	Liter	4,000.000	6.00	24,000.00	
L/c for Pointing and Clening in flooring surface	Sft	1,208.750	3.00	3,626.25	
L/c for vertified tile laying work	Sft	1,208.750	20.00	24,175.00	
L/c for Wethering corse surki concrete laying with lifting	Cft	302.188	35.00	10,576.58	
L/c for Wethering corse Brick bats Broken charges	Cft	302.188	20.00	6,043.76	
OH/C SUNDRISE & TOOLS	LS	1,208.750	1.00	1,208.75	**2,73,507.84**
ADDITIONAL WORKS					
Providing & fabricating and fixing work for M.S. Trap door	Kg	480.000	170.00	81,600.00	

Aathiv builds and designs

DESCRIPTION	UNIT	TOTAL QTY	RATE	AMOUNT (Rs)	TOTAL AMOUNT
Supply of 3' Well Ring for Rainwater Harversting	Nos	21.000	2,000.00	42,000.00	
Erection of 3' Well Ring for Rainwater Harversting	Nos	21.000	850.00	17,850.00	
Sump/Septic/Overhead TANK - 9"(BW+ RCC)	Lit	10,000.000	20.00	2,00,000.00	
9"-BW SUMP/SEPTIC TANK	Litr	1,000.000	50.00	50,000.00	
Compound wall Work	Rft	60.000	2,700.00	1,62,000.00	**5,53,450.00**
PMC FEE					
Supply of Supervisor	Day	1.000	0,00,000.00	20,00,000.00	**20,00,000.00**