Aathiv builds and designs

Analysis of work items

1500		**PROPOSED RSIDENTIAL BUILDING**					
1510		**FOUNDATION WORKS (UPTO FFL)**					
1520	**1.1.1**	**F-Earth work for Footing (Shalow Excavation)**	**6,035.750 Cft**	**11(Net)**	**11(Gross)**	**66,393.25(Amt.)**	**0.47 %**

F-Earth work for Footing (Shalow Excavation)

Group : 1 Excavation Labour -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-EAW-001	Rental charges of Earthwork Machinery	hr	40.4395	1,300.00	52,571.38	8.71	1.000	8.71	52,571.38	79.18

Group : 2 Other Consumables

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	12,071.5000	1.00	12,071.50	2.00	1.000	2.00	12,071.50	18.18

1525	**1.1.2**	**F-Msand filling in Flooring - 10"**	**715.667 Cft**	**72(Net)**	**72(Gross)**	**51,528.02(Amt.)**	**0.36 %**

F-Msand filling in Flooring - 10"

Group : 1 LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-01-FIL-004	L/C for Msand / Quary dust filling	Cft	715.6670	11.00	7,872.34	11.00	1.000	11.00	7,872.34	15.28

Group : 2 MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%

A-02-AGG-02-004	M SAND (BLACK)	Cft	787.2337	55.00	43,297.85	60.50	1.000	60.50	43,297.85	84.03

1530 1.1.3 F-PCC 1:4:8 for FOOTING 4" 284.543 Cft 147(Net) 147(Gross) 41,827.82(Amt.) 0.30 %

F-PCC 1:4:8 for FOOTING 4"

Group : 1 PCC LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-010	L/C for laying concrete for P.C.C	Cft	284.5430	35.00	9,959.01	35.00	1.000	35.00	9,959.01	23.81

Group : 2 PCC MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	26.2349	335.00	8,789.53	30.89	1.000	30.89	8,789.53	21.01
A-02-AGG-02-004	M SAND (BLACK)	Cft	131.1743	55.00	7,216.01	25.36	1.000	25.36	7,216.01	17.25
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	262.3486	45.00	11,805.69	41.49	1.000	41.49	11,805.69	28.22

Group : 3 PCC MACHINERY

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	0.9390	2,500.00	2,347.48	8.25	1.000	8.25	2,347.48	5.61

Group : 4 Other Consumables

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	284.5430	1.00	284.54	1.00	1.000	1.00	284.54	0.68
O-01-CUR-001	OH/C CURING WORK	LS	284.5430	3.00	853.63	3.00	1.000	3.00	853.63	2.04

O-03-CONS-001	OH/C CONSUMABLES	LS	284.5430	2.00	569.09	2.00	1.000	2.00	569.09	1.36

1550 1.1.4 F-RCC M20 (1:1.5:3) for Footing 997.140 CFT 397.64(Net) 397.64(Gross) 3,96,502.75(Amt.) 2.80 %

F-RCC M20 (1:1.5:3) for Footing

Group : 1 RCC LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-020	L/C for laying concrete for Footing	Cft	997.1400	40.00	39,885.60	40.00	1.000	40.00	39,885.60	10.06

Group : 2 RCC MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	214.3851	335.00	71,823.99	72.03	1.000	72.03	71,823.99	18.11
A-02-AGG-02-004	M SAND (BLACK)	Cft	401.9471	55.00	22,106.59	22.17	1.000	22.17	22,106.59	5.58
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	803.8943	45.00	36,176.24	36.28	1.000	36.28	36,176.24	9.12
A-04-CHM-003	ADMIXTURE	KG	63.4181	80.00	5,075.44	5.09	1.000	5.09	5,075.44	1.28

Group : 3 RCC MACHINE

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	3.2906	2,500.00	8,226.41	8.25	1.000	8.25	8,226.41	2.07
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	3.2906	500.00	1,645.28	1.65	1.000	1.65	1,645.28	0.41

Group : 4 RCC CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%

O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	997.1400	1.00	997.14	1.00	1.000	1.00	997.14	0.25
O-01-CUR-001	OH/C CURING WORK	LS	997.1400	3.00	2,991.42	3.00	1.000	3.00	2,991.42	0.75
O-03-CONS-001	OH/C CONSUMABLES	LS	997.1400	2.00	1,994.28	2.00	1.000	2.00	1,994.28	0.50

Group : 5 STEEL MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	1,545.5670	80.00	1,23,645.36	124.00	1.000	124.00	1,23,645.36	31.18
A-03-REF-03	BINDING WIRE	KG	46.3670	100.00	4,636.70	4.65	1.000	4.65	4,636.70	1.17
A-05-COV-011	COVER BLOCK	NO	386.3918	2.00	777.77	0.78	1.000	0.78	777.77	0.20

Group : 6 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	1,545.5670	25.00	38,639.18	38.75	1.000	38.75	38,639.18	9.74

Group : 7 Shuttering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-001	L/c- Footing/raft Shuttering	Sft	997.1400	20.00	19,942.80	20.00	1.000	20.00	19,942.80	5.03

Group : 8 Shuttering material-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-001	S/c- Footing/raft Shuttering material Cost	Sft	997.1400	15.00	14,957.10	15.00	1.000	15.00	14,957.10	3.77

Group : 9 MACHINERY and CONSUMA

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	997.1400	1.00	997.14	1.00	1.000	1.00	997.14	0.25

O-03-CONS-001	OH/C CONSUMABLES	LS	997.1400	2.00	1,994.28	2.00	1.000	2.00	1,994.28	0.50

1560 1.1.5 F-RCC M20 (1:1.5:3) COLUMN Upto E.B BOTTOM 59.040 CFT 1,384.59(Net) 1,384.59(Gross) 81,746.19(Amt.) 0.58 %

F-RCC M20 (1:1.5:3) COLUMN Upto E.B BOTTOM

Group : 1 RCC LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-035	L/C for laying concrete for Column	Cft	59.0400	60.00	3,542.40	60.00	1.000	60.00	3,542.40	4.33

Group : 2 RCC MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	12.6936	335.00	4,252.65	72.03	1.000	72.03	4,252.65	5.20
A-02-AGG-02-004	M SAND (BLACK)	Cft	23.7990	55.00	1,308.92	22.17	1.000	22.17	1,308.92	1.60
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	47.5980	45.00	2,141.97	36.28	1.000	36.28	2,141.97	2.62
A-04-CHM-003	ADMIXTURE	KG	3.7549	80.00	300.51	5.09	1.000	5.09	300.51	0.37

Group : 3 RCC MACHINE

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	0.1948	2,500.00	487.08	8.25	1.000	8.25	487.08	0.60
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.1948	500.00	97.42	1.65	1.000	1.65	97.42	0.12

Group : 4 RCC CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	59.0400	1.00	59.04	1.00	1.000	1.00	59.04	0.07
O-01-CUR-001	OH/C CURING WORK	LS	59.0400	3.00	177.12	3.00	1.000	3.00	177.12	0.22
O-03-CONS-001	OH/C CONSUMABLES	LS	59.0400	2.00	118.08	2.00	1.000	2.00	118.08	0.14

Group : 5 Shuttering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-002	L/c- Column Shuttering	Sft	265.6800	17.00	4,516.56	76.50	1.000	76.50	4,516.56	5.53

Group : 6 Shuttering material-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-005	S/c- Column Shuttering material Cost	Sft	265.6800	20.00	5,313.60	90.00	1.000	90.00	5,313.60	6.50

Group : 7 MACHINERY and CONSUMA

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	59.0400	1.00	59.04	1.00	1.000	1.00	59.04	0.07
O-03-CONS-001	OH/C CONSUMABLES	LS	59.0400	2.00	118.08	2.00	1.000	2.00	118.08	0.14

Group : 8 STEEL MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	546.1200	80.00	43,689.60	740.00	1.000	740.00	43,689.60	53.45
A-03-REF-03	BINDING WIRE	KG	16.3836	100.00	1,638.36	27.75	1.000	27.75	1,638.36	2.00
A-05-COV-011	COVER BLOCK	NO	136.5300	2.00	273.36	4.63	1.000	4.63	273.36	0.33

Group : 9 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	546.1200	25.00	13,653.00	231.25	1.000	231.25	13,653.00	16.70

1570 1.1.6 F-Earth work for Earth beam (Manual excavation) 222.541 Cft 20(Net) 20(Gross) 4,450.82(Amt.) 0.03 %

F-Earth work for Earth beam (Manual excavation)

Group : 1 Labour -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-01-EXC-257	L/C Earth work Excavation upto 5' to 10' depth	Cft	222.5410	20.00	4,450.82	20.00	1.000	20.00	4,450.82	100.00

1580 1.1.7 F-Refilling Excavated Earth In Foundation 4,210.000 Cft 4.00(Net) 4.00(Gross) 16,840.00(Amt.) 0.12 %

F-Refilling Excavated Earth In Foundation

Group : 1 FILLING LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-01-FIL-035	L/C Earth Refilling with leveling & consolidation	Cft	4,210.0000	3.00	12,630.00	3.00	1.000	3.00	12,630.00	75.00

Group : 2 Other Consumables

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	4,210.0000	1.00	4,210.00	1.00	1.000	1.00	4,210.00	25.00

1585 1.1.8 F-Msand filling in Earth beam - 2" 74.328 Cft 72(Net) 72(Gross) 5,351.62(Amt.) 0.04 %

F-Msand filling in Earth beam - 2"

Group : 1 LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-01-FIL-004	L/C for Msand / Quary dust filling	Cft	74.3280	11.00	817.61	11.00	1.000	11.00	817.61	15.28

Group : 2 MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-02-AGG-02-004	M SAND (BLACK)	Cft	81.7608	55.00	4,496.84	60.50	1.000	60.50	4,496.84	84.03

1590 1.1.9 F-PCC 1:4:8 for Earth beam -4" 146.877 Cft 147(Net) 147(Gross) 21,590.92(Amt.) 0.15 %

F-PCC 1:4:8 for Earth beam -4"

Group : 1 PCC LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-010	L/C for laying concrete for P.C.C	Cft	146.8770	35.00	5,140.70	35.00	1.000	35.00	5,140.70	23.81

Group : 2 PCC MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	13.5421	335.00	4,537.03	30.89	1.000	30.89	4,537.03	21.01
A-02-AGG-02-004	M SAND (BLACK)	Cft	67.7103	55.00	3,724.80	25.36	1.000	25.36	3,724.80	17.25
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	135.4206	45.00	6,093.93	41.49	1.000	41.49	6,093.93	28.22

Group : 3 PCC MACHINERY

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%

R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	0.4847	2,500.00	1,211.74	8.25	1.000	8.25	1,211.74	5.61

Group : 4 Other Consumables

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	146.8770	1.00	146.88	1.00	1.000	1.00	146.88	0.68
O-01-CUR-001	OH/C CURING WORK	LS	146.8770	3.00	440.63	3.00	1.000	3.00	440.63	2.04
O-03-CONS-001	OH/C CONSUMABLES	LS	146.8770	2.00	293.75	2.00	1.000	2.00	293.75	1.36

1600 1.1.10 F-RCC M20(1:1.5:3) Earth Beam 238.437 CFT 620.96(Net) 620.96(Gross) 1,48,059.84(Amt.) 1.05 %

F-RCC M20(1:1.5:3) Earth Beam

Group : 1 RCC LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-040	L/c for laying concrete for Earth beam	Cft	238.4370	45.00	10,729.67	45.00	1.000	45.00	10,729.67	7.25

Group : 2 RCC MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	51.2640	335.00	17,174.62	72.03	1.000	72.03	17,174.62	11.60
A-02-AGG-02-004	M SAND (BLACK)	Cft	96.1140	55.00	5,286.15	22.17	1.000	22.17	5,286.15	3.57
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	192.2279	45.00	8,650.49	36.28	1.000	36.28	8,650.49	5.84
A-04-CHM-003	ADMIXTURE	KG	15.1646	80.00	1,213.64	5.09	1.000	5.09	1,213.64	0.82

Group : 3 RCC MACHINE

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	0.7868	2,500.00	1,967.11	8.25	1.000	8.25	1,967.11	1.33
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.7868	500.00	393.42	1.65	1.000	1.65	393.42	0.27

Group : 4 RCC CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	238.4370	1.00	238.44	1.00	1.000	1.00	238.44	0.16
O-01-CUR-001	OH/C CURING WORK	LS	238.4370	3.00	715.31	3.00	1.000	3.00	715.31	0.48
O-03-CONS-001	OH/C CONSUMABLES	LS	238.4370	2.00	476.87	2.00	1.000	2.00	476.87	0.32

Group : 5 Shuttering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-004	L/c- Earth/Plinth beam Shuttering	Sft	596.0925	20.00	11,921.85	50.00	1.000	50.00	11,921.85	8.05

Group : 6 Shuttering material-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-015	S/c- Earth/Plinth beam Shuttering material Cost	Sft	596.0925	20.00	11,921.85	50.00	1.000	50.00	11,921.85	8.05

Group : 7 STEEL MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	715.3110	80.00	57,224.88	240.00	1.000	240.00	57,224.88	38.65
A-03-REF-03	BINDING WIRE	KG	21.4593	100.00	2,145.93	9.00	1.000	9.00	2,145.93	1.45
A-05-COV-011	COVER BLOCK	NO	59.6093	2.00	119.22	0.50	1.000	0.50	119.22	0.08

Group : 8 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	715.3110	25.00	17,882.78	75.00	1.000	75.00	17,882.78	12.08

1610 1.1.11 F-RCC M20 (1:1.5:3) COLUMN Upto FFL 46.126 CFT 1,384.59(Net) 1,384.59(Gross) 63,865.60(Amt.) 0.45 %

F-RCC M20 (1:1.5:3) COLUMN Upto FFL

Group : 1 RCC LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-035	L/C for laying concrete for Column	Cft	46.1260	60.00	2,767.56	60.00	1.000	60.00	2,767.56	4.33

Group : 2 RCC MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	9.9171	335.00	3,322.46	72.03	1.000	72.03	3,322.46	5.20
A-02-AGG-02-004	M SAND (BLACK)	Cft	18.5934	55.00	1,022.61	22.17	1.000	22.17	1,022.61	1.60
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	37.1868	45.00	1,673.45	36.28	1.000	36.28	1,673.45	2.62
A-04-CHM-003	ADMIXTURE	KG	2.9336	80.00	234.78	5.09	1.000	5.09	234.78	0.37

Group : 3 RCC MACHINE

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	0.1522	2,500.00	380.54	8.25	1.000	8.25	380.54	0.60
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.1522	500.00	76.11	1.65	1.000	1.65	76.11	0.12

Group : 4 RCC CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	46.1260	1.00	46.13	1.00	1.000	1.00	46.13	0.07
O-01-CUR-001	OH/C CURING WORK	LS	46.1260	3.00	138.38	3.00	1.000	3.00	138.38	0.22
O-03-CONS-001	OH/C CONSUMABLES	LS	46.1260	2.00	92.25	2.00	1.000	2.00	92.25	0.14

Group : 5 Shuttering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-002	L/c- Column Shuttering	Sft	207.5670	17.00	3,528.64	76.50	1.000	76.50	3,528.64	5.53

Group : 6 Shuttering material-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-005	S/c- Column Shuttering material Cost	Sft	207.5670	20.00	4,151.34	90.00	1.000	90.00	4,151.34	6.50

Group : 7 MACHINERY and CONSUMA

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	46.1260	1.00	46.13	1.00	1.000	1.00	46.13	0.07
O-03-CONS-001	OH/C CONSUMABLES	LS	46.1260	2.00	92.25	2.00	1.000	2.00	92.25	0.14

Group : 8 STEEL MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	426.6655	80.00	34,133.24	740.00	1.000	740.00	34,133.24	53.45
A-03-REF-03	BINDING WIRE	KG	12.8000	100.00	1,280.00	27.75	1.000	27.75	1,280.00	2.00
A-05-COV-011	COVER BLOCK	NO	106.6664	2.00	213.56	4.63	1.000	4.63	213.56	0.33

Group : 9 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	426.6655	25.00	10,666.64	231.25	1.000	231.25	10,666.64	16.70

1620 1.1.12 F-RCC M20(1:1.5:3) Basement Belt 95.376 CFT 451.46(Net) 451.46(Gross) 43,058.45(Amt.) 0.30 %

F-RCC M20(1:1.5:3) Basement Belt

Group : 1 RCC MACHINE

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	0.3147	2,500.00	786.85	8.25	1.000	8.25	786.85	1.83
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.3147	500.00	157.37	1.65	1.000	1.65	157.37	0.37

Group : 2 RCC LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-042	L/c for laying concrete for Basement belt	Cft	95.3760	50.00	4,768.80	50.00	1.000	50.00	4,768.80	11.08

Group : 3 RCC MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	20.5058	335.00	6,869.93	72.03	1.000	72.03	6,869.93	15.95
A-02-AGG-02-004	M SAND (BLACK)	Cft	38.4461	55.00	2,114.49	22.17	1.000	22.17	2,114.49	4.91
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	76.8921	45.00	3,460.24	36.28	1.000	36.28	3,460.24	8.04
A-01-OCE-004	PLASTICIZER	KG	6.0659	80.00	485.46	5.09	1.000	5.09	485.46	1.13

Group : 4 RCC CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	95.3760	1.00	95.38	1.00	1.000	1.00	95.38	0.22
O-01-CUR-001	OH/C CURING WORK	LS	95.3760	3.00	286.13	3.00	1.000	3.00	286.13	0.66
O-03-CONS-001	OH/C CONSUMABLES	LS	95.3760	2.00	190.75	2.00	1.000	2.00	190.75	0.44

Group : 5 Shuttering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-006	L/c- DPC/Sill/Coping Shuttering	Sft	238.4400	20.00	4,768.80	50.00	1.000	50.00	4,768.80	11.08

Group : 6 Shuttering material-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-020	S/c- DPC/Sill/Coping Shuttering material Cost	Sft	238.4400	15.00	3,576.60	37.50	1.000	37.50	3,576.60	8.31

Group : 7 STEEL MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	143.0640	80.00	11,445.12	120.00	1.000	120.00	11,445.12	26.58
A-03-REF-03	BINDING WIRE	KG	4.2919	100.00	429.19	4.50	1.000	4.50	429.19	1.00
A-05-COV-011	COVER BLOCK	NO	23.8440	2.00	47.69	0.50	1.000	0.50	47.69	0.11

Group : 8 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	143.0640	25.00	3,576.60	37.50	1.000	37.50	3,576.60	8.31

1630 1.1.13 F-9" FLY ASH BRICK WORK (CM1:6) FOR BASEMENT 238.437 Cft 211(Net) 211(Gross) 50,310.21(Amt.) 0.36 %

F-9" FLY ASH BRICK WORK (CM1:6) FOR BASEMENT

Group : 1 MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	12.5418	335.00	4,201.26	17.62	1.000	17.62	4,201.26	8.35
A-02-AGG-02-004	M SAND (BLACK)	Cft	109.7526	55.00	6,037.22	25.32	1.000	25.32	6,037.22	12.00
A-02-BRK-02-007	FLYASH BRICK (9" X 3" X 4")	NO	3,338.1180	8.00	26,704.94	112.00	1.000	112.00	26,704.94	53.08

Group : 2 LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-04-MAS-155	L/c for 9" brick masonry	Cft	238.4370	50.00	11,921.85	50.00	1.000	50.00	11,921.85	23.70

Group : 3 CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-01-CUR-001	OH/C CURING WORK	LS	238.4370	3.00	715.31	3.00	1.000	3.00	715.31	1.42
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	238.4370	1.00	238.44	1.00	1.000	1.00	238.44	0.47
O-03-CONS-001	OH/C CONSUMABLES	LS	238.4370	2.00	476.87	2.00	1.000	2.00	476.87	0.95

1640 1.1.14 F-BASEMENT PLASTERING WITH BITUMEN COAT - 2C 1,434.480 Sft 45(Net) 45(Gross) 64,551.60(Amt.) 0.46 %

F-BASEMENT PLASTERING WITH BITUMEN COAT - 2C

Group : 1 Bitumen Paint

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-04-CHM-125	Bitumen waterproofing Paint	Lit	38.3006	0.00	0.00	0.00	1.000	0.00	0.00	0.00
L-09-WPP-015	L/c for Bitumen waterproofing Painting work - 1 coat	Sft	2,868.9600	2.00	5,737.92	4.00	1.000	4.00	5,737.92	8.89

Group : 2 PLASTERING LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-06-EXT-005	L/c for external plaster	Sft	1,434.4800	25.00	35,862.00	25.00	1.000	25.00	35,862.00	55.56

Group : 3 PLASTERING MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	20.5131	335.00	6,871.16	4.79	1.000	4.79	6,871.16	10.64
A-02-AGG-02-006	P SAND (PLASTER)	Cft	153.9197	65.00	9,998.33	6.97	1.000	6.97	9,998.33	15.49
A-04-CHM-119	WATERPROOFING CHEMICAL For Basement	Ltr	4.1600	150.00	631.17	0.44	1.000	0.44	631.17	0.98

Group : 4 CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-01-CUR-001	OH/C CURING WORK	LS	1,434.4800	3.00	4,303.44	3.00	1.000	3.00	4,303.44	6.67
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	1,434.4800	1.00	1,434.48	1.00	1.000	1.00	1,434.48	2.22

1650 1.1.15 F-Refilling Excavated earth in basement 2,047.000 Cft 4(Net) 4(Gross) 8,188.00(Amt.) 0.06 %

F-Refilling Excavated earth in basement

Group : 1 FILLING LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-01-FIL-035	L/C Earth Refilling with leveling & consolidation	Cft	2,047.0000	3.00	6,141.00	3.00	1.000	3.00	6,141.00	75.00

Group : 2 Other Consumables

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	2,047.0000	1.00	2,047.00	1.00	1.000	1.00	2,047.00	25.00

1660 1.1.16 F-Filling with Brought out Well gravel for necessary area 383.327 Cft 35(Net) 35(Gross) 13,416.45(Amt.) 0.09 %

F-Filling with Brought out Well gravel for necessary area

Group : 1 FILLING LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-01-FIL-035	L/C Earth Refilling with leveling & consolidation	Cft	383.3270	3.00	1,149.98	3.00	1.000	3.00	1,149.98	8.57

Group : 2 FILLING MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-02-AGG-07-001	Well Gravel	Cft	479.1588	23.00	11,020.65	28.75	1.000	28.75	11,020.65	82.14

Group : 3 Other Consumables

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	383.3270	1.00	383.33	1.00	1.000	1.00	383.33	2.86
R-02-EAW-003	Rentel charges for Earth rammer for Compaction	N/day	0.3833	2,400.00	919.98	2.40	1.000	2.40	919.98	6.86

1670 1.1.17 F-Msand filling in Flooring - 2" 201.854 Cft 72(Net) 72(Gross) 14,533.49(Amt.) 0.10 %

F-Msand filling in Flooring - 2"

Group : 1 LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-01-FIL-004	L/C for Msand / Quary dust filling	Cft	201.8540	11.00	2,220.39	11.00	1.000	11.00	2,220.39	15.28

Group : 2 MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-02-AGG-02-004	M SAND (BLACK)	Cft	222.0394	55.00	12,212.17	60.50	1.000	60.50	12,212.17	84.03

1680 1.1.18 F-PCC 1:4:8 for Floorings -4" 398.873 Cft 198(Net) 198(Gross) 78,976.85(Amt.) 0.56 %

F-PCC 1:4:8 for Floorings -4"

Group : 1 PCC LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-010	L/C for laying concrete for P.C.C	Cft	398.8730	35.00	13,960.56	35.00	1.000	35.00	13,960.56	17.68

Group : 2 PCC MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	36.7761	335.00	12,321.19	30.89	1.000	30.89	12,321.19	15.60
A-02-AGG-02-004	M SAND (BLACK)	Cft	183.8805	55.00	10,115.42	25.36	1.000	25.36	10,115.42	12.81
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	367.7609	45.00	16,549.24	41.49	1.000	41.49	16,549.24	20.95

Group : 3 **PCC MACHINERY**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	1.3163	2,500.00	3,290.70	8.25	1.000	8.25	3,290.70	4.17

Group : 4 **Other Consumables**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	398.8730	1.00	398.87	1.00	1.000	1.00	398.87	0.51
O-01-CUR-001	OH/C CURING WORK	LS	398.8730	3.00	1,196.62	3.00	1.000	3.00	1,196.62	1.52
O-03-CONS-001	OH/C CONSUMABLES	LS	398.8730	2.00	797.75	2.00	1.000	2.00	797.75	1.01

Group : 5 **ATT**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-01-ANT-010	Providing and Applying Antitermite Treatment	Sqft	1,208.7049	12.00	14,503.02	36.36	1.000	36.36	14,503.02	18.36

Group : 6 **LDPE**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
E-10-MIS-223.1	LDPE SHEET	Sqft	1,208.7049	2.00	2,417.17	6.06	1.000	6.06	2,417.17	3.06
L-01-PAP-010	Labour charges for laying LDPE sheet	Sqft	1,208.7049	3.00	3,625.76	9.09	1.000	9.09	3,625.76	4.59

1690 **STILT/GROUND FLOOR**

1700 **SUPER STRUCTURE RCC WORK**

1710 **1.2.1.1** **GF- RCC - M20 (1:1.5:3)For Column** **161.439 Cft** **1,385(Net)** **1,385(Gross)** **2,23,593.01(Amt.)** **1.58 %**

Aathiv builds and designs

GF- RCC - M20 (1:1.5:3)For Column

Group : 1 **RCC LABOUR -L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-035	L/C for laying concrete for Column	Cft	161.4390	60.00	9,686.34	60.00	1.000	60.00	9,686.34	4.33

Group : 2 **RCC MATERIAL**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	34.7094	335.00	11,628.45	72.03	1.000	72.03	11,628.45	5.20
A-02-AGG-02-004	M SAND (BLACK)	Cft	65.0761	55.00	3,579.10	22.17	1.000	22.17	3,579.10	1.60
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	130.1521	45.00	5,857.01	36.28	1.000	36.28	5,857.01	2.62
A-04-CHM-003	ADMIXTURE	KG	10.2675	80.00	821.72	5.09	1.000	5.09	821.72	0.37

Group : 3 **RCC MACHINE**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	0.5327	2,500.00	1,331.87	8.25	1.000	8.25	1,331.87	0.60
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.5327	500.00	266.37	1.65	1.000	1.65	266.37	0.12

Group : 4 **RCC CONSUMABLES**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	161.4390	1.00	161.44	1.00	1.000	1.00	161.44	0.07
O-01-CUR-001	OH/C CURING WORK	LS	161.4390	3.00	484.32	3.00	1.000	3.00	484.32	0.22
O-03-CONS-001	OH/C CONSUMABLES	LS	161.4390	2.00	322.88	2.00	1.000	2.00	322.88	0.14

Group : 5 **Shuttering Labour-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-002	L/c- Column Shuttering	Sft	726.4755	17.00	12,350.08	76.50	1.000	76.50	12,350.08	5.52

Group : 6 **Shuttering material-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-005	S/c- Column Shuttering material Cost	Sft	726.4755	20.00	14,529.51	90.00	1.000	90.00	14,529.51	6.50

Group : 7 **MACHINERY and CONSUMA**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	161.4390	1.00	161.44	1.00	1.000	1.00	161.44	0.07
O-03-CONS-001	OH/C CONSUMABLES	LS	161.4390	2.00	322.88	2.00	1.000	2.00	322.88	0.14

Group : 8 **STEEL MATERIAL**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	1,493.3108	80.00	1,19,464.86	740.00	1.000	740.00	1,19,464.86	53.43
A-03-REF-03	BINDING WIRE	KG	44.7993	100.00	4,479.93	27.75	1.000	27.75	4,479.93	2.00
A-05-COV-011	COVER BLOCK	NO	373.3277	2.00	747.46	4.63	1.000	4.63	747.46	0.33

Group : 9 **STEEL LABOUR-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	1,493.3108	25.00	37,332.77	231.25	1.000	231.25	37,332.77	16.70

1720 1.2.1.2 GF- RCC - M20 (1:1.5:3)For Sill - 3" 22.993 Cft 451(Net) 451(Gross) 10,369.84(Amt.) 0.07 %

GF- RCC - M20 (1:1.5:3)For Sill - 3"

Group : 1 **RCC MACHINE**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	0.0759	2,500.00	189.69	8.25	1.000	8.25	189.69	1.83
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.0759	500.00	37.94	1.65	1.000	1.65	37.94	0.37

Group : 2 **RCC LABOUR -L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-090	L/c for laying concrete for Sill	Cft	22.9930	45.00	1,034.69	45.00	1.000	45.00	1,034.69	9.98

Group : 3 **RCC MATERIAL**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	4.9435	335.00	1,656.19	72.03	1.000	72.03	1,656.19	15.97
A-02-AGG-02-004	M SAND (BLACK)	Cft	9.2685	55.00	509.75	22.17	1.000	22.17	509.75	4.92
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	18.5370	45.00	834.19	36.28	1.000	36.28	834.19	8.04
A-04-CHM-003	ADMIXTURE	KG	1.4624	80.00	117.03	5.09	1.000	5.09	117.03	1.13

Group : 4 **RCC CONSUMABLES**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	22.9930	1.00	22.99	1.00	1.000	1.00	22.99	0.22
O-01-CUR-001	OH/C CURING WORK	LS	22.9930	3.00	68.98	3.00	1.000	3.00	68.98	0.67
O-03-CONS-001	OH/C CONSUMABLES	LS	22.9930	2.00	45.99	2.00	1.000	2.00	45.99	0.44

Group : 5 **Shuttering Labour-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-090	Labour charges for shuttering of Sill	Sft	57.4825	0.00	0.00	0.00	1.000	0.00	0.00	0.00

Group : 6 **Shuttering material-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-020	S/c- DPC/Sill/Coping Shuttering material Cost	Sft	57.4825	15.00	862.24	37.50	1.000	37.50	862.24	8.31

Group : 7 **STEEL MATERIAL**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	45.9860	80.00	3,678.88	160.00	1.000	160.00	3,678.88	35.48
A-03-REF-03	BINDING WIRE	KG	1.3796	100.00	137.96	6.00	1.000	6.00	137.96	1.33
A-05-COV-011	COVER BLOCK	NO	11.4965	2.00	22.99	1.00	1.000	1.00	22.99	0.22

Group : 8 **STEEL LABOUR-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	45.9860	25.00	1,149.65	50.00	1.000	50.00	1,149.65	11.09

1730 1.2.1.3 GF- RCC - M20 (1:1.5:3)For Lintel 45.987 Cft 685(Net) 685(Gross) 31,501.10(Amt.) 0.22 %

GF- RCC - M20 (1:1.5:3)For Lintel

Group : 1 **RCC MACHINE**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	0.1518	2,500.00	379.39	8.25	1.000	8.25	379.39	1.20
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.1518	500.00	75.88	1.65	1.000	1.65	75.88	0.24

Group : 2 **RCC LABOUR -L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-065	L/c for laying concrete for Lintel	Cft	45.9870	45.00	2,069.42	45.00	1.000	45.00	2,069.42	6.57

Group : 3 **RCC MATERIAL**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	9.8872	335.00	3,312.44	72.03	1.000	72.03	3,312.44	10.52
A-02-AGG-02-004	M SAND (BLACK)	Cft	18.5374	55.00	1,019.53	22.17	1.000	22.17	1,019.53	3.24
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	37.0747	45.00	1,668.41	36.28	1.000	36.28	1,668.41	5.30
A-04-CHM-003	ADMIXTURE	KG	2.9248	80.00	234.07	5.09	1.000	5.09	234.07	0.74

Group : 4 **RCC CONSUMABLES**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	45.9870	1.00	45.99	1.00	1.000	1.00	45.99	0.15
O-01-CUR-001	OH/C CURING WORK	LS	45.9870	3.00	137.96	3.00	1.000	3.00	137.96	0.44
O-03-CONS-001	OH/C CONSUMABLES	LS	45.9870	2.00	91.97	2.00	1.000	2.00	91.97	0.29

Group : 5 **Shuttering Labour-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-065	L/c- Lintel Shuttering	Sft	114.9675	25.00	2,874.19	62.50	1.000	62.50	2,874.19	9.12

Group : 6 **Shuttering material-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%

K-05-SHU-025	S/c- Lintel Shuttering material Cost	Sft	114.9675	25.00	2,874.19	62.50	1.000	62.50	2,874.19	9.12

Group : 7 STEEL MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	154.0565	80.00	12,324.52	268.00	1.000	268.00	12,324.52	39.12
A-03-REF-03	BINDING WIRE	KG	4.6217	100.00	462.17	10.05	1.000	10.05	462.17	1.47
A-05-COV-011	COVER BLOCK	NO	38.5141	2.00	77.26	1.68	1.000	1.68	77.26	0.25

Group : 8 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	154.0565	25.00	3,851.41	83.75	1.000	83.75	3,851.41	12.23

1740 1.2.1.4 GF- RCC - M20 (1:1.5:3)For Loft & Sunshade 36.000 Sft 217(Net) 217(Gross) 7,812.00(Amt.) 0.06 %

GF- RCC - M20 (1:1.5:3)For Kitchen Table top,Low roof,Loft and Sunshade

Group : 1 RCC MACHINE

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	0.0288	2,500.00	72.00	2.00	1.000	2.00	72.00	0.92
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.0288	500.00	14.40	0.40	1.000	0.40	14.40	0.18

Group : 2 RCC LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-065	L/c for laying concrete for Lintel	Cft	36.0000	45.00	1,620.00	45.00	1.000	45.00	1,620.00	20.74

Group : 3 RCC MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	1.9368	335.00	648.72	18.02	1.000	18.02	648.72	8.30
A-02-AGG-02-004	M SAND (BLACK)	Cft	3.6288	55.00	199.44	5.54	1.000	5.54	199.44	2.55
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	7.2576	45.00	326.52	9.07	1.000	9.07	326.52	4.18
A-04-CHM-003	ADMIXTURE	KG	0.5724	80.00	45.72	1.27	1.000	1.27	45.72	0.59

Group : 4 RCC CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	36.0000	1.00	36.00	1.00	1.000	1.00	36.00	0.46
O-01-CUR-001	OH/C CURING WORK	LS	36.0000	3.00	108.00	3.00	1.000	3.00	108.00	1.38
O-03-CONS-001	OH/C CONSUMABLES	LS	36.0000	2.00	72.00	2.00	1.000	2.00	72.00	0.92

Group : 5 Shuttering material-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-030	S/c- Loft / sunshade /kitchen table Shuttering material Cost	Sft	36.0000	25.00	900.00	25.00	1.000	25.00	900.00	11.52

Group : 6 Shuttering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-037	L/c- Loft / sunshade /kitchen table Shuttering	Sft	36.0000	23.00	828.00	23.00	1.000	23.00	828.00	10.60

Group : 7 STEEL MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	27.0000	80.00	2,160.00	60.00	1.000	60.00	2,160.00	27.65

A-03-REF-03	BINDING WIRE	KG	0.8100	100.00	81.00	2.25	1.000	2.25	81.00	1.04
A-05-COV-011	COVER BLOCK	NO	6.7500	2.00	13.68	0.38	1.000	0.38	13.68	0.18

Group : 8 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	27.0000	25.00	675.00	18.75	1.000	18.75	675.00	8.64

1750 1.2.1.5 GF- RCC - M20 (1:1.5:3)For Staircase 152.375 Sft 420(Net) 420(Gross) 63,997.50(Amt.) 0.45 %

GF- RCC - M20 (1:1.5:3)For Staircase

Group : 1 Shuttering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-050	L/c- Staircase Shuttering	Sft	228.5625	60.00	13,713.75	90.00	1.000	90.00	13,713.75	21.43

Group : 2 Shuttering material-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-035	S/c- Staircase Shuttering material Cost	Sft	228.5625	50.00	11,428.13	75.00	1.000	75.00	11,428.13	17.86

Group : 3 RCC LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-050	L/c for laying concrete for Staircase	Cft	62.4738	50.00	3,123.69	20.50	1.000	20.50	3,123.69	4.88

Group : 4 RCC MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	13.4395	335.00	4,502.68	29.55	1.000	29.55	4,502.68	7.04

A-02-AGG-02-004	M SAND (BLACK)	Cft	25.1876	55.00	1,385.09	9.09	1.000	9.09	1,385.09	2.16
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	50.3752	45.00	2,267.34	14.88	1.000	14.88	2,267.34	3.54
A-04-CHM-003	ADMIXTURE	KG	3.9770	80.00	318.46	2.09	1.000	2.09	318.46	0.50

Group : 5 RCC MACHINE

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	0.2133	2,500.00	533.31	3.50	1.000	3.50	533.31	0.83
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.2133	500.00	106.66	0.70	1.000	0.70	106.66	0.17

Group : 6 RCC CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	152.3750	1.00	152.38	1.00	1.000	1.00	152.38	0.24
O-01-CUR-001	OH/C CURING WORK	LS	152.3750	3.00	457.13	3.00	1.000	3.00	457.13	0.71
O-03-CONS-001	OH/C CONSUMABLES	LS	152.3750	2.00	304.75	2.00	1.000	2.00	304.75	0.48

Group : 7 STEEL MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	228.5625	80.00	18,285.00	120.00	1.000	120.00	18,285.00	28.57
A-03-REF-03	BINDING WIRE	KG	6.8569	100.00	685.69	4.50	1.000	4.50	685.69	1.07
A-05-COV-011	COVER BLOCK	NO	57.1406	2.00	114.28	0.75	1.000	0.75	114.28	0.18

Group : 8 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%

L-02-REF-005	L/C for reinforcement work	KG	228.5625	25.00	5,714.06	37.50	1.000	37.50	5,714.06	8.93

Group : 9 CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-01-CUR-001	OH/C CURING WORK	LS	152.3750	3.00	457.13	3.00	1.000	3.00	457.13	0.71
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	152.3750	1.00	152.38	1.00	1.000	1.00	152.38	0.24
O-03-CONS-001	OH/C CONSUMABLES	LS	152.3750	2.00	304.75	2.00	1.000	2.00	304.75	0.48

1755 1.2.1.6 GF- RCC - M20 Roof Beam using RMC 264.687 Cft 895(Net) 895(Gross) 2,36,894.87(Amt.) 1.67 %

GF- RCC - M20 Roof Beam using RMC

Group : 1 Shuttering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-105	L/c- Roof Beam Shuttering	Sft	899.9358	17.00	15,298.91	57.80	1.000	57.80	15,298.91	6.46

Group : 2 Shuttering material-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-040	S/c- Roof beam Shuttering material Cost	Sft	899.9358	30.00	26,998.07	102.00	1.000	102.00	26,998.07	11.40

Group : 3 STEEL MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	1,323.4350	80.00	1,05,874.80	400.00	1.000	400.00	1,05,874.80	44.69
A-03-REF-03	BINDING WIRE	KG	39.7030	100.00	3,970.31	15.00	1.000	15.00	3,970.31	1.68
A-05-COV-011	COVER BLOCK	NO	330.8588	2.00	661.72	2.50	1.000	2.50	661.72	0.28

Group : 4 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	1,323.4350	25.00	33,085.88	125.00	1.000	125.00	33,085.88	13.97

Group : 5 RCC LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-180	L/C for RMC Concrete laying using Pump	Cft	264.6870	15.00	3,970.31	15.00	1.000	15.00	3,970.31	1.68

Group : 6 RCC RMC MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-02-RMC-01-031	READYMIX CONCRETE M 20 GRADE	Cft	264.6870	160.00	42,349.92	160.00	1.000	160.00	42,349.92	17.88
M-01-PUM-02	CONCRETE PUMP	Cft	264.6870	5.00	1,323.44	5.00	1.000	5.00	1,323.44	0.56

Group : 7 RCC MACHINERY

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.8735	500.00	436.73	1.65	1.000	1.65	436.73	0.18

Group : 8 RCC CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	264.6870	1.00	264.69	1.00	1.000	1.00	264.69	0.11
O-01-CUR-001	OH/C CURING WORK	LS	264.6870	3.00	794.06	3.00	1.000	3.00	794.06	0.34
O-03-CONS-001	OH/C CONSUMABLES	LS	264.6870	2.00	529.37	2.00	1.000	2.00	529.37	0.22
O-03-CONS-005	OH/C Lead and Lift	LS	264.6870	5.00	1,323.44	5.00	1.000	5.00	1,323.44	0.56

1760 1.2.1.7 GF- RCC - M20 Roof slab using RMC 406.123 Cft 563(Net) 563(Gross) 2,28,647.25(Amt.) 1.62 %

Aathiv builds and designs

GF- RCC - M20 Roof slab using RMC

Group : 1 Shuttering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-100	L/c- Roof Slab Shuttering	Sft	990.5340	25.00	24,765.38	60.98	1.000	60.98	24,765.38	10.83

Group : 2 Shuttering material-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-045	S/c- Roof Slab Shuttering material Cost	Sft	990.5340	20.00	19,810.68	48.78	1.000	48.78	19,810.68	8.66

Group : 3 STEEL MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	974.6952	80.00	77,975.62	192.00	1.000	192.00	77,975.62	34.10
A-03-REF-03	BINDING WIRE	KG	29.2409	100.00	2,924.09	7.20	1.000	7.20	2,924.09	1.28
A-05-COV-011	COVER BLOCK	NO	243.6738	2.00	487.35	1.20	1.000	1.20	487.35	0.21

Group : 4 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	974.6952	25.00	24,367.38	60.00	1.000	60.00	24,367.38	10.66

Group : 5 RCC LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-180	L/C for RMC Concrete laying using Pump	Cft	406.1230	15.00	6,091.85	15.00	1.000	15.00	6,091.85	2.66

Group : 6 RCC RMC MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%

A-02-RMC-01-031	READYMIX CONCRETE M 20 GRADE	Cft	406.1230	160.00	64,979.68	160.00	1.000	160.00	64,979.68	28.42
M-01-PUM-02	CONCRETE PUMP	Cft	406.1230	5.00	2,030.62	5.00	1.000	5.00	2,030.62	0.89

Group : 7 RCC MACHINERY

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	1.3402	500.00	670.10	1.65	1.000	1.65	670.10	0.29

Group : 8 RCC CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	406.1230	1.00	406.12	1.00	1.000	1.00	406.12	0.18
O-01-CUR-001	OH/C CURING WORK	LS	406.1230	3.00	1,218.37	3.00	1.000	3.00	1,218.37	0.53
O-03-CONS-001	OH/C CONSUMABLES	LS	406.1230	2.00	812.25	2.00	1.000	2.00	812.25	0.36
O-03-CONS-005	OH/C Lead and Lift	LS	406.1230	5.00	2,030.62	5.00	1.000	5.00	2,030.62	0.89

1765 MASONRY WORK

1770 1.2.2.1 GF- 9" Brick work - Red brick with CM 1:6 Upto Roof level 583.825 Cft 267(Net) 267(Gross) 1,55,881.28(Amt.) 1.10 %

GF- 9" Brick work - Red brick with CM 1:6 Upto Roof level

Group : 1 MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	30.7092	335.00	10,287.00	17.62	1.000	17.62	10,287.00	6.60
A-02-AGG-02-004	M SAND (BLACK)	Cft	268.7346	55.00	14,782.45	25.32	1.000	25.32	14,782.45	9.48

A-02-BRK-02-006	RED BRICK (9" X 3" X 4")	NO	8,173.5500	12.00	98,082.60	168.00	1.000	168.00	98,082.60	62.92

Group : 2 LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-04-MAS-155	L/c for 9" brick masonry	Cft	583.8250	50.00	29,191.25	50.00	1.000	50.00	29,191.25	18.73

Group : 3 CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-01-CUR-001	OH/C CURING WORK	LS	583.8250	3.00	1,751.48	3.00	1.000	3.00	1,751.48	1.12
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	583.8250	1.00	583.83	1.00	1.000	1.00	583.83	0.37
O-03-CONS-001	OH/C CONSUMABLES	LS	583.8250	2.00	1,167.65	2.00	1.000	2.00	1,167.65	0.75

1775 1.2.2.2 GF- 4.5" Brick work - Red brick with CM 1:4 Upto Roof level 194.253 Sft 119(Net) 119(Gross) 23,116.11(Amt.) 0.16 %

GF- 4.5" Brick work - Red brick with CM 1:4 Upto Roof level

Group : 1 4.5" BW LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-04-MAS-160	L/c for 4.5" brick masonry	Sft	194.2530	35.00	6,798.86	35.00	1.000	35.00	6,798.86	29.41

Group : 2 4.5" BW MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	4.2153	335.00	1,412.22	7.27	1.000	7.27	1,412.22	6.11

A-02-AGG-02-004	M SAND (BLACK)	Cft	26.3407	55.00	1,449.13	7.46	1.000	7.46	1,449.13	6.27
A-02-BRK-02-006	RED BRICK (9" X 3" X 4")	NO	1,019.8282	12.00	12,237.94	63.00	1.000	63.00	12,237.94	52.94

Group : 3 BW CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-01-CUR-001	OH/C CURING WORK	LS	194.2530	3.00	582.76	3.00	1.000	3.00	582.76	2.52
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	194.2530	1.00	194.25	1.00	1.000	1.00	194.25	0.84
O-03-CONS-001	OH/C CONSUMABLES	LS	194.2530	2.00	388.51	2.00	1.000	2.00	388.51	1.68

1785 PLASTREING WORK

1800 1.2.3.1 GF-Celing Plastering - 12mm thik - 1:4 1,324.692 Sft 47(Net) 47(Gross) 62,260.52(Amt.) 0.44 %

GF-Celing Plastering - 12mm thik - 1:4

Group : 1 CELING PLASTERING LABO

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-05-INT-010	L/c for Internal ceiling plaster	Sft	1,324.6920	25.00	33,117.30	25.00	1.000	25.00	33,117.30	53.19
L-07-MIS-035	L/c for pointing for plastering work	Sft	1,324.6920	3.00	3,974.08	3.00	1.000	3.00	3,974.08	6.38

Group : 2 CELING PLASTERING MATE

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	18.2807	335.00	6,120.08	4.62	1.000	4.62	6,120.08	9.83
A-02-AGG-02-006	P SAND (PLASTER)	Cft	114.3209	65.00	7,431.52	5.61	1.000	5.61	7,431.52	11.94

Group : 3 CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-01-CUR-001	OH/C CURING WORK	LS	1,324.6920	3.00	3,974.08	3.00	1.000	3.00	3,974.08	6.38
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	1,324.6920	1.00	1,324.69	1.00	1.000	1.00	1,324.69	2.13
O-03-CONS-001	OH/C CONSUMABLES	LS	1,324.6920	2.00	2,649.38	2.00	1.000	2.00	2,649.38	4.26
R-01-SCA-005	Providing and fixing of Scaffolding Cost	Sft	1,324.6920	3.00	3,974.08	3.00	1.000	3.00	3,974.08	6.38

1810 1.2.3.2 GF-Internal Plastering - 18mm thik - 1:5 1,619.000 Sft 44(Net) 44(Gross) 71,236.00(Amt.) 0.50 %

GF-Internal Plastering - 18mm thik - 1:5

Group : 1 WALL PLASTERING LABOU

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-05-INT-015	L/c for Internal Wall plaster	Sft	1,619.0000	23.00	37,237.00	23.00	1.000	23.00	37,237.00	52.27

Group : 2 WALL PLASTERING MATER

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	23.1517	335.00	7,755.01	4.79	1.000	4.79	7,755.01	10.89
A-02-AGG-02-006	P SAND (PLASTER)	Cft	173.7187	65.00	11,284.43	6.97	1.000	6.97	11,284.43	15.84

Group : 3 CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-01-CUR-001	OH/C CURING WORK	LS	1,619.0000	3.00	4,857.00	3.00	1.000	3.00	4,857.00	6.82
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	1,619.0000	1.00	1,619.00	1.00	1.000	1.00	1,619.00	2.27

R-01-SCA-005	Providing and fixing of Scaffolding Cost	Sft	1,619.0000	3.00	4,857.00	3.00	1.000	3.00	4,857.00	6.82
O-03-CONS-001	OH/C CONSUMABLES	LS	1,619.0000	2.00	3,238.00	2.00	1.000	2.00	3,238.00	4.55

1820 1.2.3.3 GF-External Plastering - 18mm thik - 1:5 1,328.580 Sft 46(Net) 46(Gross) 61,114.68(Amt.) 0.43 %

GF-External Plastering - 18mm thik - 1:5

Group : 1 WALL PLASTERING LABOU

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-06-EXT-005	L/c for external plaster	Sft	1,328.5800	25.00	33,214.50	25.00	1.000	25.00	33,214.50	54.35

Group : 2 WALL PLASTERING MATER

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	18.9987	335.00	6,363.90	4.79	1.000	4.79	6,363.90	10.41
A-02-AGG-02-006	P SAND (PLASTER)	Cft	142.5566	65.00	9,260.20	6.97	1.000	6.97	9,260.20	15.15

Group : 3 CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-01-CUR-001	OH/C CURING WORK	LS	1,328.5800	3.00	3,985.74	3.00	1.000	3.00	3,985.74	6.52
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	1,328.5800	1.00	1,328.58	1.00	1.000	1.00	1,328.58	2.17
O-03-CONS-001	OH/C CONSUMABLES	LS	1,328.5800	2.00	2,657.16	2.00	1.000	2.00	2,657.16	4.35
R-01-SCA-005	Providing and fixing of Scaffolding Cost	Sft	1,328.5800	3.00	3,985.74	3.00	1.000	3.00	3,985.74	6.52

1830 GRILL WORKS

1840 1.2.4.1 GF-Staircase SS Hand rail works 27.000 Rft 1,003(Net) 1,003(Gross) 27,081.00(Amt.) 0.19 %

GF-Staircase SS Hand rail works

Group : 1 SS handrail Material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-30-FAB-041	Providing & fabricating work for SS Hand Railing	Rft	27.0000	1,000.00	27,000.00	1,000.00	1.000	1,000.00	27,000.00	99.70

Group : 2 Other Consumables

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	27.0000	1.00	27.00	1.00	1.000	1.00	27.00	0.10
O-03-CONS-001	OH/C CONSUMABLES	LS	27.0000	2.00	54.00	2.00	1.000	2.00	54.00	0.20

1850 DOOR WORKS

1860 1.2.5.1 GF-Teak door for Main door 24.500 Sft 2,328(Net) 2,328(Gross) 57,036.00(Amt.) 0.40 %

GF-Teak door for Main door

Group : 1 Wood works

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-06-A-01	Teak Wood Door Frame	Cft	3.2732	3,500.00	11,456.20	467.60	1.000	467.60	11,456.20	20.09
B-06-A-02	Teak Door Shutter	Cft	4.0915	3,500.00	14,320.25	584.50	1.000	584.50	14,320.25	25.11
B-06-B-01	Door lense	Nos	1.1662	350.00	408.17	16.66	1.000	16.66	408.17	0.72
B-06-B-02	6" Hinges	Nos	6.9997	500.00	3,499.83	142.85	1.000	142.85	3,499.83	6.14
B-06-B-03	8" Handle Front	Nos	1.1662	2,500.00	2,915.50	119.00	1.000	119.00	2,915.50	5.11
B-06-B-04	6" Handle Back	Nos	1.1662	1,000.00	1,166.20	47.60	1.000	47.60	1,166.20	2.04
B-06-B-05	Main door Lock	Nos	1.1662	12,000.00	13,994.40	571.20	1.000	571.20	13,994.40	24.54

B-06-B-06	8" Tower bolt	Nos	1.1662	750.00	874.65	35.70	1.000	35.70	874.65	1.53
B-06-B-07	Door stoper	Nos	1.1662	350.00	408.17	16.66	1.000	16.66	408.17	0.72
B-06-B-08	Frame Clamps	Nos	6.9997	100.00	699.97	28.57	1.000	28.57	699.97	1.23
B-06-B-09	Nails and other consumables for Wooderen works	Ls	1.1662	1,000.00	1,166.20	47.60	1.000	47.60	1,166.20	2.04
L-53-OTH-085	L/c For Woodern frame fixing and paking (Door, Window)	Sft	24.5000	50.00	1,225.00	50.00	1.000	50.00	1,225.00	2.15
L-53-OTH-090	L/c For Woodern Shutter and fitting fixing carpentry works	Sqft	24.5000	200.00	4,900.00	200.00	1.000	200.00	4,900.00	8.59

1870 1.2.5.2 GF-Wood frame with flush door shutter for Bed room door 42.000 Sft 920(Net) 920(Gross) 38,640.00(Amt.) 0.27 %

GF-Wood frame with flush door shutter for Bed room door

Group : 1 Wood works

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-06-A-05	Wood Door/window Frame (Padauh, Neam, Vengai)	Cft	2.8056	2,000.00	5,611.20	133.60	1.000	133.60	5,611.20	14.52
B-06-A-15	Redymade Flush Door Shutter	Sqft	42.0000	285.00	11,970.00	285.00	1.000	285.00	11,970.00	30.98
B-06-B-02	6" Hinges	Nos	11.9700	500.00	5,985.00	142.50	1.000	142.50	5,985.00	15.49
B-06-B-03	8" Handle Front	Nos	2.1000	2,500.00	5,250.00	125.00	1.000	125.00	5,250.00	13.59
B-06-B-04	6" Handle Back	Nos	2.1000	1,000.00	2,100.00	50.00	1.000	50.00	2,100.00	5.43
B-06-B-06	8" Tower bolt	Nos	2.1000	750.00	1,575.00	37.50	1.000	37.50	1,575.00	4.08
B-06-B-07	Door stoper	Nos	2.1000	350.00	735.00	17.50	1.000	17.50	735.00	1.90
B-06-B-08	Frame Clamps	Nos	11.9700	100.00	1,197.00	28.50	1.000	28.50	1,197.00	3.10
B-06-B-09	Nails and other consumables for Wooderen works	Ls	2.1000	1,000.00	2,100.00	50.00	1.000	50.00	2,100.00	5.43
L-53-OTH-085	L/c For Woodern frame fixing and paking (Door, Window)	Sft	42.0000	50.00	2,100.00	50.00	1.000	50.00	2,100.00	5.43

1880 1.2.5.3 GF-WPC door for Toilet 35.000 Sft 713(Net) 713(Gross) 24,955.00(Amt.) 0.18 %

GF-UPVC door for Toilet

Group : 1 WPC Door Subcontract -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-12-FLD-015	S&F WPC Door Frame with shutter	Sft	43.7500	570.00	24,937.50	712.50	1.000	712.50	24,937.50	99.93

1890 JOINERY WORKS

1900 1.2.6.1 GF-UPVC Winodw with safey grill 156.000 Sft 695(Net) 695(Gross) 1,08,420.00(Amt.) 0.77 %

GF-UPVC Winodw with safey grill

Group : 1 UPVC works

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-16-A-01	Supply & Fixing of UPVC Sliding window	Sft	156.0000	470.00	73,320.00	470.00	1.000	470.00	73,320.00	67.63

Group : 2 MS Grill window/door/Vent S

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-30-FAB-040	Providing & fabricating and fixing work for M.S. Grill	Kg	234.0000	150.00	35,100.00	225.00	1.000	225.00	35,100.00	32.37

1910 1.2.6.2 GF-UPVC Ventilator with excahust 4.000 Sft 600(Net) 600(Gross) 2,400.00(Amt.) 0.02 %

GF-UPVC Ventilator with excahust

Group : 1 Sub contract-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%

K-16-B-05	Supply & Fixing of UPVC Ventilator with Louver and exhaust	Sft	4.0000	600.00	2,400.00	600.00	1.000	600.00	2,400.00	100.00

1920 **FLOORING WORKS**

1930 **1.2.7.1** **GF- Staircase Italian marble** **226.500 Sft** **759(Net)** **759(Gross)** **1,71,913.50(Amt.)** **1.21 %**

GF- Staircase Italian marble

Group : 1 **Granite Material**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-02-MAR-01-002	MARBLE ITALIAN	SQFT	249.1500	600.00	1,49,490.00	660.00	1.000	660.00	1,49,490.00	86.96
A-01-CEM-01-001	CEMENT	BAG	6.5685	335.00	2,201.58	9.72	1.000	9.72	2,201.58	1.28
A-02-AGG-02-004	M SAND (BLACK)	Cft	49.2638	55.00	2,708.94	11.96	1.000	11.96	2,708.94	1.58
A-04-CHM-048	Jiont grouting filler for Grainte and tile works	KG	11.3250	45.00	509.63	2.25	1.000	2.25	509.63	0.30

Group : 2 **Granite Labour-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-10-GRN-002	L/c for Step Granite laying Work	Sqft	249.1500	40.00	9,966.00	44.00	1.000	44.00	9,966.00	5.80
L-10-MIS-002	L/c for Pointing and Clening in flooring surface	Sft	249.1500	3.00	747.45	3.30	1.000	3.30	747.45	0.43
L-10-GRN-004	L/c for Granite Full Nosing work	Rft	90.6000	70.00	6,342.00	28.00	1.000	28.00	6,342.00	3.69

1940 **1.2.7.2** **GF-Parking tile flooring for Portico** **779.875 Sft** **155(Net)** **155(Gross)** **1,20,880.63(Amt.)** **0.85 %**

GF-Parking tile flooring for Portico

Aathiv builds and designs

Group : 1 **Flooring Material**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-01-MIS-015	Parking / Portico Cement Tile	Sft	857.8625	100.00	85,786.25	110.00	1.000	110.00	85,786.25	70.97
A-01-CEM-01-001	CEMENT	BAG	26.2818	335.00	8,804.79	11.29	1.000	11.29	8,804.79	7.28
A-02-AGG-02-004	M SAND (BLACK)	Cft	131.4089	55.00	7,229.44	9.27	1.000	9.27	7,229.44	5.98
A-04-CHM-048	Jiont grouting filler for Grainte and tile works	KG	12.3220	45.00	553.71	0.71	1.000	0.71	553.71	0.46

Group : 2 **Flooring Labour-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-10-VIT-005	L/c Portico tile Laying	Sft	779.8750	20.00	15,597.50	20.00	1.000	20.00	15,597.50	12.90
L-10-MIS-002	L/c for Pointing and Clening in flooring surface	Sft	779.8750	3.00	2,339.63	3.00	1.000	3.00	2,339.63	1.94
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	779.8750	1.00	779.88	1.00	1.000	1.00	779.88	0.65

1950 1.2.7.3 GF-Hall and Room flooring 181.417 Sft 155(Net) 155(Gross) 28,119.64(Amt.) 0.20 %

GF-Hall and Room flooring

Group : 1 **Tile Flooring Material**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-01-VIT-01-005	VITRIFIED TILE 24" X 24"	Sft	199.5587	100.00	19,955.87	110.00	1.000	110.00	19,955.87	70.97
A-01-CEM-01-001	CEMENT	BAG	6.1138	335.00	2,048.20	11.29	1.000	11.29	2,048.20	7.28
A-02-AGG-02-004	M SAND (BLACK)	Cft	30.5688	55.00	1,681.74	9.27	1.000	9.27	1,681.74	5.98

A-04-CHM-048	Jiont grouting filler for Grainte and tile works	KG	2.8664	45.00	128.81	0.71	1.000	0.71	128.81	0.46

Group : 2 Tile Flooring Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-10-VIT-001	L/c for vertified tile laying work	Sft	181.4170	20.00	3,628.34	20.00	1.000	20.00	3,628.34	12.90
L-10-MIS-002	L/c for Pointing and Clening in flooring surface	Sft	181.4170	3.00	544.25	3.00	1.000	3.00	544.25	1.94
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	181.4170	1.00	181.42	1.00	1.000	1.00	181.42	0.65

1960 1.2.7.4 GF-Toilet anti skid tile flooring 29.250 Sft 155(Net) 155(Gross) 4,533.75(Amt.) 0.03 %

GF-Toilet anti skid tile flooring

Group : 1 Tile Flooring Material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-01-VIT-01-004	VITRIFIED TILE 12" X 12"	Sft	32.1750	100.00	3,217.50	110.00	1.000	110.00	3,217.50	70.97
A-01-CEM-01-001	CEMENT	BAG	0.9857	335.00	330.23	11.29	1.000	11.29	330.23	7.28
A-02-AGG-02-004	M SAND (BLACK)	Cft	4.9286	55.00	271.15	9.27	1.000	9.27	271.15	5.98
A-04-CHM-048	Jiont grouting filler for Grainte and tile works	KG	0.4622	45.00	20.77	0.71	1.000	0.71	20.77	0.46

Group : 2 Tile Flooring Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-10-VIT-001	L/c for vertified tile laying work	Sft	29.2500	20.00	585.00	20.00	1.000	20.00	585.00	12.90
L-10-MIS-002	L/c for Pointing and Clening in flooring surface	Sft	29.2500	3.00	87.75	3.00	1.000	3.00	87.75	1.94

O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	29.2500	1.00	29.25	1.00	1.000	1.00	29.25	0.65

1970 1.2.7.5 GF-Toilet full wall tile 202.500 Sft 150(Net) 150(Gross) 30,375.00(Amt.) 0.21 %

GF-Toilet full wall tile

Group : 1 Wall tile Material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-01-VIT-01-006	VITRIFIED WALL TILE	Sft	222.7500	100.00	22,275.00	110.00	1.000	110.00	22,275.00	73.33
A-01-CEM-01-001	CEMENT	BAG	5.8725	335.00	1,968.30	9.72	1.000	9.72	1,968.30	6.48
A-02-AGG-02-004	M SAND (BLACK)	Cft	22.0320	55.00	1,210.95	5.98	1.000	5.98	1,210.95	3.99
A-04-CHM-048	Jiont grouting filler for Grainte and tile works	KG	3.1995	45.00	143.78	0.71	1.000	0.71	143.78	0.47

Group : 2 Wall tile Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-10-VIT-010	L/c Wall Tile Laying	Sft	202.5000	20.00	4,050.00	20.00	1.000	20.00	4,050.00	13.33
L-10-MIS-002	L/c for Pointing and Clening in flooring surface	Sft	202.5000	3.00	607.50	3.00	1.000	3.00	607.50	2.00
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	202.5000	1.00	202.50	1.00	1.000	1.00	202.50	0.67

2020 PAINTING WORKS

2030 1.2.8.1 GF-Inner celing painting 1,324.000 Sft 21(Net) 21(Gross) 27,804.00(Amt.) 0.20 %

GF-Inner celing (White wash - 2 coat, primer-1, Emultion-2)

Group : 1 In.Paint Material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PT-001	White cement	Kg	72.8200	17.00	1,244.56	0.94	1.000	0.94	1,244.56	4.48
B-03-PT-002	Interior Primer	Ltr	11.2540	120.00	1,350.48	1.02	1.000	1.02	1,350.48	4.86
B-03-PT-004	Interior Emultion	Ltr	24.2292	500.00	12,114.60	9.15	1.000	9.15	12,114.60	43.57

Group : 2 In.Paint Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-11-INT-001	L/c for Int.paint White cement per coat	Sft	1,324.0000	2.10	2,780.40	2.10	1.000	2.10	2,780.40	10.00
L-11-INT-004	L/c for In.Paint Celing primer per coat	Sft	1,324.0000	2.10	2,780.40	2.10	1.000	2.10	2,780.40	10.00
L-11-INT-015	L/c for In.Paint Celing Emultion per coat	Sft	2,648.0000	2.30	6,090.40	4.60	1.000	4.60	6,090.40	21.90
L-07-MIS-040	Labour charges for Celing Surface Cleaning work	Sft	1,324.0000	1.00	1,324.00	1.00	1.000	1.00	1,324.00	4.76

Group : 3 In.paint Accessories

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PTH-010	4" Brush	NO	1.4564	250.00	370.72	0.28	1.000	0.28	370.72	1.33
B-03-PTO-007	Waste cloth	Kg	1.4564	80.00	119.16	0.09	1.000	0.09	119.16	0.43
B-03-PTH-045	Crack putty plate	NO	1.3240	25.00	39.72	0.03	1.000	0.03	39.72	0.14
B-03-PTH-060	6" Putty plate	NO	0.3972	85.00	39.72	0.03	1.000	0.03	39.72	0.14

2040 1.2.8.2 GF-inner wall painting 1,619.000 Sft 30(Net) 30(Gross) 48,570.00(Amt.) 0.34 %

GF-inner wall (Putty - 2 coat, Primer-1 coat, Emultion - 2 coat)

Group : 1 In.Paint Material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PT-006	Interior wall putty	kg	161.9000	25.00	4,047.50	2.50	1.000	2.50	4,047.50	8.33

B-03-PT-002	Interior Primer	Ltr	13.7615	120.00	1,651.38	1.02	1.000	1.02	1,651.38	3.40
B-03-PT-004	Interior Emultion	Ltr	29.6277	500.00	14,813.85	9.15	1.000	9.15	14,813.85	30.50

Group : 2 **In.Paint Labour-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-11-INT-030	L/c for In.Paint Wall putty per coat	Sft	3,238.0000	2.50	8,095.00	5.00	1.000	5.00	8,095.00	16.67
L-11-INT-005	L/c for Int.paint Wall primer per coat	Sft	1,619.0000	2.10	3,399.90	2.10	1.000	2.10	3,399.90	7.00
L-11-INT-020	L/c for In.Paint Wall Emultion per coat	Sft	3,238.0000	2.30	7,447.40	4.60	1.000	4.60	7,447.40	15.33
L-07-MIS-045	Labour charges for Wall Surface Cleaning work	Sft	1,619.0000	1.00	1,619.00	1.00	1.000	1.00	1,619.00	3.33

Group : 3 **In.paint Accessories**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PTH-010	4" Brush	NO	1.7809	250.00	453.32	0.28	1.000	0.28	453.32	0.93
B-03-PTH-035	9" Roller	NO	0.9714	260.00	259.04	0.16	1.000	0.16	259.04	0.53
B-03-PTH-045	Crack putty plate	NO	1.6190	25.00	48.57	0.03	1.000	0.03	48.57	0.10
B-03-PTH-070	12" Putty plate	NO	0.4857	130.00	64.76	0.04	1.000	0.04	64.76	0.13
B-03-PTH-065	8" Putty plate	NO	0.4857	100.00	48.57	0.03	1.000	0.03	48.57	0.10
B-03-PTH-060	6" Putty plate	NO	0.4857	85.00	48.57	0.03	1.000	0.03	48.57	0.10
B-03-PTO-007	Waste cloth	Kg	1.7809	80.00	145.71	0.09	1.000	0.09	145.71	0.30
B-03-PTO-003	POLISH PAPER - Emerry sheet - 180	NO	8.0950	20.00	161.90	0.10	1.000	0.10	161.90	0.33
B-03-PTO-009	POP	Kg	1.6190	25.00	48.57	0.03	1.000	0.03	48.57	0.10

Group : 4 **Other**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%

O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	1,619.0000	1.00	1,619.00	1.00	1.000	1.00	1,619.00	3.33
R-01-SCA-005	Providing and fixing of Scaffolding Cost	Sft	1,619.0000	3.00	4,857.00	3.00	1.000	3.00	4,857.00	10.00

2050 1.2.8.3 GF-Exterier wall painting 1,328.000 Sft 31(Net) 31(Gross) 41,168.00(Amt.) 0.29 %

GF-Exterier wall (White wash - 2 coat, Primer-1 coat, Emultion - 2 coat)

Group : 1 Ext.Paint Material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PT-001	White cement	Kg	73.0400	17.00	1,248.32	0.94	1.000	0.94	1,248.32	3.03
B-03-PT-003	Exterior Primer	Ltr	18.3264	200.00	3,665.28	2.76	1.000	2.76	3,665.28	8.90
B-03-PT-005	Exterior Emultion	Ltr	32.4032	600.00	19,441.92	14.64	1.000	14.64	19,441.92	47.23

Group : 2 Ext.Paint Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-11-EXT-001	L/c for Ext.paint White cement per coat	Sft	2,656.0000	2.15	5,710.40	4.30	1.000	4.30	5,710.40	13.87
L-11-EXT-005	L/c for Ext.paint Wall primer per coat	Sft	1,328.0000	2.15	2,855.20	2.15	1.000	2.15	2,855.20	6.94
L-11-EXT-015	L/c for Ext.paint Emultion per coat	Sft	2,656.0000	2.20	5,843.20	4.40	1.000	4.40	5,843.20	14.19
L-07-MIS-045	Labour charges for Wall Surface Cleaning work	Sft	1,328.0000	1.00	1,328.00	1.00	1.000	1.00	1,328.00	3.23

Group : 3 Ext.paint Accessories

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PTH-010	4" Brush	NO	1.4608	250.00	371.84	0.28	1.000	0.28	371.84	0.90
B-03-PTH-045	Crack putty plate	NO	1.3280	25.00	39.84	0.03	1.000	0.03	39.84	0.10
B-03-PTH-060	6" Putty plate	NO	0.3984	85.00	39.84	0.03	1.000	0.03	39.84	0.10

B-03-PTO-007	Waste cloth	Kg	1.4608	80.00	119.52	0.09	1.000	0.09	119.52	0.29
B-03-PTO-009	POP	Kg	1.3280	25.00	39.84	0.03	1.000	0.03	39.84	0.10

2060 1.2.8.4 GF-Wood/Grill Painting 186.000 Sft 25(Net) 25(Gross) 4,650.00(Amt.) 0.03 %

GF-Grill Painting(Zinc.primer-2 + Enamal paint 2)

Group : 1 Gril. painting Material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PT-011	Enamal Paint	Lit	2.6598	300.00	797.94	4.29	1.000	4.29	797.94	17.16
B-03-PT-010	Zinchromate primer	Lit	1.3206	120.00	158.10	0.85	1.000	0.85	158.10	3.40
B-03-PTO-005	THINNER	LTR	1.3206	90.00	119.04	0.64	1.000	0.64	119.04	2.56

Group : 2 Grill Painting Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-11-INT-007	L/c for In.Paint Zink primer per coat	Sft	186.0000	5.25	976.50	5.25	1.000	5.25	976.50	21.00
L-11-INT-045	L/c for In.Paint Enamal paint (Grill two side) per coat	Sft	372.0000	7.00	2,604.00	14.00	1.000	14.00	2,604.00	56.00

Group : 3 Grill Painting Accessories

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PTH-075	18 no Flat brush	NO	0.0930	100.00	9.30	0.05	1.000	0.05	9.30	0.20
B-03-PTH-080	20 no Flat brush	NO	0.0930	120.00	11.16	0.06	1.000	0.06	11.16	0.24
B-03-PTO-001	POLISH PAPER - Emerry sheet - 100	NO	0.9300	20.00	18.60	0.10	1.000	0.10	18.60	0.40
B-03-PTO-007	Waste cloth	Kg	0.0930	80.00	7.44	0.04	1.000	0.04	7.44	0.16

2070	**1.2.8.5**	**GF-Main door polish work painting**	**57.750 Sft**	**114(Net)**	**114(Gross)**	**6,583.50(Amt.)** **0.05 %**

GF-Main door polish work painting

Group : 1 MATRIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PT-012	Melamine teak wood Polish	Lit	1.4438	150.00	216.56	3.75	1.000	3.75	216.56	3.29

Group : 2 LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-11-POL-005	L/c for Pol. Melamine POLISH FINSIH	Sft	57.7500	110.00	6,352.50	110.00	1.000	110.00	6,352.50	96.49

2080		**ELECTRICAL & PLUMBING WORKS**				
2090	**1.2.9.1**	**GF-supply and fixing of Electrical Subcontract works**	**1,274.000 Sft**	**152(Net)**	**152(Gross)**	**1,93,648.00(Amt.)** **1.37 %**

GF-supply and fixing of Electrical Subcontract works

Group : 1 Electrical works material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
D-08-ELE-A-005	25mm HMS PVC Conduit Pipe (Slab & Walls)	Rft	573.3000	25.00	14,332.50	11.25	1.000	11.25	14,332.50	7.40
D-08-ELE-A-010	20mm HMS PVC Conduit Pipe (Point Wiring)	Rft	254.8000	21.00	5,350.80	4.20	1.000	4.20	5,350.80	2.76
D-08-ELE-B-005	1.0 sq.mm Wire (Light/Fan Points - Green/Red/Black)	Coils	10.1920	2,300.00	23,441.60	18.40	1.000	18.40	23,441.60	12.11
D-08-ELE-B-010	1.5 sq.mm Wire (Primary Circuits/Sockets)	Coils	5.0960	3,000.00	15,288.00	12.00	1.000	12.00	15,288.00	7.89
D-08-ELE-B-015	2.5 sq.mm Wire (Power Points/ Geyser)	Coils	3.8220	5,200.00	19,874.40	15.60	1.000	15.60	19,874.40	10.26

D-08-ELE-B-020	4.0 sq.mm Wire (Main Line/ AC)	Coils	2.5480	7,500.00	19,110.00	15.00	1.000	15.00	19,110.00	9.87
D-08-ELE-C-005	12 Module Metal Box (Main Switch Board)	Nos	3.8220	250.00	955.50	0.75	1.000	0.75	955.50	0.49
D-08-ELE-C-010	8 Module Metal Box (Bedrooms/Kitchen)	Nos	5.0960	180.00	917.28	0.72	1.000	0.72	917.28	0.47
D-08-ELE-C-015	6 Module Metal Box (Utility/ AC)	Nos	5.0960	150.00	764.40	0.60	1.000	0.60	764.40	0.39
D-08-ELE-C-020	3/2/1 Module Metal Box (Single points/Calling bell)	Nos	15.2880	80.00	1,223.04	0.96	1.000	0.96	1,223.04	0.63
D-08-ELE-D-005	6A One-way Switch	Nos	57.3300	65.00	3,732.82	2.93	1.000	2.93	3,732.82	1.93
D-08-ELE-D-010	6A 3-pin Socket	Nos	22.9320	120.00	2,751.84	2.16	1.000	2.16	2,751.84	1.42
D-08-ELE-D-015	16A/25A Power Socket with Switch	Nos	7.6440	350.00	2,675.40	2.10	1.000	2.10	2,675.40	1.38
D-08-ELE-D-020	Fan Regulator (2-module step type)	Nos	6.3700	250.00	1,592.50	1.25	1.000	1.25	1,592.50	0.82
D-08-ELE-E-005	8-12 Way Double Door DB Box	Nos	1.2740	8,000.00	10,192.00	8.00	1.000	8.00	10,192.00	5.26
D-08-ELE-E-010	63A DP RCCB (30mA for safety)	Nos	1.2740	2,200.00	2,802.80	2.20	1.000	2.20	2,802.80	1.45
D-08-ELE-E-015	63A FP Isolator	Nos	1.2740	950.00	1,210.30	0.95	1.000	0.95	1,210.30	0.63
D-08-ELE-E-020	6A/10A/16A/25A Single Pole MCB	Nos	1.2740	350.00	445.90	0.35	1.000	0.35	445.90	0.23
D-08-ELE-F-005	PVC Junction Boxes (Deep/ Surface)	Nos	57.3300	25.00	1,439.62	1.13	1.000	1.13	1,439.62	0.74
D-08-ELE-F-015	PVC Bend (25mm/20mm)	Nos	76.4400	15.00	1,146.60	0.90	1.000	0.90	1,146.60	0.59
D-08-ELE-F-020	Solvent Cement (100ml)	Nos	2.5480	120.00	305.76	0.24	1.000	0.24	305.76	0.16
D-08-ELE-F-025	Insulation Tape (Assorted colors)	Nos	12.7400	30.00	382.20	0.30	1.000	0.30	382.20	0.20

D-08-ELE-F-030	Flexible Pipe (for drops)	Rft	38.2200	12.00	458.64	0.36	1.000	0.36	458.64	0.24

Group : 2 Electrical Labor

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-31-ELE-020	L/C for Ele - Roof slab conduiting pipe laying works	Nos	6.3700	1,000.00	6,370.00	5.00	1.000	5.00	6,370.00	3.29
L-31-ELE-025	L/C for Ele - Wall Pipe and Mettal box fixing works	Nos	16.9442	1,000.00	16,944.20	13.30	1.000	13.30	16,944.20	8.75
L-31-ELE-030	L/C for Ele - Wiring works	Nos	12.7400	1,000.00	12,740.00	10.00	1.000	10.00	12,740.00	6.58
L-31-ELE-035	L/C for Ele - Swtiches & socket assamble and fixing works	Nos	10.5742	1,000.00	10,574.20	8.30	1.000	8.30	10,574.20	5.46
L-31-ELE-040	L/C for Ele - DB Board fixing & Wiring works	Nos	4.2042	1,000.00	4,204.20	3.30	1.000	3.30	4,204.20	2.17
L-31-ELE-045	L/C for Ele - Service connection and Testing works	Nos	4.2042	1,000.00	4,204.20	3.30	1.000	3.30	4,204.20	2.17
L-31-ELE-050	L/C for Ele - Light, fan, motor and orther fitting works	Nos	4.2042	1,000.00	4,204.20	3.30	1.000	3.30	4,204.20	2.17
L-31-ELE-055	L/C for Ele - other miscellaneous works	Nos	4.2042	1,000.00	4,204.20	3.30	1.000	3.30	4,204.20	2.17

2100 1.2.9.2 GF-supply and fixing of plumbing Subcontract works 1,274.000 Sft 210(Net) 210(Gross) 2,67,540.00(Amt.) 1.89 %

GF-supply and fixing of plumbing Subcontract works

Group : 1 Plumbingwork subcontract-

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-00-SUB-005	Plumbing Work Subcontract Labour	Sft	1,274.0000	50.00	63,700.00	50.00	1.000	50.00	63,700.00	23.81
K-00-SUB-006	Plumbing Work Subcontract Material	Sft	1,274.0000	160.00	2,03,840.00	160.00	1.000	160.00	2,03,840.00	76.19

2200 **FIRST FLOOR**

2210 **SUPER STRUCTURE RCC WORK**

2220 **1.3.1.1** **FF- RCC - M20 (1:1.5:3)For Column** **161.719 Cft** **1,385(Net)** **1,385(Gross)** **2,23,980.82(Amt.)** **1.58 %**

FF- RCC - M20 (1:1.5:3)For Column

Group : 1 **RCC LABOUR -L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-035	L/C for laying concrete for Column	Cft	161.7190	60.00	9,703.14	60.00	1.000	60.00	9,703.14	4.33

Group : 2 **RCC MATERIAL**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	34.7696	335.00	11,648.62	72.03	1.000	72.03	11,648.62	5.20
A-02-AGG-02-004	M SAND (BLACK)	Cft	65.1889	55.00	3,585.31	22.17	1.000	22.17	3,585.31	1.60
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	130.3779	45.00	5,867.17	36.28	1.000	36.28	5,867.17	2.62
A-04-CHM-003	ADMIXTURE	KG	10.2853	80.00	823.15	5.09	1.000	5.09	823.15	0.37

Group : 3 **RCC MACHINE**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	0.5337	2,500.00	1,334.18	8.25	1.000	8.25	1,334.18	0.60
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.5337	500.00	266.84	1.65	1.000	1.65	266.84	0.12

Group : 4 **RCC CONSUMABLES**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	161.7190	1.00	161.72	1.00	1.000	1.00	161.72	0.07
O-01-CUR-001	OH/C CURING WORK	LS	161.7190	3.00	485.16	3.00	1.000	3.00	485.16	0.22
O-03-CONS-001	OH/C CONSUMABLES	LS	161.7190	2.00	323.44	2.00	1.000	2.00	323.44	0.14

Group : 5 Shuttering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-002	L/c- Column Shuttering	Sft	727.7355	17.00	12,371.50	76.50	1.000	76.50	12,371.50	5.52

Group : 6 Shuttering material-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-005	S/c- Column Shuttering material Cost	Sft	727.7355	20.00	14,554.71	90.00	1.000	90.00	14,554.71	6.50

Group : 7 MACHINERY and CONSUMA

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	161.7190	1.00	161.72	1.00	1.000	1.00	161.72	0.07
O-03-CONS-001	OH/C CONSUMABLES	LS	161.7190	2.00	323.44	2.00	1.000	2.00	323.44	0.14

Group : 8 STEEL MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	1,495.9008	80.00	1,19,672.06	740.00	1.000	740.00	1,19,672.06	53.43
A-03-REF-03	BINDING WIRE	KG	44.8770	100.00	4,487.70	27.75	1.000	27.75	4,487.70	2.00
A-05-COV-011	COVER BLOCK	NO	373.9752	2.00	748.76	4.63	1.000	4.63	748.76	0.33

Group : 9 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	1,495.9008	25.00	37,397.52	231.25	1.000	231.25	37,397.52	16.70

2230 1.3.1.2 FF- RCC - M20 (1:1.5:3)For Sill - 3" 39.731 Cft 451(Net) 451(Gross) 17,918.68(Amt.) 0.13 %

FF- RCC - M20 (1:1.5:3)For Sill - 3"

Group : 1 RCC MACHINE

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	0.1311	2,500.00	327.78	8.25	1.000	8.25	327.78	1.83
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.1311	500.00	65.56	1.65	1.000	1.65	65.56	0.37

Group : 2 RCC LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-090	L/c for laying concrete for Sill	Cft	39.7310	45.00	1,787.90	45.00	1.000	45.00	1,787.90	9.98

Group : 3 RCC MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	8.5422	335.00	2,861.82	72.03	1.000	72.03	2,861.82	15.97
A-02-AGG-02-004	M SAND (BLACK)	Cft	16.0156	55.00	880.84	22.17	1.000	22.17	880.84	4.92
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	32.0311	45.00	1,441.44	36.28	1.000	36.28	1,441.44	8.04
A-04-CHM-003	ADMIXTURE	KG	2.5269	80.00	202.23	5.09	1.000	5.09	202.23	1.13

Group : 4 RCC CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	39.7310	1.00	39.73	1.00	1.000	1.00	39.73	0.22
O-01-CUR-001	OH/C CURING WORK	LS	39.7310	3.00	119.19	3.00	1.000	3.00	119.19	0.67
O-03-CONS-001	OH/C CONSUMABLES	LS	39.7310	2.00	79.46	2.00	1.000	2.00	79.46	0.44

Group : 5 Shuttering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-090	Labour charges for shuttering of Sill	Sft	99.3275	0.00	0.00	0.00	1.000	0.00	0.00	0.00

Group : 6 Shuttering material-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-020	S/c- DPC/Sill/Coping Shuttering material Cost	Sft	99.3275	15.00	1,489.91	37.50	1.000	37.50	1,489.91	8.31

Group : 7 STEEL MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	79.4620	80.00	6,356.96	160.00	1.000	160.00	6,356.96	35.48
A-03-REF-03	BINDING WIRE	KG	2.3839	100.00	238.39	6.00	1.000	6.00	238.39	1.33
A-05-COV-011	COVER BLOCK	NO	19.8655	2.00	39.73	1.00	1.000	1.00	39.73	0.22

Group : 8 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	79.4620	25.00	1,986.55	50.00	1.000	50.00	1,986.55	11.09

2240 1.3.1.3 FF - RCC - M20 (1:1.5:3)For Lintel 79.464 Cft 685(Net) 685(Gross) 54,432.84(Amt.) 0.38 %

Aathiv builds and designs

FF - RCC - M20 (1:1.5:3)For Lintel

Group : 1 RCC MACHINE

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	0.2622	2,500.00	655.58	8.25	1.000	8.25	655.58	1.20
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.2622	500.00	131.12	1.65	1.000	1.65	131.12	0.24

Group : 2 RCC LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-065	L/c for laying concrete for Lintel	Cft	79.4640	45.00	3,575.88	45.00	1.000	45.00	3,575.88	6.57

Group : 3 RCC MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	17.0848	335.00	5,723.79	72.03	1.000	72.03	5,723.79	10.52
A-02-AGG-02-004	M SAND (BLACK)	Cft	32.0319	55.00	1,761.72	22.17	1.000	22.17	1,761.72	3.24
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	64.0639	45.00	2,882.95	36.28	1.000	36.28	2,882.95	5.30
A-04-CHM-003	ADMIXTURE	KG	5.0539	80.00	404.47	5.09	1.000	5.09	404.47	0.74

Group : 4 RCC CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	79.4640	1.00	79.46	1.00	1.000	1.00	79.46	0.15
O-01-CUR-001	OH/C CURING WORK	LS	79.4640	3.00	238.39	3.00	1.000	3.00	238.39	0.44
O-03-CONS-001	OH/C CONSUMABLES	LS	79.4640	2.00	158.93	2.00	1.000	2.00	158.93	0.29

Group : 5 **Shuttering Labour-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-065	L/c- Lintel Shuttering	Sft	198.6600	25.00	4,966.50	62.50	1.000	62.50	4,966.50	9.12

Group : 6 **Shuttering material-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-025	S/c- Lintel Shuttering material Cost	Sft	198.6600	25.00	4,966.50	62.50	1.000	62.50	4,966.50	9.12

Group : 7 **STEEL MATERIAL**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	266.2044	80.00	21,296.35	268.00	1.000	268.00	21,296.35	39.12
A-03-REF-03	BINDING WIRE	KG	7.9861	100.00	798.61	10.05	1.000	10.05	798.61	1.47
A-05-COV-011	COVER BLOCK	NO	66.5511	2.00	133.50	1.68	1.000	1.68	133.50	0.25

Group : 8 **STEEL LABOUR-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	266.2044	25.00	6,655.11	83.75	1.000	83.75	6,655.11	12.23

2250 1.3.1.4 FF- RCC - M20 (1:1.5:3)For Kitchen Table top,Loft & Sunshade 178.000 Sft 217(Net) 217(Gross) 38,626.00(Amt.) 0.27 %

GF- RCC - M20 (1:1.5:3)For Kitchen Table top,Low roof,Loft and Sunshade

Group : 1 **RCC MACHINE**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	0.1424	2,500.00	356.00	2.00	1.000	2.00	356.00	0.92

R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.1424	500.00	71.20	0.40	1.000	0.40	71.20	0.18

Group : 2 RCC LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-065	L/c for laying concrete for Lintel	Cft	178.0000	45.00	8,010.00	45.00	1.000	45.00	8,010.00	20.74

Group : 3 RCC MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	9.5764	335.00	3,207.56	18.02	1.000	18.02	3,207.56	8.30
A-02-AGG-02-004	M SAND (BLACK)	Cft	17.9424	55.00	986.12	5.54	1.000	5.54	986.12	2.55
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	35.8848	45.00	1,614.46	9.07	1.000	9.07	1,614.46	4.18
A-04-CHM-003	ADMIXTURE	KG	2.8302	80.00	226.06	1.27	1.000	1.27	226.06	0.59

Group : 4 RCC CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	178.0000	1.00	178.00	1.00	1.000	1.00	178.00	0.46
O-01-CUR-001	OH/C CURING WORK	LS	178.0000	3.00	534.00	3.00	1.000	3.00	534.00	1.38
O-03-CONS-001	OH/C CONSUMABLES	LS	178.0000	2.00	356.00	2.00	1.000	2.00	356.00	0.92

Group : 5 Shuttering material-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-030	S/c- Loft / sunshade /kitchen table Shuttering material Cost	Sft	178.0000	25.00	4,450.00	25.00	1.000	25.00	4,450.00	11.52

Group : 6 Shuttering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-037	L/c- Loft / sunshade /kitchen table Shuttering	Sft	178.0000	23.00	4,094.00	23.00	1.000	23.00	4,094.00	10.60

Group : 7 STEEL MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	133.5000	80.00	10,680.00	60.00	1.000	60.00	10,680.00	27.65
A-03-REF-03	BINDING WIRE	KG	4.0050	100.00	400.50	2.25	1.000	2.25	400.50	1.04
A-05-COV-011	COVER BLOCK	NO	33.3750	2.00	67.64	0.38	1.000	0.38	67.64	0.18

Group : 8 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	133.5000	25.00	3,337.50	18.75	1.000	18.75	3,337.50	8.64

2260 1.3.1.5 FF - RCC - M20 (1:1.5:3)For Staircase 152.375 Sft 420(Net) 420(Gross) 63,997.50(Amt.) 0.45 %

FF - RCC - M20 (1:1.5:3)For Staircase

Group : 1 Shuttering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-050	L/c- Staircase Shuttering	Sft	228.5625	60.00	13,713.75	90.00	1.000	90.00	13,713.75	21.43

Group : 2 Shuttering material-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-035	S/c- Staircase Shuttering material Cost	Sft	228.5625	50.00	11,428.13	75.00	1.000	75.00	11,428.13	17.86

Group : 3 RCC LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-050	L/c for laying concrete for Staircase	Cft	62.4738	50.00	3,123.69	20.50	1.000	20.50	3,123.69	4.88

Group : 4 RCC MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	13.4395	335.00	4,502.68	29.55	1.000	29.55	4,502.68	7.04
A-02-AGG-02-004	M SAND (BLACK)	Cft	25.1876	55.00	1,385.09	9.09	1.000	9.09	1,385.09	2.16
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	50.3752	45.00	2,267.34	14.88	1.000	14.88	2,267.34	3.54
A-04-CHM-003	ADMIXTURE	KG	3.9770	80.00	318.46	2.09	1.000	2.09	318.46	0.50

Group : 5 RCC MACHINE

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	0.2133	2,500.00	533.31	3.50	1.000	3.50	533.31	0.83
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.2133	500.00	106.66	0.70	1.000	0.70	106.66	0.17

Group : 6 RCC CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	152.3750	1.00	152.38	1.00	1.000	1.00	152.38	0.24
O-01-CUR-001	OH/C CURING WORK	LS	152.3750	3.00	457.13	3.00	1.000	3.00	457.13	0.71
O-03-CONS-001	OH/C CONSUMABLES	LS	152.3750	2.00	304.75	2.00	1.000	2.00	304.75	0.48

Group : 7 STEEL MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	228.5625	80.00	18,285.00	120.00	1.000	120.00	18,285.00	28.57
A-03-REF-03	BINDING WIRE	KG	6.8569	100.00	685.69	4.50	1.000	4.50	685.69	1.07
A-05-COV-011	COVER BLOCK	NO	57.1406	2.00	114.28	0.75	1.000	0.75	114.28	0.18

Group : 8 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	228.5625	25.00	5,714.06	37.50	1.000	37.50	5,714.06	8.93

Group : 9 CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-01-CUR-001	OH/C CURING WORK	LS	152.3750	3.00	457.13	3.00	1.000	3.00	457.13	0.71
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	152.3750	1.00	152.38	1.00	1.000	1.00	152.38	0.24
O-03-CONS-001	OH/C CONSUMABLES	LS	152.3750	2.00	304.75	2.00	1.000	2.00	304.75	0.48

2270 1.3.1.6 FF - RCC - M20 Roof Beam using RMC 264.687 Cft 895(Net) 895(Gross) 2,36,894.87(Amt.) 1.67 %

FF - RCC - M20 Roof Beam using RMC

Group : 1 Shuttering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-105	L/c- Roof Beam Shuttering	Sft	899.9358	17.00	15,298.91	57.80	1.000	57.80	15,298.91	6.46

Group : 2 Shuttering material-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-040	S/c- Roof beam Shuttering material Cost	Sft	899.9358	30.00	26,998.07	102.00	1.000	102.00	26,998.07	11.40

Group : 3 **STEEL MATERIAL**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	1,323.4350	80.00	1,05,874.80	400.00	1.000	400.00	1,05,874.80	44.69
A-03-REF-03	BINDING WIRE	KG	39.7030	100.00	3,970.31	15.00	1.000	15.00	3,970.31	1.68
A-05-COV-011	COVER BLOCK	NO	330.8588	2.00	661.72	2.50	1.000	2.50	661.72	0.28

Group : 4 **STEEL LABOUR-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	1,323.4350	25.00	33,085.88	125.00	1.000	125.00	33,085.88	13.97

Group : 5 **RCC LABOUR -L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-180	L/C for RMC Concrete laying using Pump	Cft	264.6870	15.00	3,970.31	15.00	1.000	15.00	3,970.31	1.68

Group : 6 **RCC RMC MATERIAL**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-02-RMC-01-031	READYMIX CONCRETE M 20 GRADE	Cft	264.6870	160.00	42,349.92	160.00	1.000	160.00	42,349.92	17.88
M-01-PUM-02	CONCRETE PUMP	Cft	264.6870	5.00	1,323.44	5.00	1.000	5.00	1,323.44	0.56

Group : 7 **RCC MACHINERY**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.8735	500.00	436.73	1.65	1.000	1.65	436.73	0.18

Group : 8 **RCC CONSUMABLES**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%

O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	264.6870	1.00	264.69	1.00	1.000	1.00	264.69	0.11
O-01-CUR-001	OH/C CURING WORK	LS	264.6870	3.00	794.06	3.00	1.000	3.00	794.06	0.34
O-03-CONS-001	OH/C CONSUMABLES	LS	264.6870	2.00	529.37	2.00	1.000	2.00	529.37	0.22
O-03-CONS-005	OH/C Lead and Lift	LS	264.6870	5.00	1,323.44	5.00	1.000	5.00	1,323.44	0.56

2280 1.3.1.7 FF - RCC - M20 Roof slab using RMC 428.792 Cft 563(Net) 563(Gross) 2,41,409.90(Amt.) 1.71 %

FF - RCC - M20 Roof slab using RMC

Group : 1 Shuttering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-100	L/c- Roof Slab Shuttering	Sft	1,045.8237	25.00	26,147.74	60.98	1.000	60.98	26,147.74	10.83

Group : 2 Shuttering material-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-045	S/c- Roof Slab Shuttering material Cost	Sft	1,045.8237	20.00	20,916.47	48.78	1.000	48.78	20,916.47	8.66

Group : 3 STEEL MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	1,029.1008	80.00	82,328.06	192.00	1.000	192.00	82,328.06	34.10
A-03-REF-03	BINDING WIRE	KG	30.8730	100.00	3,087.30	7.20	1.000	7.20	3,087.30	1.28
A-05-COV-011	COVER BLOCK	NO	257.2752	2.00	514.55	1.20	1.000	1.20	514.55	0.21

Group : 4 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	1,029.1008	25.00	25,727.52	60.00	1.000	60.00	25,727.52	10.66

Group : 5 **RCC LABOUR -L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-180	L/C for RMC Concrete laying using Pump	Cft	428.7920	15.00	6,431.88	15.00	1.000	15.00	6,431.88	2.66

Group : 6 **RCC RMC MATERIAL**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-02-RMC-01-031	READYMIX CONCRETE M 20 GRADE	Cft	428.7920	160.00	68,606.72	160.00	1.000	160.00	68,606.72	28.42
M-01-PUM-02	CONCRETE PUMP	Cft	428.7920	5.00	2,143.96	5.00	1.000	5.00	2,143.96	0.89

Group : 7 **RCC MACHINERY**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	1.4150	500.00	707.51	1.65	1.000	1.65	707.51	0.29

Group : 8 **RCC CONSUMABLES**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	428.7920	1.00	428.79	1.00	1.000	1.00	428.79	0.18
O-01-CUR-001	OH/C CURING WORK	LS	428.7920	3.00	1,286.38	3.00	1.000	3.00	1,286.38	0.53
O-03-CONS-001	OH/C CONSUMABLES	LS	428.7920	2.00	857.58	2.00	1.000	2.00	857.58	0.36
O-03-CONS-005	OH/C Lead and Lift	LS	428.7920	5.00	2,143.96	5.00	1.000	5.00	2,143.96	0.89

2290 **MASONRY WORK**

2300 **1.3.2.1** **FF- 9" Brick work - Red brick with CM 1:6 Upto Roof level** **873.379 Cft** **267(Net)** **267(Gross)** **2,33,192.19(Amt.)** **1.65 %**

FF- 9" Brick work - Red brick with CM 1:6 Upto Roof level

Group : 1 MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	45.9397	335.00	15,388.94	17.62	1.000	17.62	15,388.94	6.60
A-02-AGG-02-004	M SAND (BLACK)	Cft	402.0164	55.00	22,113.96	25.32	1.000	25.32	22,113.96	9.48
A-02-BRK-02-006	RED BRICK (9" X 3" X 4")	NO	12,227.3060	12.00	1,46,727.67	168.00	1.000	168.00	1,46,727.67	62.92

Group : 2 LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-04-MAS-155	L/c for 9" brick masonry	Cft	873.3790	50.00	43,668.95	50.00	1.000	50.00	43,668.95	18.73

Group : 3 CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-01-CUR-001	OH/C CURING WORK	LS	873.3790	3.00	2,620.14	3.00	1.000	3.00	2,620.14	1.12
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	873.3790	1.00	873.38	1.00	1.000	1.00	873.38	0.37
O-03-CONS-001	OH/C CONSUMABLES	LS	873.3790	2.00	1,746.76	2.00	1.000	2.00	1,746.76	0.75

2310 1.3.2.2 FF- 4.5" Brick work - Red brick with CM 1:4 Upto Roof level 447.590 Sft 119(Net) 119(Gross) 53,263.21(Amt.) 0.38 %

FF- 4.5" Brick work - Red brick with CM 1:4 Upto Roof level

Group : 1 4.5" BW LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-04-MAS-160	L/c for 4.5" brick masonry	Sft	447.5900	35.00	15,665.65	35.00	1.000	35.00	15,665.65	29.41

Group : 2 **4.5" BW MATERIAL**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	9.7127	335.00	3,253.98	7.27	1.000	7.27	3,253.98	6.11
A-02-AGG-02-004	M SAND (BLACK)	Cft	60.6932	55.00	3,339.02	7.46	1.000	7.46	3,339.02	6.27
A-02-BRK-02-006	RED BRICK (9" X 3" X 4")	NO	2,349.8475	12.00	28,198.17	63.00	1.000	63.00	28,198.17	52.94

Group : 3 **BW CONSUMABLES**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-01-CUR-001	OH/C CURING WORK	LS	447.5900	3.00	1,342.77	3.00	1.000	3.00	1,342.77	2.52
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	447.5900	1.00	447.59	1.00	1.000	1.00	447.59	0.84
O-03-CONS-001	OH/C CONSUMABLES	LS	447.5900	2.00	895.18	2.00	1.000	2.00	895.18	1.68

2320 **PLASTREING WORK**

2330 **1.3.3.1** **FF-Celing Plastering - 12mm thik - 1:4** **1,314.115 Sft** **47(Net)** **47(Gross)** **61,763.41(Amt.)** **0.44 %**

FF-Celing Plastering - 12mm thik - 1:4

Group : 1 **CELING PLASTERING LABO**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-05-INT-010	L/c for Internal ceiling plaster	Sft	1,314.1150	25.00	32,852.88	25.00	1.000	25.00	32,852.88	53.19

L-07-MIS-035	L/c for pointing for plastering work	Sft	1,314.1150	3.00	3,942.35	3.00	1.000	3.00	3,942.35	6.38

Group : 2 CELING PLASTERING MATE

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	18.1348	335.00	6,071.21	4.62	1.000	4.62	6,071.21	9.83
A-02-AGG-02-006	P SAND (PLASTER)	Cft	113.4081	65.00	7,372.19	5.61	1.000	5.61	7,372.19	11.94

Group : 3 CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-01-CUR-001	OH/C CURING WORK	LS	1,314.1150	3.00	3,942.35	3.00	1.000	3.00	3,942.35	6.38
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	1,314.1150	1.00	1,314.12	1.00	1.000	1.00	1,314.12	2.13
O-03-CONS-001	OH/C CONSUMABLES	LS	1,314.1150	2.00	2,628.23	2.00	1.000	2.00	2,628.23	4.26
R-01-SCA-005	Providing and fixing of Scaffolding Cost	Sft	1,314.1150	3.00	3,942.35	3.00	1.000	3.00	3,942.35	6.38

2340 1.3.3.2 FF-Internal Plastering - 18mm thik - 1:5 4,309.760 Sft 44(Net) 44(Gross) 1,89,629.44(Amt.) 1.34 %

FF-Internal Plastering - 18mm thik - 1:5

Group : 1 WALL PLASTERING LABOU

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-05-INT-015	L/c for Internal Wall plaster	Sft	4,309.7600	23.00	99,124.48	23.00	1.000	23.00	99,124.48	52.27

Group : 2 WALL PLASTERING MATER

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%

A-01-CEM-01-001	CEMENT	BAG	61.6296	335.00	20,643.75	4.79	1.000	4.79	20,643.75	10.89
A-02-AGG-02-006	P SAND (PLASTER)	Cft	462.4372	65.00	30,039.03	6.97	1.000	6.97	30,039.03	15.84

Group : 3 CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-01-CUR-001	OH/C CURING WORK	LS	4,309.7600	3.00	12,929.28	3.00	1.000	3.00	12,929.28	6.82
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	4,309.7600	1.00	4,309.76	1.00	1.000	1.00	4,309.76	2.27
R-01-SCA-005	Providing and fixing of Scaffolding Cost	Sft	4,309.7600	3.00	12,929.28	3.00	1.000	3.00	12,929.28	6.82
O-03-CONS-001	OH/C CONSUMABLES	LS	4,309.7600	2.00	8,619.52	2.00	1.000	2.00	8,619.52	4.55

2350 1.3.3.3 FF-External Plastering - 18mm thik - 1:5 1,500.000 Sft 46(Net) 46(Gross) 69,000.00(Amt.) 0.49 %

FF-External Plastering - 18mm thik - 1:5

Group : 1 WALL PLASTERING LABOU

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-06-EXT-005	L/c for external plaster	Sft	1,500.0000	25.00	37,500.00	25.00	1.000	25.00	37,500.00	54.35

Group : 2 WALL PLASTERING MATER

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	21.4500	335.00	7,185.00	4.79	1.000	4.79	7,185.00	10.41
A-02-AGG-02-006	P SAND (PLASTER)	Cft	160.9500	65.00	10,455.00	6.97	1.000	6.97	10,455.00	15.15

Group : 3 CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-01-CUR-001	OH/C CURING WORK	LS	1,500.0000	3.00	4,500.00	3.00	1.000	3.00	4,500.00	6.52
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	1,500.0000	1.00	1,500.00	1.00	1.000	1.00	1,500.00	2.17
O-03-CONS-001	OH/C CONSUMABLES	LS	1,500.0000	2.00	3,000.00	2.00	1.000	2.00	3,000.00	4.35
R-01-SCA-005	Providing and fixing of Scaffolding Cost	Sft	1,500.0000	3.00	4,500.00	3.00	1.000	3.00	4,500.00	6.52

2360 **GRILL WORKS**

2370 **1.3.4.1** **FF-Staircase SS Hand rail works** **27.000 Rft** **1,003(Net)** **1,003(Gross)** **27,081.00(Amt.)** **0.19 %**

FF-Staircase SS Hand rail works

Group : 1 **SS handrail Material**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-30-FAB-041	Providing & fabricating work for SS Hand Railing	Rft	27.0000	1,000.00	27,000.00	1,000.00	1.000	1,000.00	27,000.00	99.70

Group : 2 **Other Consumables**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	27.0000	1.00	27.00	1.00	1.000	1.00	27.00	0.10
O-03-CONS-001	OH/C CONSUMABLES	LS	27.0000	2.00	54.00	2.00	1.000	2.00	54.00	0.20

2375 **1.3.4.2** **FF- Balcony Grill Work** **93.520 Sft** **262.50(Net)** **262.50(Gross)** **24,549.00(Amt.)** **0.17 %**

FF- Balcony Grill Work

Group : 1 GrIll work

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-30-FAB-040	Providing & fabricating and fixing work for M.S. Grill	Kg	163.6600	150.00	24,549.00	262.50	1.000	262.50	24,549.00	100.00

2378 1.3.4.3 FF-SS Handrail with Glass 21.000 Rft 2,200.00(Net) 2,200.00(Gross) 46,200.00(Amt.) 0.33 %

FF-SS Handrail with Glass

Group : 1 SS with Glass

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-30-FAB-035	Providing & fabricating work for SS handrail with glass	Rft	21.0000	2,200.00	46,200.00	2,200.00	1.000	2,200.00	46,200.00	100.00

2380 DOOR WORKS

2390 1.3.5.1 FF-Teak door for Main door 21.000 Sft 2,328(Net) 2,328(Gross) 48,888.00(Amt.) 0.35 %

FF-Teak door for Main door

Group : 1 Wood works

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-06-A-01	Teak Wood Door Frame	Cft	2.8056	3,500.00	9,819.60	467.60	1.000	467.60	9,819.60	20.09
B-06-A-02	Teak Door Shutter	Cft	3.5070	3,500.00	12,274.50	584.50	1.000	584.50	12,274.50	25.11
B-06-B-01	Door lense	Nos	0.9996	350.00	349.86	16.66	1.000	16.66	349.86	0.72
B-06-B-02	6" Hinges	Nos	5.9997	500.00	2,999.85	142.85	1.000	142.85	2,999.85	6.14
B-06-B-03	8" Handle Front	Nos	0.9996	2,500.00	2,499.00	119.00	1.000	119.00	2,499.00	5.11
B-06-B-04	6" Handle Back	Nos	0.9996	1,000.00	999.60	47.60	1.000	47.60	999.60	2.04
B-06-B-05	Main door Lock	Nos	0.9996	12,000.00	11,995.20	571.20	1.000	571.20	11,995.20	24.54
B-06-B-06	8" Tower bolt	Nos	0.9996	750.00	749.70	35.70	1.000	35.70	749.70	1.53
B-06-B-07	Door stoper	Nos	0.9996	350.00	349.86	16.66	1.000	16.66	349.86	0.72

B-06-B-08	Frame Clamps	Nos	5.9997	100.00	599.97	28.57	1.000	28.57	599.97	1.23
B-06-B-09	Nails and other consumables for Wooderen works	Ls	0.9996	1,000.00	999.60	47.60	1.000	47.60	999.60	2.04
L-53-OTH-085	L/c For Woodern frame fixing and paking (Door, Window)	Sft	21.0000	50.00	1,050.00	50.00	1.000	50.00	1,050.00	2.15
L-53-OTH-090	L/c For Woodern Shutter and fitting fixing carpentry works	Sqft	21.0000	200.00	4,200.00	200.00	1.000	200.00	4,200.00	8.59

2400 1.3.5.2 FF-Wood frame with flush door shutter for Bed room door 73.500 Sft 920(Net) 920(Gross) 67,620.00(Amt.) 0.48 %

FF-Wood frame with flush door shutter for Bed room door

Group : 1 Wood works

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-06-A-05	Wood Door/window Frame (Padauh, Neam, Vengai)	Cft	4.9098	2,000.00	9,819.60	133.60	1.000	133.60	9,819.60	14.52
B-06-A-15	Redymade Flush Door Shutter	Sqft	73.5000	285.00	20,947.50	285.00	1.000	285.00	20,947.50	30.98
B-06-B-02	6" Hinges	Nos	20.9475	500.00	10,473.75	142.50	1.000	142.50	10,473.75	15.49
B-06-B-03	8" Handle Front	Nos	3.6750	2,500.00	9,187.50	125.00	1.000	125.00	9,187.50	13.59
B-06-B-04	6" Handle Back	Nos	3.6750	1,000.00	3,675.00	50.00	1.000	50.00	3,675.00	5.43
B-06-B-06	8" Tower bolt	Nos	3.6750	750.00	2,756.25	37.50	1.000	37.50	2,756.25	4.08
B-06-B-07	Door stoper	Nos	3.6750	350.00	1,286.25	17.50	1.000	17.50	1,286.25	1.90
B-06-B-08	Frame Clamps	Nos	20.9475	100.00	2,094.75	28.50	1.000	28.50	2,094.75	3.10
B-06-B-09	Nails and other consumables for Wooderen works	Ls	3.6750	1,000.00	3,675.00	50.00	1.000	50.00	3,675.00	5.43
L-53-OTH-085	L/c For Woodern frame fixing and paking (Door, Window)	Sft	73.5000	50.00	3,675.00	50.00	1.000	50.00	3,675.00	5.43

2405 1.3.5.3 FF- UPVC Sliding Door 42.000 Sft 550.00(Net) 550.00(Gross) 23,100.00(Amt.) 0.16 %

FF- UPVC Sliding Door

Group : 1 Door

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-16-C-05	Supply & Fixing of UPVC Sliding DOOR	Sft	42.0000	550.00	23,100.00	550.00	1.000	550.00	23,100.00	100.00

2410 1.3.5.4 FF-WPC door for Toilet 21.000 Sft 570(Net) 570(Gross) 11,970.00(Amt.) 0.08 %

GF-UPVC door for Toilet

Group : 1 WPC Door Subcontract -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-12-FLD-015	S&F WPC Door Frame with shutter	Sft	21.0000	570.00	11,970.00	570.00	1.000	570.00	11,970.00	100.00

2420 JOINERY WORKS

2430 1.3.6.1 FF-French UPVC Winodw with safey grill 144.000 Sft 1,725(Net) 1,725(Gross) 2,48,400.00(Amt.) 1.75 %

FF-French UPVC Winodw with safey grill

Group : 1 UPVC works

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-16-A-01	Supply & Fixing of UPVC Sliding window	Sft	144.0000	1,500.00	2,16,000.00	1,500.00	1.000	1,500.00	2,16,000.00	86.96

Group : 2 MS Grill window/door/Vent S

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-30-FAB-040	Providing & fabricating and fixing work for M.S. Grill	Kg	216.0000	150.00	32,400.00	225.00	1.000	225.00	32,400.00	13.04

2435 1.3.6.2 FF-UPVC Winodw with safey grill 147.500 Sft 695(Net) 695(Gross) 1,02,512.50(Amt.) 0.72 %

FF-UPVC Winodw with safey grill

Group : 1 UPVC works

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-16-A-01	Supply & Fixing of UPVC Sliding window	Sft	147.5000	470.00	69,325.00	470.00	1.000	470.00	69,325.00	67.63

Group : 2 MS Grill window/door/Vent S

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-30-FAB-040	Providing & fabricating and fixing work for M.S. Grill	Kg	221.2500	150.00	33,187.50	225.00	1.000	225.00	33,187.50	32.37

2440 1.3.6.3 FF-UPVC Ventilator with excahust 4.000 Sft 600(Net) 600(Gross) 2,400.00(Amt.) 0.02 %

FF-UPVC Ventilator with excahust

Group : 1 Sub contract-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-16-B-05	Supply & Fixing of UPVC Ventilator with Louver and exhaust	Sft	4.0000	600.00	2,400.00	600.00	1.000	600.00	2,400.00	100.00

2450 FLOORING WORKS

2460 1.3.7.1 FF-Staircase Italian marble 189.125 Sft 759(Net) 759(Gross) 1,43,545.88(Amt.) 1.01 %

FF-Staircase Italian marble

Group : 1 Granite Material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-02-MAR-01-002	MARBLE ITALIAN	SQFT	208.0375	600.00	1,24,822.50	660.00	1.000	660.00	1,24,822.50	86.96
A-01-CEM-01-001	CEMENT	BAG	5.4846	335.00	1,838.30	9.72	1.000	9.72	1,838.30	1.28
A-02-AGG-02-004	M SAND (BLACK)	Cft	41.1347	55.00	2,261.94	11.96	1.000	11.96	2,261.94	1.58
A-04-CHM-048	Jiont grouting filler for Grainte and tile works	KG	9.4563	45.00	425.53	2.25	1.000	2.25	425.53	0.30

Group : 2 Granite Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-10-GRN-002	L/c for Step Granite laying Work	Sqft	208.0375	40.00	8,321.50	44.00	1.000	44.00	8,321.50	5.80
L-10-MIS-002	L/c for Pointing and Clening in flooring surface	Sft	208.0375	3.00	624.11	3.30	1.000	3.30	624.11	0.43
L-10-GRN-004	L/c for Granite Full Nosing work	Rft	75.6500	70.00	5,295.50	28.00	1.000	28.00	5,295.50	3.69

2480 1.3.7.2 FF-Italian marble Flooring 882.442 Sft 759(Net) 759(Gross) 6,69,773.48(Amt.) 4.73 %

FF-Italian marble Flooring

Group : 1 Granite Material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-02-MAR-01-002	MARBLE ITALIAN	SQFT	970.6862	600.00	5,82,411.72	660.00	1.000	660.00	5,82,411.72	86.96
A-01-CEM-01-001	CEMENT	BAG	25.5908	335.00	8,577.34	9.72	1.000	9.72	8,577.34	1.28
A-02-AGG-02-004	M SAND (BLACK)	Cft	191.9311	55.00	10,554.01	11.96	1.000	11.96	10,554.01	1.58
A-04-CHM-048	Jiont grouting filler for Grainte and tile works	KG	44.1221	45.00	1,985.49	2.25	1.000	2.25	1,985.49	0.30

Group : 2 **Granite Labour-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-10-GRN-002	L/c for Step Granite laying Work	Sqft	970.6862	40.00	38,827.45	44.00	1.000	44.00	38,827.45	5.80
L-10-MIS-002	L/c for Pointing and Clening in flooring surface	Sft	970.6862	3.00	2,912.06	3.30	1.000	3.30	2,912.06	0.43
L-10-GRN-004	L/c for Granite Full Nosing work	Rft	352.9768	70.00	24,708.38	28.00	1.000	28.00	24,708.38	3.69

2490 **1.3.7.3** **FF-Toilet anti skid tile flooring** **125.385 Sft** **155(Net)** **155(Gross)** **19,434.68(Amt.)** **0.14 %**

FF-Toilet anti skid tile flooring

Group : 1 **Tile Flooring Material**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-01-VIT-01-004	VITRIFIED TILE 12" X 12"	Sft	137.9235	100.00	13,792.35	110.00	1.000	110.00	13,792.35	70.97
A-01-CEM-01-001	CEMENT	BAG	4.2255	335.00	1,415.60	11.29	1.000	11.29	1,415.60	7.28
A-02-AGG-02-004	M SAND (BLACK)	Cft	21.1274	55.00	1,162.32	9.27	1.000	9.27	1,162.32	5.98
A-04-CHM-048	Jiont grouting filler for Grainte and tile works	KG	1.9811	45.00	89.02	0.71	1.000	0.71	89.02	0.46

Group : 2 **Tile Flooring Labour-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-10-VIT-001	L/c for vertified tile laying work	Sft	125.3850	20.00	2,507.70	20.00	1.000	20.00	2,507.70	12.90
L-10-MIS-002	L/c for Pointing and Clening in flooring surface	Sft	125.3850	3.00	376.16	3.00	1.000	3.00	376.16	1.94
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	125.3850	1.00	125.39	1.00	1.000	1.00	125.39	0.65

2500 1.3.7.4 FF-Toilet full wall tile 176.280 Sft 150(Net) 150(Gross) 26,442.00(Amt.) 0.19 %

FF-Toilet full wall tile

Group : 1 Wall tile Material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-01-VIT-01-006	VITRIFIED WALL TILE	Sft	193.9080	100.00	19,390.80	110.00	1.000	110.00	19,390.80	73.33
A-01-CEM-01-001	CEMENT	BAG	5.1121	335.00	1,713.44	9.72	1.000	9.72	1,713.44	6.48
A-02-AGG-02-004	M SAND (BLACK)	Cft	19.1793	55.00	1,054.15	5.98	1.000	5.98	1,054.15	3.99
A-04-CHM-048	Jiont grouting filler for Grainte and tile works	KG	2.7852	45.00	125.16	0.71	1.000	0.71	125.16	0.47

Group : 2 Wall tile Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-10-VIT-010	L/c Wall Tile Laying	Sft	176.2800	20.00	3,525.60	20.00	1.000	20.00	3,525.60	13.33
L-10-MIS-002	L/c for Pointing and Clening in flooring surface	Sft	176.2800	3.00	528.84	3.00	1.000	3.00	528.84	2.00
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	176.2800	1.00	176.28	1.00	1.000	1.00	176.28	0.67

2510 1.3.7.5 FF-Kitchen above table top full wall tile 132.000 Sft 150(Net) 150(Gross) 19,800.00(Amt.) 0.14 %

FF-Kitchen above table top full wall tile

Group : 1 Wall tile Material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-01-VIT-01-006	VITRIFIED WALL TILE	Sft	145.2000	100.00	14,520.00	110.00	1.000	110.00	14,520.00	73.33

A-01-CEM-01-001	CEMENT	BAG	3.8280	335.00	1,283.04	9.72	1.000	9.72	1,283.04	6.48
A-02-AGG-02-004	M SAND (BLACK)	Cft	14.3616	55.00	789.36	5.98	1.000	5.98	789.36	3.99
A-04-CHM-048	Jiont grouting filler for Grainte and tile works	KG	2.0856	45.00	93.72	0.71	1.000	0.71	93.72	0.47

Group : 2 Wall tile Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-10-VIT-010	L/c Wall Tile Laying	Sft	132.0000	20.00	2,640.00	20.00	1.000	20.00	2,640.00	13.33
L-10-MIS-002	L/c for Pointing and Clening in flooring surface	Sft	132.0000	3.00	396.00	3.00	1.000	3.00	396.00	2.00
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	132.0000	1.00	132.00	1.00	1.000	1.00	132.00	0.67

2520 1.3.7.6 FF-Black Granite for Kitchen table top 91.500 Sft 259(Net) 259(Gross) 23,698.50(Amt.) 0.17 %

FF-Black Granite for Kitchen table top

Group : 1 Kitchen top Granite Material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-02-GRA-01-001	GRANITE BLACK	Sft	100.6500	150.00	15,097.50	165.00	1.000	165.00	15,097.50	63.71
A-01-CEM-01-001	CEMENT	BAG	2.6535	335.00	889.38	9.72	1.000	9.72	889.38	3.75
A-02-AGG-02-004	M SAND (BLACK)	Cft	19.9013	55.00	1,094.34	11.96	1.000	11.96	1,094.34	4.62
A-04-CHM-048	Jiont grouting filler for Grainte and tile works	KG	4.5750	45.00	205.88	2.25	1.000	2.25	205.88	0.87

Group : 2 Kitchen top Granite Labour-

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%

L-10-GRN-003	L/c for Kitchen Table Top Granite laying	Sqft	100.6500	35.00	3,522.75	38.50	1.000	38.50	3,522.75	14.86
L-10-MIS-002	L/c for Pointing and Clening in flooring surface	Sft	100.6500	3.00	301.95	3.30	1.000	3.30	301.95	1.27
L-10-GRN-004	L/c for Granite Full Nosing work	Rft	36.6000	70.00	2,562.00	28.00	1.000	28.00	2,562.00	10.81

2530 1.3.7.7 FF-Kitchen fiber Sink Supply and fixing 1.000 Nos 5,600(Net) 5,600(Gross) 5,600.00(Amt.) 0.04 %

FF-Kitchen fiber Sink Supply and fixing

Group : 1 GF-Kitchen fiber Sink fixing

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
C-09-SNK-007	STAINLESS STEEL SINK 24" X 20" X 8"	NO	1.0000	5,000.00	5,000.00	5,000.00	1.000	5,000.00	5,000.00	89.29
L-54-PLU-003	Labour charges for fixing sink	NO	1.0000	600.00	600.00	600.00	1.000	600.00	600.00	10.71

2540 1.3.7.8 FF- kitchen table top cudupah slab fixing with floor dimmy 114.375 Sft 150(Net) 150(Gross) 17,156.25(Amt.) 0.12 %

FF- kitchen table top cudupah slab fixing with floor dimmy

Group : 1 GF-Cubord works BW, PL, c

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-00-SUB-007	Cubord work for Cuddupha slab fixing,brick& plastering works	Sft	114.3750	150.00	17,156.25	150.00	1.000	150.00	17,156.25	100.00

2550 PAINTING WORKS

2560 1.3.8.1 FF-Inner celing painting 1,314.000 Sft 21(Net) 21(Gross) 27,594.00(Amt.) 0.19 %

GF-Inner celing (White wash - 2 coat, primer-1, Emultion-2)

Group : 1 In.Paint Material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PT-001	White cement	Kg	72.2700	17.00	1,235.16	0.94	1.000	0.94	1,235.16	4.48
B-03-PT-002	Interior Primer	Ltr	11.1690	120.00	1,340.28	1.02	1.000	1.02	1,340.28	4.86
B-03-PT-004	Interior Emultion	Ltr	24.0462	500.00	12,023.10	9.15	1.000	9.15	12,023.10	43.57

Group : 2 In.Paint Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-11-INT-001	L/c for Int.paint White cement per coat	Sft	1,314.0000	2.10	2,759.40	2.10	1.000	2.10	2,759.40	10.00
L-11-INT-004	L/c for In.Paint Celing primer per coat	Sft	1,314.0000	2.10	2,759.40	2.10	1.000	2.10	2,759.40	10.00
L-11-INT-015	L/c for In.Paint Celing Emultion per coat	Sft	2,628.0000	2.30	6,044.40	4.60	1.000	4.60	6,044.40	21.90
L-07-MIS-040	Labour charges for Celing Surface Cleaning work	Sft	1,314.0000	1.00	1,314.00	1.00	1.000	1.00	1,314.00	4.76

Group : 3 In.paint Accessories

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PTH-010	4" Brush	NO	1.4454	250.00	367.92	0.28	1.000	0.28	367.92	1.33
B-03-PTO-007	Waste cloth	Kg	1.4454	80.00	118.26	0.09	1.000	0.09	118.26	0.43
B-03-PTH-045	Crack putty plate	NO	1.3140	25.00	39.42	0.03	1.000	0.03	39.42	0.14
B-03-PTH-060	6" Putty plate	NO	0.3942	85.00	39.42	0.03	1.000	0.03	39.42	0.14

2570 1.3.8.2 FF-inner wall painting 3,996.000 Sft 30(Net) 30(Gross) 1,19,880.00(Amt.) 0.85 %

GF-inner wall (Putty - 2 coat, Primer-1 coat, Emultion - 2 coat)

Group : 1 In.Paint Material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PT-006	Interior wall putty	kg	399.6000	25.00	9,990.00	2.50	1.000	2.50	9,990.00	8.33
B-03-PT-002	Interior Primer	Ltr	33.9660	120.00	4,075.92	1.02	1.000	1.02	4,075.92	3.40
B-03-PT-004	Interior Emultion	Ltr	73.1268	500.00	36,563.40	9.15	1.000	9.15	36,563.40	30.50

Group : 2 **In.Paint Labour-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-11-INT-030	L/c for In.Paint Wall putty per coat	Sft	7,992.0000	2.50	19,980.00	5.00	1.000	5.00	19,980.00	16.67
L-11-INT-005	L/c for Int.paint Wall primer per coat	Sft	3,996.0000	2.10	8,391.60	2.10	1.000	2.10	8,391.60	7.00
L-11-INT-020	L/c for In.Paint Wall Emultion per coat	Sft	7,992.0000	2.30	18,381.60	4.60	1.000	4.60	18,381.60	15.33
L-07-MIS-045	Labour charges for Wall Surface Cleaning work	Sft	3,996.0000	1.00	3,996.00	1.00	1.000	1.00	3,996.00	3.33

Group : 3 **In.paint Accessories**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PTH-010	4" Brush	NO	4.3956	250.00	1,118.88	0.28	1.000	0.28	1,118.88	0.93
B-03-PTH-035	9" Roller	NO	2.3976	260.00	639.36	0.16	1.000	0.16	639.36	0.53
B-03-PTH-045	Crack putty plate	NO	3.9960	25.00	119.88	0.03	1.000	0.03	119.88	0.10
B-03-PTH-070	12" Putty plate	NO	1.1988	130.00	159.84	0.04	1.000	0.04	159.84	0.13
B-03-PTH-065	8" Putty plate	NO	1.1988	100.00	119.88	0.03	1.000	0.03	119.88	0.10
B-03-PTH-060	6" Putty plate	NO	1.1988	85.00	119.88	0.03	1.000	0.03	119.88	0.10
B-03-PTO-007	Waste cloth	Kg	4.3956	80.00	359.64	0.09	1.000	0.09	359.64	0.30
B-03-PTO-003	POLISH PAPER - Emerry sheet - 180	NO	19.9800	20.00	399.60	0.10	1.000	0.10	399.60	0.33
B-03-PTO-009	POP	Kg	3.9960	25.00	119.88	0.03	1.000	0.03	119.88	0.10

Group : 4 **Other**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	3,996.0000	1.00	3,996.00	1.00	1.000	1.00	3,996.00	3.33
R-01-SCA-005	Providing and fixing of Scaffolding Cost	Sft	3,996.0000	3.00	11,988.00	3.00	1.000	3.00	11,988.00	10.00

2580 1.3.8.3 FF-Exterier wall painting 1,500.000 Sft 31(Net) 31(Gross) 46,500.00(Amt.) 0.33 %

GF-Exterier wall (White wash - 2 coat, Primer-1 coat, Emultion - 2 coat)

Group : 1 Ext.Paint Material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PT-001	White cement	Kg	82.5000	17.00	1,410.00	0.94	1.000	0.94	1,410.00	3.03
B-03-PT-003	Exterior Primer	Ltr	20.7000	200.00	4,140.00	2.76	1.000	2.76	4,140.00	8.90
B-03-PT-005	Exterior Emultion	Ltr	36.6000	600.00	21,960.00	14.64	1.000	14.64	21,960.00	47.23

Group : 2 Ext.Paint Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-11-EXT-001	L/c for Ext.paint White cement per coat	Sft	3,000.0000	2.15	6,450.00	4.30	1.000	4.30	6,450.00	13.87
L-11-EXT-005	L/c for Ext.paint Wall primer per coat	Sft	1,500.0000	2.15	3,225.00	2.15	1.000	2.15	3,225.00	6.94
L-11-EXT-015	L/c for Ext.paint Emultion per coat	Sft	3,000.0000	2.20	6,600.00	4.40	1.000	4.40	6,600.00	14.19
L-07-MIS-045	Labour charges for Wall Surface Cleaning work	Sft	1,500.0000	1.00	1,500.00	1.00	1.000	1.00	1,500.00	3.23

Group : 3 Ext.paint Accessories

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PTH-010	4" Brush	NO	1.6500	250.00	420.00	0.28	1.000	0.28	420.00	0.90
B-03-PTH-045	Crack putty plate	NO	1.5000	25.00	45.00	0.03	1.000	0.03	45.00	0.10

B-03-PTH-060	6" Putty plate	NO	0.4500	85.00	45.00	0.03	1.000	0.03	45.00	0.10
B-03-PTO-007	Waste cloth	Kg	1.6500	80.00	135.00	0.09	1.000	0.09	135.00	0.29
B-03-PTO-009	POP	Kg	1.5000	25.00	45.00	0.03	1.000	0.03	45.00	0.10

2590 1.3.8.4 FF-Wood/Grill Painting 528.000 Sft 25(Net) 25(Gross) 13,200.00(Amt.) 0.09 %

GF-Grill Painting(Zinc.primer-2 + Enamal paint 2)

Group : 1 Gril. painting Material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PT-011	Enamal Paint	Lit	7.5504	300.00	2,265.12	4.29	1.000	4.29	2,265.12	17.16
B-03-PT-010	Zinchromate primer	Lit	3.7488	120.00	448.80	0.85	1.000	0.85	448.80	3.40
B-03-PTO-005	THINNER	LTR	3.7488	90.00	337.92	0.64	1.000	0.64	337.92	2.56

Group : 2 Grill Painting Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-11-INT-007	L/c for In.Paint Zink primer per coat	Sft	528.0000	5.25	2,772.00	5.25	1.000	5.25	2,772.00	21.00
L-11-INT-045	L/c for In.Paint Enamal paint (Grill two side) per coat	Sft	1,056.0000	7.00	7,392.00	14.00	1.000	14.00	7,392.00	56.00

Group : 3 Grill Painting Accessories

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PTH-075	18 no Flat brush	NO	0.2640	100.00	26.40	0.05	1.000	0.05	26.40	0.20
B-03-PTH-080	20 no Flat brush	NO	0.2640	120.00	31.68	0.06	1.000	0.06	31.68	0.24
B-03-PTO-001	POLISH PAPER - Emerry sheet - 100	NO	2.6400	20.00	52.80	0.10	1.000	0.10	52.80	0.40
B-03-PTO-007	Waste cloth	Kg	0.2640	80.00	21.12	0.04	1.000	0.04	21.12	0.16

2600 1.3.8.5 FF-Main door polish work painting 57.750 Sft 114(Net) 114(Gross) 6,583.50(Amt.) 0.05 %

FF-Main door polish work painting

Group : 1 MATRIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PT-012	Melamine teak wood Polish	Lit	1.4438	150.00	216.56	3.75	1.000	3.75	216.56	3.29

Group : 2 LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-11-POL-005	L/c for Pol. Melamine POLISH FINSIH	Sft	57.7500	110.00	6,352.50	110.00	1.000	110.00	6,352.50	96.49

2610 ELECTRICAL & PLUMBING WORKS

2620 1.3.9.1 FF-supply and fixing of Electrical Subcontract works 1,274.000 Sft 152(Net) 152(Gross) 1,93,648.00(Amt.) 1.37 %

FF-supply and fixing of Electrical Subcontract works

Group : 1 Electrical works material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
D-08-ELE-A-005	25mm HMS PVC Conduit Pipe (Slab & Walls)	Rft	573.3000	25.00	14,332.50	11.25	1.000	11.25	14,332.50	7.40
D-08-ELE-A-010	20mm HMS PVC Conduit Pipe (Point Wiring)	Rft	254.8000	21.00	5,350.80	4.20	1.000	4.20	5,350.80	2.76
D-08-ELE-B-005	1.0 sq.mm Wire (Light/Fan Points - Green/Red/Black)	Coils	10.1920	2,300.00	23,441.60	18.40	1.000	18.40	23,441.60	12.11
D-08-ELE-B-010	1.5 sq.mm Wire (Primary Circuits/Sockets)	Coils	5.0960	3,000.00	15,288.00	12.00	1.000	12.00	15,288.00	7.89

D-08-ELE-B-015	2.5 sq.mm Wire (Power Points/ Geyser)	Coils	3.8220	5,200.00	19,874.40	15.60	1.000	15.60	19,874.40	10.26
D-08-ELE-B-020	4.0 sq.mm Wire (Main Line/ AC)	Coils	2.5480	7,500.00	19,110.00	15.00	1.000	15.00	19,110.00	9.87
D-08-ELE-C-005	12 Module Metal Box (Main Switch Board)	Nos	3.8220	250.00	955.50	0.75	1.000	0.75	955.50	0.49
D-08-ELE-C-010	8 Module Metal Box (Bedrooms/Kitchen)	Nos	5.0960	180.00	917.28	0.72	1.000	0.72	917.28	0.47
D-08-ELE-C-015	6 Module Metal Box (Utility/ AC)	Nos	5.0960	150.00	764.40	0.60	1.000	0.60	764.40	0.39
D-08-ELE-C-020	3/2/1 Module Metal Box (Single points/Calling bell)	Nos	15.2880	80.00	1,223.04	0.96	1.000	0.96	1,223.04	0.63
D-08-ELE-D-005	6A One-way Switch	Nos	57.3300	65.00	3,732.82	2.93	1.000	2.93	3,732.82	1.93
D-08-ELE-D-010	6A 3-pin Socket	Nos	22.9320	120.00	2,751.84	2.16	1.000	2.16	2,751.84	1.42
D-08-ELE-D-015	16A/25A Power Socket with Switch	Nos	7.6440	350.00	2,675.40	2.10	1.000	2.10	2,675.40	1.38
D-08-ELE-D-020	Fan Regulator (2-module step type)	Nos	6.3700	250.00	1,592.50	1.25	1.000	1.25	1,592.50	0.82
D-08-ELE-E-005	8-12 Way Double Door DB Box	Nos	1.2740	8,000.00	10,192.00	8.00	1.000	8.00	10,192.00	5.26
D-08-ELE-E-010	63A DP RCCB (30mA for safety)	Nos	1.2740	2,200.00	2,802.80	2.20	1.000	2.20	2,802.80	1.45
D-08-ELE-E-015	63A FP Isolator	Nos	1.2740	950.00	1,210.30	0.95	1.000	0.95	1,210.30	0.63
D-08-ELE-E-020	6A/10A/16A/25A Single Pole MCB	Nos	1.2740	350.00	445.90	0.35	1.000	0.35	445.90	0.23
D-08-ELE-F-005	PVC Junction Boxes (Deep/ Surface)	Nos	57.3300	25.00	1,439.62	1.13	1.000	1.13	1,439.62	0.74
D-08-ELE-F-015	PVC Bend (25mm/20mm)	Nos	76.4400	15.00	1,146.60	0.90	1.000	0.90	1,146.60	0.59
D-08-ELE-F-020	Solvent Cement (100ml)	Nos	2.5480	120.00	305.76	0.24	1.000	0.24	305.76	0.16

D-08-ELE-F-025	Insulation Tape (Assorted colors)	Nos	12.7400	30.00	382.20	0.30	1.000	0.30	382.20	0.20
D-08-ELE-F-030	Flexible Pipe (for drops)	Rft	38.2200	12.00	458.64	0.36	1.000	0.36	458.64	0.24

Group : 2 Electrical Labor

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-31-ELE-020	L/C for Ele - Roof slab conduiting pipe laying works	Nos	6.3700	1,000.00	6,370.00	5.00	1.000	5.00	6,370.00	3.29
L-31-ELE-025	L/C for Ele - Wall Pipe and Mettal box fixing works	Nos	16.9442	1,000.00	16,944.20	13.30	1.000	13.30	16,944.20	8.75
L-31-ELE-030	L/C for Ele - Wiring works	Nos	12.7400	1,000.00	12,740.00	10.00	1.000	10.00	12,740.00	6.58
L-31-ELE-035	L/C for Ele - Swtiches & socket assamble and fixing works	Nos	10.5742	1,000.00	10,574.20	8.30	1.000	8.30	10,574.20	5.46
L-31-ELE-040	L/C for Ele - DB Board fixing & Wiring works	Nos	4.2042	1,000.00	4,204.20	3.30	1.000	3.30	4,204.20	2.17
L-31-ELE-045	L/C for Ele - Service connection and Testing works	Nos	4.2042	1,000.00	4,204.20	3.30	1.000	3.30	4,204.20	2.17
L-31-ELE-050	L/C for Ele - Light, fan, motor and orther fitting works	Nos	4.2042	1,000.00	4,204.20	3.30	1.000	3.30	4,204.20	2.17
L-31-ELE-055	L/C for Ele - other miscellaneous works	Nos	4.2042	1,000.00	4,204.20	3.30	1.000	3.30	4,204.20	2.17

2630 1.3.9.2 FF-supply and fixing of plumbing Subcontract works 1,274.000 Sft 210(Net) 210(Gross) 2,67,540.00(Amt.) 1.89 %

FF-supply and fixing of plumbing Subcontract works

Group : 1 Plumbingwork subcontract-

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-00-SUB-005	Plumbing Work Subcontract Labour	Sft	1,274.0000	50.00	63,700.00	50.00	1.000	50.00	63,700.00	23.81

K-00-SUB-006	Plumbing Work Subcontract Material	Sft	1,274.0000	160.00	2,03,840.00	160.00	1.000	160.00	2,03,840.00	76.19

2700 **SECOND FLOOR**

2710 **SUPER STRUCTURE RCC WORK**

2720 **1.4.1.1** **SF - RCC - M20 (1:1.5:3)For Column** **147.656 Cft** **1,385(Net)** **1,385(Gross)** **2,04,503.56(Amt.)** **1.44 %**

SF - RCC - M20 (1:1.5:3)For Column

Group : 1 **RCC LABOUR -L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-035	L/C for laying concrete for Column	Cft	147.6560	60.00	8,859.36	60.00	1.000	60.00	8,859.36	4.33

Group : 2 **RCC MATERIAL**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	31.7460	335.00	10,635.66	72.03	1.000	72.03	10,635.66	5.20
A-02-AGG-02-004	M SAND (BLACK)	Cft	59.5201	55.00	3,273.53	22.17	1.000	22.17	3,273.53	1.60
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	119.0403	45.00	5,356.96	36.28	1.000	36.28	5,356.96	2.62
A-04-CHM-003	ADMIXTURE	KG	9.3909	80.00	751.57	5.09	1.000	5.09	751.57	0.37

Group : 3 **RCC MACHINE**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	0.4873	2,500.00	1,218.16	8.25	1.000	8.25	1,218.16	0.60
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.4873	500.00	243.63	1.65	1.000	1.65	243.63	0.12

Group : 4 **RCC CONSUMABLES**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	147.6560	1.00	147.66	1.00	1.000	1.00	147.66	0.07
O-01-CUR-001	OH/C CURING WORK	LS	147.6560	3.00	442.97	3.00	1.000	3.00	442.97	0.22
O-03-CONS-001	OH/C CONSUMABLES	LS	147.6560	2.00	295.31	2.00	1.000	2.00	295.31	0.14

Group : 5 **Shuttering Labour-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-002	L/c- Column Shuttering	Sft	664.4520	17.00	11,295.68	76.50	1.000	76.50	11,295.68	5.52

Group : 6 **Shuttering material-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-005	S/c- Column Shuttering material Cost	Sft	664.4520	20.00	13,289.04	90.00	1.000	90.00	13,289.04	6.50

Group : 7 **MACHINERY and CONSUMA**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	147.6560	1.00	147.66	1.00	1.000	1.00	147.66	0.07
O-03-CONS-001	OH/C CONSUMABLES	LS	147.6560	2.00	295.31	2.00	1.000	2.00	295.31	0.14

Group : 8 **STEEL MATERIAL**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	1,365.8180	80.00	1,09,265.44	740.00	1.000	740.00	1,09,265.44	53.43
A-03-REF-03	BINDING WIRE	KG	40.9745	100.00	4,097.45	27.75	1.000	27.75	4,097.45	2.00
A-05-COV-011	COVER BLOCK	NO	341.4545	2.00	683.65	4.63	1.000	4.63	683.65	0.33

Group : 9 **STEEL LABOUR-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	1,365.8180	25.00	34,145.45	231.25	1.000	231.25	34,145.45	16.70

2730 1.4.1.2 SF - RCC - M20 (1:1.5:3)For Sill - 3" 43.779 Cft 451(Net) 451(Gross) 19,744.33(Amt.) 0.14 %

SF - RCC - M20 (1:1.5:3)For Sill - 3"

Group : 1 **RCC MACHINE**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	0.1445	2,500.00	361.18	8.25	1.000	8.25	361.18	1.83
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.1445	500.00	72.24	1.65	1.000	1.65	72.24	0.37

Group : 2 **RCC LABOUR -L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-090	L/c for laying concrete for Sill	Cft	43.7790	45.00	1,970.06	45.00	1.000	45.00	1,970.06	9.98

Group : 3 **RCC MATERIAL**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	9.4125	335.00	3,153.40	72.03	1.000	72.03	3,153.40	15.97
A-02-AGG-02-004	M SAND (BLACK)	Cft	17.6473	55.00	970.58	22.17	1.000	22.17	970.58	4.92
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	35.2946	45.00	1,588.30	36.28	1.000	36.28	1,588.30	8.04
A-04-CHM-003	ADMIXTURE	KG	2.7843	80.00	222.84	5.09	1.000	5.09	222.84	1.13

Group : 4 **RCC CONSUMABLES**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	43.7790	1.00	43.78	1.00	1.000	1.00	43.78	0.22
O-01-CUR-001	OH/C CURING WORK	LS	43.7790	3.00	131.34	3.00	1.000	3.00	131.34	0.67
O-03-CONS-001	OH/C CONSUMABLES	LS	43.7790	2.00	87.56	2.00	1.000	2.00	87.56	0.44

Group : 5 **Shuttering Labour-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-090	Labour charges for shuttering of Sill	Sft	109.4475	0.00	0.00	0.00	1.000	0.00	0.00	0.00

Group : 6 **Shuttering material-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-020	S/c- DPC/Sill/Coping Shuttering material Cost	Sft	109.4475	15.00	1,641.71	37.50	1.000	37.50	1,641.71	8.31

Group : 7 **STEEL MATERIAL**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	87.5580	80.00	7,004.64	160.00	1.000	160.00	7,004.64	35.48
A-03-REF-03	BINDING WIRE	KG	2.6267	100.00	262.67	6.00	1.000	6.00	262.67	1.33
A-05-COV-011	COVER BLOCK	NO	21.8895	2.00	43.78	1.00	1.000	1.00	43.78	0.22

Group : 8 **STEEL LABOUR-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	87.5580	25.00	2,188.95	50.00	1.000	50.00	2,188.95	11.09

2740 1.4.1.3 SF - RCC - M20 (1:1.5:3)For Lintel 87.554 Cft 685(Net) 685(Gross) 59,974.49(Amt.) 0.42 %

SF - RCC - M20 (1:1.5:3)For Lintel

Group : 1 RCC MACHINE

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	0.2889	2,500.00	722.32	8.25	1.000	8.25	722.32	1.20
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.2889	500.00	144.46	1.65	1.000	1.65	144.46	0.24

Group : 2 RCC LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-065	L/c for laying concrete for Lintel	Cft	87.5540	45.00	3,939.93	45.00	1.000	45.00	3,939.93	6.57

Group : 3 RCC MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	18.8241	335.00	6,306.51	72.03	1.000	72.03	6,306.51	10.52
A-02-AGG-02-004	M SAND (BLACK)	Cft	35.2930	55.00	1,941.07	22.17	1.000	22.17	1,941.07	3.24
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	70.5860	45.00	3,176.46	36.28	1.000	36.28	3,176.46	5.30
A-04-CHM-003	ADMIXTURE	KG	5.5684	80.00	445.65	5.09	1.000	5.09	445.65	0.74

Group : 4 RCC CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	87.5540	1.00	87.55	1.00	1.000	1.00	87.55	0.15
O-01-CUR-001	OH/C CURING WORK	LS	87.5540	3.00	262.66	3.00	1.000	3.00	262.66	0.44

O-03-CONS-001	OH/C CONSUMABLES	LS	87.5540	2.00	175.11	2.00	1.000	2.00	175.11	0.29

Group : 5 Shuttering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-065	L/c- Lintel Shuttering	Sft	218.8850	25.00	5,472.13	62.50	1.000	62.50	5,472.13	9.12

Group : 6 Shuttering material-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-025	S/c- Lintel Shuttering material Cost	Sft	218.8850	25.00	5,472.13	62.50	1.000	62.50	5,472.13	9.12

Group : 7 STEEL MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	293.3059	80.00	23,464.47	268.00	1.000	268.00	23,464.47	39.12
A-03-REF-03	BINDING WIRE	KG	8.7992	100.00	879.92	10.05	1.000	10.05	879.92	1.47
A-05-COV-011	COVER BLOCK	NO	73.3265	2.00	147.09	1.68	1.000	1.68	147.09	0.25

Group : 8 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	293.3059	25.00	7,332.65	83.75	1.000	83.75	7,332.65	12.23

2750 1.4.1.4 SF- RCC - M20 (1:1.5:3)For Loft & Sunshade 122.000 Sft 217(Net) 217(Gross) 26,474.00(Amt.) 0.19 %

GF- RCC - M20 (1:1.5:3)For Kitchen Table top,Low roof,Loft and Sunshade

Group : 1 RCC MACHINE

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%

R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	0.0976	2,500.00	244.00	2.00	1.000	2.00	244.00	0.92
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.0976	500.00	48.80	0.40	1.000	0.40	48.80	0.18

Group : 2 **RCC LABOUR -L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-065	L/c for laying concrete for Lintel	Cft	122.0000	45.00	5,490.00	45.00	1.000	45.00	5,490.00	20.74

Group : 3 **RCC MATERIAL**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	6.5636	335.00	2,198.44	18.02	1.000	18.02	2,198.44	8.30
A-02-AGG-02-004	M SAND (BLACK)	Cft	12.2976	55.00	675.88	5.54	1.000	5.54	675.88	2.55
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	24.5952	45.00	1,106.54	9.07	1.000	9.07	1,106.54	4.18
A-04-CHM-003	ADMIXTURE	KG	1.9398	80.00	154.94	1.27	1.000	1.27	154.94	0.59

Group : 4 **RCC CONSUMABLES**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	122.0000	1.00	122.00	1.00	1.000	1.00	122.00	0.46
O-01-CUR-001	OH/C CURING WORK	LS	122.0000	3.00	366.00	3.00	1.000	3.00	366.00	1.38
O-03-CONS-001	OH/C CONSUMABLES	LS	122.0000	2.00	244.00	2.00	1.000	2.00	244.00	0.92

Group : 5 **Shuttering material-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%

K-05-SHU-030	S/c- Loft / sunshade /kitchen table Shuttering material Cost	Sft	122.0000	25.00	3,050.00	25.00	1.000	25.00	3,050.00	11.52

Group : 6 Shuttering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-037	L/c- Loft / sunshade /kitchen table Shuttering	Sft	122.0000	23.00	2,806.00	23.00	1.000	23.00	2,806.00	10.60

Group : 7 STEEL MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	91.5000	80.00	7,320.00	60.00	1.000	60.00	7,320.00	27.65
A-03-REF-03	BINDING WIRE	KG	2.7450	100.00	274.50	2.25	1.000	2.25	274.50	1.04
A-05-COV-011	COVER BLOCK	NO	22.8750	2.00	46.36	0.38	1.000	0.38	46.36	0.18

Group : 8 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	91.5000	25.00	2,287.50	18.75	1.000	18.75	2,287.50	8.64

2760 1.4.1.5 SF - RCC - M20 (1:1.5:3)For Staircase 152.375 Sft 420(Net) 420(Gross) 63,997.50(Amt.) 0.45 %

SF - RCC - M20 (1:1.5:3)For Staircase

Group : 1 Shuttering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-050	L/c- Staircase Shuttering	Sft	228.5625	60.00	13,713.75	90.00	1.000	90.00	13,713.75	21.43

Group : 2 Shuttering material-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-035	S/c- Staircase Shuttering material Cost	Sft	228.5625	50.00	11,428.13	75.00	1.000	75.00	11,428.13	17.86

Group : 3 **RCC LABOUR -L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-050	L/c for laying concrete for Staircase	Cft	62.4738	50.00	3,123.69	20.50	1.000	20.50	3,123.69	4.88

Group : 4 **RCC MATERIAL**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	13.4395	335.00	4,502.68	29.55	1.000	29.55	4,502.68	7.04
A-02-AGG-02-004	M SAND (BLACK)	Cft	25.1876	55.00	1,385.09	9.09	1.000	9.09	1,385.09	2.16
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	50.3752	45.00	2,267.34	14.88	1.000	14.88	2,267.34	3.54
A-04-CHM-003	ADMIXTURE	KG	3.9770	80.00	318.46	2.09	1.000	2.09	318.46	0.50

Group : 5 **RCC MACHINE**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	0.2133	2,500.00	533.31	3.50	1.000	3.50	533.31	0.83
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.2133	500.00	106.66	0.70	1.000	0.70	106.66	0.17

Group : 6 **RCC CONSUMABLES**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	152.3750	1.00	152.38	1.00	1.000	1.00	152.38	0.24
O-01-CUR-001	OH/C CURING WORK	LS	152.3750	3.00	457.13	3.00	1.000	3.00	457.13	0.71
O-03-CONS-001	OH/C CONSUMABLES	LS	152.3750	2.00	304.75	2.00	1.000	2.00	304.75	0.48

Group : 7 STEEL MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	228.5625	80.00	18,285.00	120.00	1.000	120.00	18,285.00	28.57
A-03-REF-03	BINDING WIRE	KG	6.8569	100.00	685.69	4.50	1.000	4.50	685.69	1.07
A-05-COV-011	COVER BLOCK	NO	57.1406	2.00	114.28	0.75	1.000	0.75	114.28	0.18

Group : 8 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	228.5625	25.00	5,714.06	37.50	1.000	37.50	5,714.06	8.93

Group : 9 CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-01-CUR-001	OH/C CURING WORK	LS	152.3750	3.00	457.13	3.00	1.000	3.00	457.13	0.71
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	152.3750	1.00	152.38	1.00	1.000	1.00	152.38	0.24
O-03-CONS-001	OH/C CONSUMABLES	LS	152.3750	2.00	304.75	2.00	1.000	2.00	304.75	0.48

2770 1.4.1.6 SF - RCC - M20 Roof Beam using RMC 264.687 Cft 895(Net) 895(Gross) 2,36,894.87(Amt.) 1.67 %

SF - RCC - M20 Roof Beam using RMC

Group : 1 Shuttering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-105	L/c- Roof Beam Shuttering	Sft	899.9358	17.00	15,298.91	57.80	1.000	57.80	15,298.91	6.46

Group : 2 Shuttering material-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%

K-05-SHU-040	S/c- Roof beam Shuttering material Cost	Sft	899.9358	30.00	26,998.07	102.00	1.000	102.00	26,998.07	11.40

Group : 3 STEEL MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	1,323.4350	80.00	1,05,874.80	400.00	1.000	400.00	1,05,874.80	44.69
A-03-REF-03	BINDING WIRE	KG	39.7030	100.00	3,970.31	15.00	1.000	15.00	3,970.31	1.68
A-05-COV-011	COVER BLOCK	NO	330.8588	2.00	661.72	2.50	1.000	2.50	661.72	0.28

Group : 4 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	1,323.4350	25.00	33,085.88	125.00	1.000	125.00	33,085.88	13.97

Group : 5 RCC LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-180	L/C for RMC Concrete laying using Pump	Cft	264.6870	15.00	3,970.31	15.00	1.000	15.00	3,970.31	1.68

Group : 6 RCC RMC MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-02-RMC-01-031	READYMIX CONCRETE M 20 GRADE	Cft	264.6870	160.00	42,349.92	160.00	1.000	160.00	42,349.92	17.88
M-01-PUM-02	CONCRETE PUMP	Cft	264.6870	5.00	1,323.44	5.00	1.000	5.00	1,323.44	0.56

Group : 7 RCC MACHINERY

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.8735	500.00	436.73	1.65	1.000	1.65	436.73	0.18

Group : 8 RCC CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	264.6870	1.00	264.69	1.00	1.000	1.00	264.69	0.11
O-01-CUR-001	OH/C CURING WORK	LS	264.6870	3.00	794.06	3.00	1.000	3.00	794.06	0.34
O-03-CONS-001	OH/C CONSUMABLES	LS	264.6870	2.00	529.37	2.00	1.000	2.00	529.37	0.22
O-03-CONS-005	OH/C Lead and Lift	LS	264.6870	5.00	1,323.44	5.00	1.000	5.00	1,323.44	0.56

2780 1.4.1.7 SF - RCC - M20 Roof slab using RMC 406.123 Cft 563(Net) 563(Gross) 2,28,647.25(Amt.) 1.62 %

SF - RCC - M20 Roof slab using RMC

Group : 1 Shuttering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-100	L/c- Roof Slab Shuttering	Sft	990.5340	25.00	24,765.38	60.98	1.000	60.98	24,765.38	10.83

Group : 2 Shuttering material-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-045	S/c- Roof Slab Shuttering material Cost	Sft	990.5340	20.00	19,810.68	48.78	1.000	48.78	19,810.68	8.66

Group : 3 STEEL MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	974.6952	80.00	77,975.62	192.00	1.000	192.00	77,975.62	34.10
A-03-REF-03	BINDING WIRE	KG	29.2409	100.00	2,924.09	7.20	1.000	7.20	2,924.09	1.28
A-05-COV-011	COVER BLOCK	NO	243.6738	2.00	487.35	1.20	1.000	1.20	487.35	0.21

Group : 4 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	974.6952	25.00	24,367.38	60.00	1.000	60.00	24,367.38	10.66

Group : 5 **RCC LABOUR -L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-180	L/C for RMC Concrete laying using Pump	Cft	406.1230	15.00	6,091.85	15.00	1.000	15.00	6,091.85	2.66

Group : 6 **RCC RMC MATERIAL**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-02-RMC-01-031	READYMIX CONCRETE M 20 GRADE	Cft	406.1230	160.00	64,979.68	160.00	1.000	160.00	64,979.68	28.42
M-01-PUM-02	CONCRETE PUMP	Cft	406.1230	5.00	2,030.62	5.00	1.000	5.00	2,030.62	0.89

Group : 7 **RCC MACHINERY**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	1.3402	500.00	670.10	1.65	1.000	1.65	670.10	0.29

Group : 8 **RCC CONSUMABLES**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	406.1230	1.00	406.12	1.00	1.000	1.00	406.12	0.18
O-01-CUR-001	OH/C CURING WORK	LS	406.1230	3.00	1,218.37	3.00	1.000	3.00	1,218.37	0.53
O-03-CONS-001	OH/C CONSUMABLES	LS	406.1230	2.00	812.25	2.00	1.000	2.00	812.25	0.36
O-03-CONS-005	OH/C Lead and Lift	LS	406.1230	5.00	2,030.62	5.00	1.000	5.00	2,030.62	0.89

2790 **MASONRY WORK**

2800 1.4.2.1 SF - 9" Brick work - Red brick with CM 1:6 Upto Roof level 847.430 Cft 267(Net) 267(Gross) 2,26,263.81(Amt.) 1.60 %

SF - 9" Brick work - Red brick with CM 1:6 Upto Roof level

Group : 1 MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	44.5748	335.00	14,931.72	17.62	1.000	17.62	14,931.72	6.60
A-02-AGG-02-004	M SAND (BLACK)	Cft	390.0720	55.00	21,456.93	25.32	1.000	25.32	21,456.93	9.48
A-02-BRK-02-006	RED BRICK (9" X 3" X 4")	NO	11,864.0200	12.00	1,42,368.24	168.00	1.000	168.00	1,42,368.24	62.92

Group : 2 LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-04-MAS-155	L/c for 9" brick masonry	Cft	847.4300	50.00	42,371.50	50.00	1.000	50.00	42,371.50	18.73

Group : 3 CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-01-CUR-001	OH/C CURING WORK	LS	847.4300	3.00	2,542.29	3.00	1.000	3.00	2,542.29	1.12
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	847.4300	1.00	847.43	1.00	1.000	1.00	847.43	0.37
O-03-CONS-001	OH/C CONSUMABLES	LS	847.4300	2.00	1,694.86	2.00	1.000	2.00	1,694.86	0.75

2810 1.4.2.2 SF - 4.5" Brick work - Red brick with CM 1:4 Upto Roof level 828.890 Sft 119(Net) 119(Gross) 98,637.91(Amt.) 0.70 %

SF - 4.5" Brick work - Red brick with CM 1:4 Upto Roof level

Group : 1 **4.5" BW LABOUR -L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-04-MAS-160	L/c for 4.5" brick masonry	Sft	828.8900	35.00	29,011.15	35.00	1.000	35.00	29,011.15	29.41

Group : 2 **4.5" BW MATERIAL**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	17.9869	335.00	6,026.03	7.27	1.000	7.27	6,026.03	6.11
A-02-AGG-02-004	M SAND (BLACK)	Cft	112.3975	55.00	6,183.52	7.46	1.000	7.46	6,183.52	6.27
A-02-BRK-02-006	RED BRICK (9" X 3" X 4")	NO	4,351.6725	12.00	52,220.07	63.00	1.000	63.00	52,220.07	52.94

Group : 3 **BW CONSUMABLES**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-01-CUR-001	OH/C CURING WORK	LS	828.8900	3.00	2,486.67	3.00	1.000	3.00	2,486.67	2.52
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	828.8900	1.00	828.89	1.00	1.000	1.00	828.89	0.84
O-03-CONS-001	OH/C CONSUMABLES	LS	828.8900	2.00	1,657.78	2.00	1.000	2.00	1,657.78	1.68

2820 **PLASTREING WORK**

2830 **1.4.3.1** **SF - Celing Plastering - 12mm thik - 1:4** **1,340.355 Sft** **47(Net)** **47(Gross)** **62,996.69(Amt.)** **0.45 %**

SF - Celing Plastering - 12mm thik - 1:4

Group : 1 **CELING PLASTERING LABO**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%

L-05-INT-010	L/c for Internal ceiling plaster	Sft	1,340.3550	25.00	33,508.88	25.00	1.000	25.00	33,508.88	53.19
L-07-MIS-035	L/c for pointing for plastering work	Sft	1,340.3550	3.00	4,021.07	3.00	1.000	3.00	4,021.07	6.38

Group : 2 CELING PLASTERING MATE

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	18.4969	335.00	6,192.44	4.62	1.000	4.62	6,192.44	9.83
A-02-AGG-02-006	P SAND (PLASTER)	Cft	115.6726	65.00	7,519.39	5.61	1.000	5.61	7,519.39	11.94

Group : 3 CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-01-CUR-001	OH/C CURING WORK	LS	1,340.3550	3.00	4,021.07	3.00	1.000	3.00	4,021.07	6.38
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	1,340.3550	1.00	1,340.36	1.00	1.000	1.00	1,340.36	2.13
O-03-CONS-001	OH/C CONSUMABLES	LS	1,340.3550	2.00	2,680.71	2.00	1.000	2.00	2,680.71	4.26
R-01-SCA-005	Providing and fixing of Scaffolding Cost	Sft	1,340.3550	3.00	4,021.07	3.00	1.000	3.00	4,021.07	6.38

2840 1.4.3.2 SF - Internal Plastering - 18mm thik - 1:5 4,579.100 Sft 44(Net) 44(Gross) 2,01,480.40(Amt.) 1.42 %

SF - Internal Plastering - 18mm thik - 1:5

Group : 1 WALL PLASTERING LABOU

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-05-INT-015	L/c for Internal Wall plaster	Sft	4,579.1000	23.00	1,05,319.30	23.00	1.000	23.00	1,05,319.30	52.27

Group : 2 WALL PLASTERING MATER

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%

A-01-CEM-01-001	CEMENT	BAG	65.4811	335.00	21,933.89	4.79	1.000	4.79	21,933.89	10.89
A-02-AGG-02-006	P SAND (PLASTER)	Cft	491.3374	65.00	31,916.33	6.97	1.000	6.97	31,916.33	15.84

Group : 3 CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-01-CUR-001	OH/C CURING WORK	LS	4,579.1000	3.00	13,737.30	3.00	1.000	3.00	13,737.30	6.82
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	4,579.1000	1.00	4,579.10	1.00	1.000	1.00	4,579.10	2.27
R-01-SCA-005	Providing and fixing of Scaffolding Cost	Sft	4,579.1000	3.00	13,737.30	3.00	1.000	3.00	13,737.30	6.82
O-03-CONS-001	OH/C CONSUMABLES	LS	4,579.1000	2.00	9,158.20	2.00	1.000	2.00	9,158.20	4.55

2850 1.4.3.3 SF - External Plastering - 18mm thik - 1:5 1,500.000 Sft 46(Net) 46(Gross) 69,000.00(Amt.) 0.49 %

SF - External Plastering - 18mm thik - 1:5

Group : 1 WALL PLASTERING LABOU

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-06-EXT-005	L/c for external plaster	Sft	1,500.0000	25.00	37,500.00	25.00	1.000	25.00	37,500.00	54.35

Group : 2 WALL PLASTERING MATER

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	21.4500	335.00	7,185.00	4.79	1.000	4.79	7,185.00	10.41
A-02-AGG-02-006	P SAND (PLASTER)	Cft	160.9500	65.00	10,455.00	6.97	1.000	6.97	10,455.00	15.15

Group : 3 CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-01-CUR-001	OH/C CURING WORK	LS	1,500.0000	3.00	4,500.00	3.00	1.000	3.00	4,500.00	6.52
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	1,500.0000	1.00	1,500.00	1.00	1.000	1.00	1,500.00	2.17
O-03-CONS-001	OH/C CONSUMABLES	LS	1,500.0000	2.00	3,000.00	2.00	1.000	2.00	3,000.00	4.35
R-01-SCA-005	Providing and fixing of Scaffolding Cost	Sft	1,500.0000	3.00	4,500.00	3.00	1.000	3.00	4,500.00	6.52

2860 **GRILL WORKS**

2870 **1.4.4.1** **SF - Staircase SS Hand rail works** **27.000 Rft** **1,003(Net)** **1,003(Gross)** **27,081.00(Amt.)** **0.19 %**

SF - Staircase SS Hand rail works

Group : 1 **SS handrail Material**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-30-FAB-041	Providing & fabricating work for SS Hand Railing	Rft	27.0000	1,000.00	27,000.00	1,000.00	1.000	1,000.00	27,000.00	99.70

Group : 2 **Other Consumables**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	27.0000	1.00	27.00	1.00	1.000	1.00	27.00	0.10
O-03-CONS-001	OH/C CONSUMABLES	LS	27.0000	2.00	54.00	2.00	1.000	2.00	54.00	0.20

2875 **1.4.4.2** **SF-SS Handrail with Glass** **33.000 Rft** **2,200.00(Net)** **2,200.00(Gross)** **72,600.00(Amt.)** **0.51 %**

SF-SS Handrail with Glass

Group : 1 SS with Glass

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-30-FAB-035	Providing & fabricating work for SS handrail with glass	Rft	33.0000	2,200.00	72,600.00	2,200.00	1.000	2,200.00	72,600.00	100.00

2878 1.4.4.3 SF- Balcony Grill Work 62.000 Sft 262.50(Net) 262.50(Gross) 16,275.00(Amt.) 0.11 %

SF- Balcony Grill Work

Group : 1 Grlll work

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-30-FAB-040	Providing & fabricating and fixing work for M.S. Grill	Kg	108.5000	150.00	16,275.00	262.50	1.000	262.50	16,275.00	100.00

2880 DOOR WORKS

2900 1.4.5.1 SF - Wood frame with flush door shutter for Bed room door 84.000 Sft 920(Net) 920(Gross) 77,280.00(Amt.) 0.55 %

SF - Wood frame with flush door shutter for Bed room door

Group : 1 Wood works

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-06-A-05	Wood Door/window Frame (Padauh, Neam, Vengai)	Cft	5.6112	2,000.00	11,222.40	133.60	1.000	133.60	11,222.40	14.52
B-06-A-15	Redymade Flush Door Shutter	Sqft	84.0000	285.00	23,940.00	285.00	1.000	285.00	23,940.00	30.98
B-06-B-02	6" Hinges	Nos	23.9400	500.00	11,970.00	142.50	1.000	142.50	11,970.00	15.49
B-06-B-03	8" Handle Front	Nos	4.2000	2,500.00	10,500.00	125.00	1.000	125.00	10,500.00	13.59
B-06-B-04	6" Handle Back	Nos	4.2000	1,000.00	4,200.00	50.00	1.000	50.00	4,200.00	5.43
B-06-B-06	8" Tower bolt	Nos	4.2000	750.00	3,150.00	37.50	1.000	37.50	3,150.00	4.08
B-06-B-07	Door stoper	Nos	4.2000	350.00	1,470.00	17.50	1.000	17.50	1,470.00	1.90

B-06-B-08	Frame Clamps	Nos	23.9400	100.00	2,394.00	28.50	1.000	28.50	2,394.00	3.10
B-06-B-09	Nails and other consumables for Wooderen works	Ls	4.2000	1,000.00	4,200.00	50.00	1.000	50.00	4,200.00	5.43
L-53-OTH-085	L/c For Woodern frame fixing and paking (Door, Window)	Sft	84.0000	50.00	4,200.00	50.00	1.000	50.00	4,200.00	5.43

2905 1.4.5.2 SF- UPVC Sliding Door 17.500 Sft 550.00(Net) 550.00(Gross) 9,625.00(Amt.) 0.07 %

SF- UPVC Sliding Door

Group : 1 Door

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-16-C-05	Supply & Fixing of UPVC Sliding DOOR	Sft	17.5000	550.00	9,625.00	550.00	1.000	550.00	9,625.00	100.00

2910 1.4.5.3 SF - WPC door for Toilet 105.000 Sft 570(Net) 570(Gross) 59,850.00(Amt.) 0.42 %

GF-UPVC door for Toilet

Group : 1 WPC Door Subcontract -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-12-FLD-015	S&F WPC Door Frame with shutter	Sft	105.0000	570.00	59,850.00	570.00	1.000	570.00	59,850.00	100.00

2920 JOINERY WORKS

2930 1.4.6.1 SF-UPVC Winodw with safey grill 129.000 Sft 695(Net) 695(Gross) 89,655.00(Amt.) 0.63 %

SF-UPVC Winodw with safey grill

Group : 1 UPVC works

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-16-A-01	Supply & Fixing of UPVC Sliding window	Sft	129.0000	470.00	60,630.00	470.00	1.000	470.00	60,630.00	67.63

Group : 2 MS Grill window/door/Vent S

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-30-FAB-040	Providing & fabricating and fixing work for M.S. Grill	Kg	193.5000	150.00	29,025.00	225.00	1.000	225.00	29,025.00	32.37

2940 1.4.6.2 SF-UPVC Ventilator with excahust 12.000 Sft 600(Net) 600(Gross) 7,200.00(Amt.) 0.05 %

SF-UPVC Ventilator with excahust

Group : 1 Sub contract-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-16-B-05	Supply & Fixing of UPVC Ventilator with Louver and exhaust	Sft	12.0000	600.00	7,200.00	600.00	1.000	600.00	7,200.00	100.00

2950 FLOORING WORKS

2960 1.4.7.1 SF-Lether finished granite Flooring 16.125 Sft 275(Net) 275(Gross) 4,434.38(Amt.) 0.03 %

SF-Lether finished granite Flooring

Group : 1 Granite Material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-02-GRA-01-004	STAIRCASE LEATHER GRANITE	Sqft	17.7375	160.00	2,838.00	176.00	1.000	176.00	2,838.00	64.00
A-01-CEM-01-001	CEMENT	BAG	0.4676	335.00	156.74	9.72	1.000	9.72	156.74	3.53

A-02-AGG-02-004	M SAND (BLACK)	Cft	3.5072	55.00	192.86	11.96	1.000	11.96	192.86	4.35
A-04-CHM-048	Jiont grouting filler for Grainte and tile works	KG	0.8063	45.00	36.28	2.25	1.000	2.25	36.28	0.82

Group : 2 Granite Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-10-GRN-002	L/c for Step Granite laying Work	Sqft	17.7375	40.00	709.50	44.00	1.000	44.00	709.50	16.00
L-10-MIS-002	L/c for Pointing and Clening in flooring surface	Sft	17.7375	3.00	53.21	3.30	1.000	3.30	53.21	1.20
L-10-GRN-004	L/c for Granite Full Nosing work	Rft	6.4500	70.00	451.50	28.00	1.000	28.00	451.50	10.18

2980 1.4.7.2 SF-Hall and Room flooring 744.146 Sft 155(Net) 155(Gross) 1,15,342.63(Amt.) 0.81 %

SF-Hall and Room flooring

Group : 1 Tile Flooring Material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-01-VIT-01-005	VITRIFIED TILE 24" X 24"	Sft	818.5606	100.00	81,856.06	110.00	1.000	110.00	81,856.06	70.97
A-01-CEM-01-001	CEMENT	BAG	25.0777	335.00	8,401.41	11.29	1.000	11.29	8,401.41	7.28
A-02-AGG-02-004	M SAND (BLACK)	Cft	125.3886	55.00	6,898.23	9.27	1.000	9.27	6,898.23	5.98
A-04-CHM-048	Jiont grouting filler for Grainte and tile works	KG	11.7575	45.00	528.34	0.71	1.000	0.71	528.34	0.46

Group : 2 Tile Flooring Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-10-VIT-001	L/c for vertified tile laying work	Sft	744.1460	20.00	14,882.92	20.00	1.000	20.00	14,882.92	12.90

L-10-MIS-002	L/c for Pointing and Clening in flooring surface	Sft	744.1460	3.00	2,232.44	3.00	1.000	3.00	2,232.44	1.94
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	744.1460	1.00	744.15	1.00	1.000	1.00	744.15	0.65

2990 1.4.7.3 SF-Anti skid tile flooring 235.828 Sft 155(Net) 155(Gross) 36,553.34(Amt.) 0.26 %

SF-Anti skid tile flooring

Group : 1 Tile Flooring Material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-01-VIT-01-004	VITRIFIED TILE 12" X 12"	Sft	259.4108	100.00	25,941.08	110.00	1.000	110.00	25,941.08	70.97
A-01-CEM-01-001	CEMENT	BAG	7.9474	335.00	2,662.50	11.29	1.000	11.29	2,662.50	7.28
A-02-AGG-02-004	M SAND (BLACK)	Cft	39.7370	55.00	2,186.13	9.27	1.000	9.27	2,186.13	5.98
A-04-CHM-048	Jiont grouting filler for Grainte and tile works	KG	3.7261	45.00	167.44	0.71	1.000	0.71	167.44	0.46

Group : 2 Tile Flooring Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-10-VIT-001	L/c for vertified tile laying work	Sft	235.8280	20.00	4,716.56	20.00	1.000	20.00	4,716.56	12.90
L-10-MIS-002	L/c for Pointing and Clening in flooring surface	Sft	235.8280	3.00	707.48	3.00	1.000	3.00	707.48	1.94
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	235.8280	1.00	235.83	1.00	1.000	1.00	235.83	0.65

3000 1.4.7.4 SF-Toilet full wall tile 565.560 Sft 150(Net) 150(Gross) 84,834.00(Amt.) 0.60 %

SF-Toilet full wall tile

Group : 1 **Wall tile Material**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-01-VIT-01-006	VITRIFIED WALL TILE	Sft	622.1160	100.00	62,211.60	110.00	1.000	110.00	62,211.60	73.33
A-01-CEM-01-001	CEMENT	BAG	16.4012	335.00	5,497.24	9.72	1.000	9.72	5,497.24	6.48
A-02-AGG-02-004	M SAND (BLACK)	Cft	61.5329	55.00	3,382.05	5.98	1.000	5.98	3,382.05	3.99
A-04-CHM-048	Jiont grouting filler for Grainte and tile works	KG	8.9358	45.00	401.55	0.71	1.000	0.71	401.55	0.47

Group : 2 **Wall tile Labour-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-10-VIT-010	L/c Wall Tile Laying	Sft	565.5600	20.00	11,311.20	20.00	1.000	20.00	11,311.20	13.33
L-10-MIS-002	L/c for Pointing and Clening in flooring surface	Sft	565.5600	3.00	1,696.68	3.00	1.000	3.00	1,696.68	2.00
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	565.5600	1.00	565.56	1.00	1.000	1.00	565.56	0.67

3050 **PAINTING WORKS**

3060 **1.4.8.1** **SF-Inner celing painting** **1,340.000 Sft** **21(Net)** **21(Gross)** **28,140.00(Amt.)** **0.20 %**

GF-Inner celing (White wash - 2 coat, primer-1, Emultion-2)

Group : 1 **In.Paint Material**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PT-001	White cement	Kg	73.7000	17.00	1,259.60	0.94	1.000	0.94	1,259.60	4.48
B-03-PT-002	Interior Primer	Ltr	11.3900	120.00	1,366.80	1.02	1.000	1.02	1,366.80	4.86
B-03-PT-004	Interior Emultion	Ltr	24.5220	500.00	12,261.00	9.15	1.000	9.15	12,261.00	43.57

Group : 2 **In.Paint Labour-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-11-INT-001	L/c for Int.paint White cement per coat	Sft	1,340.0000	2.10	2,814.00	2.10	1.000	2.10	2,814.00	10.00
L-11-INT-004	L/c for In.Paint Celing primer per coat	Sft	1,340.0000	2.10	2,814.00	2.10	1.000	2.10	2,814.00	10.00
L-11-INT-015	L/c for In.Paint Celing Emultion per coat	Sft	2,680.0000	2.30	6,164.00	4.60	1.000	4.60	6,164.00	21.90
L-07-MIS-040	Labour charges for Celing Surface Cleaning work	Sft	1,340.0000	1.00	1,340.00	1.00	1.000	1.00	1,340.00	4.76

Group : 3 In.paint Accessories

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PTH-010	4" Brush	NO	1.4740	250.00	375.20	0.28	1.000	0.28	375.20	1.33
B-03-PTO-007	Waste cloth	Kg	1.4740	80.00	120.60	0.09	1.000	0.09	120.60	0.43
B-03-PTH-045	Crack putty plate	NO	1.3400	25.00	40.20	0.03	1.000	0.03	40.20	0.14
B-03-PTH-060	6" Putty plate	NO	0.4020	85.00	40.20	0.03	1.000	0.03	40.20	0.14

3070 1.4.8.2 SF-inner wall painting 4,610.000 Sft 30(Net) 30(Gross) 1,38,300.00(Amt.) 0.98 %

GF-inner wall (Putty - 2 coat, Primer-1 coat, Emultion - 2 coat)

Group : 1 In.Paint Material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PT-006	Interior wall putty	kg	461.0000	25.00	11,525.00	2.50	1.000	2.50	11,525.00	8.33
B-03-PT-002	Interior Primer	Ltr	39.1850	120.00	4,702.20	1.02	1.000	1.02	4,702.20	3.40
B-03-PT-004	Interior Emultion	Ltr	84.3630	500.00	42,181.50	9.15	1.000	9.15	42,181.50	30.50

Group : 2 In.Paint Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%

L-11-INT-030	L/c for In.Paint Wall putty per coat	Sft	9,220.0000	2.50	23,050.00	5.00	1.000	5.00	23,050.00	16.67
L-11-INT-005	L/c for Int.paint Wall primer per coat	Sft	4,610.0000	2.10	9,681.00	2.10	1.000	2.10	9,681.00	7.00
L-11-INT-020	L/c for In.Paint Wall Emultion per coat	Sft	9,220.0000	2.30	21,206.00	4.60	1.000	4.60	21,206.00	15.33
L-07-MIS-045	Labour charges for Wall Surface Cleaning work	Sft	4,610.0000	1.00	4,610.00	1.00	1.000	1.00	4,610.00	3.33

Group : 3 In.paint Accessories

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PTH-010	4" Brush	NO	5.0710	250.00	1,290.80	0.28	1.000	0.28	1,290.80	0.93
B-03-PTH-035	9" Roller	NO	2.7660	260.00	737.60	0.16	1.000	0.16	737.60	0.53
B-03-PTH-045	Crack putty plate	NO	4.6100	25.00	138.30	0.03	1.000	0.03	138.30	0.10
B-03-PTH-070	12" Putty plate	NO	1.3830	130.00	184.40	0.04	1.000	0.04	184.40	0.13
B-03-PTH-065	8" Putty plate	NO	1.3830	100.00	138.30	0.03	1.000	0.03	138.30	0.10
B-03-PTH-060	6" Putty plate	NO	1.3830	85.00	138.30	0.03	1.000	0.03	138.30	0.10
B-03-PTO-007	Waste cloth	Kg	5.0710	80.00	414.90	0.09	1.000	0.09	414.90	0.30
B-03-PTO-003	POLISH PAPER - Emerry sheet - 180	NO	23.0500	20.00	461.00	0.10	1.000	0.10	461.00	0.33
B-03-PTO-009	POP	Kg	4.6100	25.00	138.30	0.03	1.000	0.03	138.30	0.10

Group : 4 Other

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	4,610.0000	1.00	4,610.00	1.00	1.000	1.00	4,610.00	3.33
R-01-SCA-005	Providing and fixing of Scaffolding Cost	Sft	4,610.0000	3.00	13,830.00	3.00	1.000	3.00	13,830.00	10.00

3080 1.4.8.3 SF-Exterier wall painting 1,500.000 Sft 31(Net) 31(Gross) 46,500.00(Amt.) 0.33 %

GF-Exterier wall (White wash - 2 coat, Primer-1 coat, Emultion - 2 coat)

Group : 1 Ext.Paint Material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PT-001	White cement	Kg	82.5000	17.00	1,410.00	0.94	1.000	0.94	1,410.00	3.03
B-03-PT-003	Exterior Primer	Ltr	20.7000	200.00	4,140.00	2.76	1.000	2.76	4,140.00	8.90
B-03-PT-005	Exterior Emultion	Ltr	36.6000	600.00	21,960.00	14.64	1.000	14.64	21,960.00	47.23

Group : 2 Ext.Paint Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-11-EXT-001	L/c for Ext.paint White cement per coat	Sft	3,000.0000	2.15	6,450.00	4.30	1.000	4.30	6,450.00	13.87
L-11-EXT-005	L/c for Ext.paint Wall primer per coat	Sft	1,500.0000	2.15	3,225.00	2.15	1.000	2.15	3,225.00	6.94
L-11-EXT-015	L/c for Ext.paint Emultion per coat	Sft	3,000.0000	2.20	6,600.00	4.40	1.000	4.40	6,600.00	14.19
L-07-MIS-045	Labour charges for Wall Surface Cleaning work	Sft	1,500.0000	1.00	1,500.00	1.00	1.000	1.00	1,500.00	3.23

Group : 3 Ext.paint Accessories

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PTH-010	4" Brush	NO	1.6500	250.00	420.00	0.28	1.000	0.28	420.00	0.90
B-03-PTH-045	Crack putty plate	NO	1.5000	25.00	45.00	0.03	1.000	0.03	45.00	0.10
B-03-PTH-060	6" Putty plate	NO	0.4500	85.00	45.00	0.03	1.000	0.03	45.00	0.10
B-03-PTO-007	Waste cloth	Kg	1.6500	80.00	135.00	0.09	1.000	0.09	135.00	0.29
B-03-PTO-009	POP	Kg	1.5000	25.00	45.00	0.03	1.000	0.03	45.00	0.10

3090 1.4.8.4 SF-Wood/Grill Painting 282.000 Sft 25(Net) 25(Gross) 7,050.00(Amt.) 0.05 %

GF-Grill Painting(Zinc.primer-2 + Enamal paint 2)

Group : 1 **Gril. painting Material**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PT-011	Enamal Paint	Lit	4.0326	300.00	1,209.78	4.29	1.000	4.29	1,209.78	17.16
B-03-PT-010	Zinchromate primer	Lit	2.0022	120.00	239.70	0.85	1.000	0.85	239.70	3.40
B-03-PTO-005	THINNER	LTR	2.0022	90.00	180.48	0.64	1.000	0.64	180.48	2.56

Group : 2 **Grill Painting Labour-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-11-INT-007	L/c for In.Paint Zink primer per coat	Sft	282.0000	5.25	1,480.50	5.25	1.000	5.25	1,480.50	21.00
L-11-INT-045	L/c for In.Paint Enamal paint (Grill two side) per coat	Sft	564.0000	7.00	3,948.00	14.00	1.000	14.00	3,948.00	56.00

Group : 3 **Grill Painting Accessories**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PTH-075	18 no Flat brush	NO	0.1410	100.00	14.10	0.05	1.000	0.05	14.10	0.20
B-03-PTH-080	20 no Flat brush	NO	0.1410	120.00	16.92	0.06	1.000	0.06	16.92	0.24
B-03-PTO-001	POLISH PAPER - Emerry sheet - 100	NO	1.4100	20.00	28.20	0.10	1.000	0.10	28.20	0.40
B-03-PTO-007	Waste cloth	Kg	0.1410	80.00	11.28	0.04	1.000	0.04	11.28	0.16

3110 **ELECTRICAL & PLUMBING WORKS**

3120 **1.4.9.1** **SF-supply and fixing of Electrical Subcontract works** **1,274.000 Sft** **152(Net)** **152(Gross)** **1,93,648.00(Amt.)** **1.37 %**

SF-supply and fixing of Electrical Subcontract works

Group : 1 **Electrical works material**

Aathiv builds and designs

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
D-08-ELE-A-005	25mm HMS PVC Conduit Pipe (Slab & Walls)	Rft	573.3000	25.00	14,332.50	11.25	1.000	11.25	14,332.50	7.40
D-08-ELE-A-010	20mm HMS PVC Conduit Pipe (Point Wiring)	Rft	254.8000	21.00	5,350.80	4.20	1.000	4.20	5,350.80	2.76
D-08-ELE-B-005	1.0 sq.mm Wire (Light/Fan Points - Green/Red/Black)	Coils	10.1920	2,300.00	23,441.60	18.40	1.000	18.40	23,441.60	12.11
D-08-ELE-B-010	1.5 sq.mm Wire (Primary Circuits/Sockets)	Coils	5.0960	3,000.00	15,288.00	12.00	1.000	12.00	15,288.00	7.89
D-08-ELE-B-015	2.5 sq.mm Wire (Power Points/ Geyser)	Coils	3.8220	5,200.00	19,874.40	15.60	1.000	15.60	19,874.40	10.26
D-08-ELE-B-020	4.0 sq.mm Wire (Main Line/ AC)	Coils	2.5480	7,500.00	19,110.00	15.00	1.000	15.00	19,110.00	9.87
D-08-ELE-C-005	12 Module Metal Box (Main Switch Board)	Nos	3.8220	250.00	955.50	0.75	1.000	0.75	955.50	0.49
D-08-ELE-C-010	8 Module Metal Box (Bedrooms/Kitchen)	Nos	5.0960	180.00	917.28	0.72	1.000	0.72	917.28	0.47
D-08-ELE-C-015	6 Module Metal Box (Utility/ AC)	Nos	5.0960	150.00	764.40	0.60	1.000	0.60	764.40	0.39
D-08-ELE-C-020	3/2/1 Module Metal Box (Single points/Calling bell)	Nos	15.2880	80.00	1,223.04	0.96	1.000	0.96	1,223.04	0.63
D-08-ELE-D-005	6A One-way Switch	Nos	57.3300	65.00	3,732.82	2.93	1.000	2.93	3,732.82	1.93
D-08-ELE-D-010	6A 3-pin Socket	Nos	22.9320	120.00	2,751.84	2.16	1.000	2.16	2,751.84	1.42
D-08-ELE-D-015	16A/25A Power Socket with Switch	Nos	7.6440	350.00	2,675.40	2.10	1.000	2.10	2,675.40	1.38
D-08-ELE-D-020	Fan Regulator (2-module step type)	Nos	6.3700	250.00	1,592.50	1.25	1.000	1.25	1,592.50	0.82
D-08-ELE-E-005	8-12 Way Double Door DB Box	Nos	1.2740	8,000.00	10,192.00	8.00	1.000	8.00	10,192.00	5.26
D-08-ELE-E-010	63A DP RCCB (30mA for safety)	Nos	1.2740	2,200.00	2,802.80	2.20	1.000	2.20	2,802.80	1.45

D-08-ELE-E-015	63A FP Isolator	Nos	1.2740	950.00	1,210.30	0.95	1.000	0.95	1,210.30	0.63
D-08-ELE-E-020	6A/10A/16A/25A Single Pole MCB	Nos	1.2740	350.00	445.90	0.35	1.000	0.35	445.90	0.23
D-08-ELE-F-005	PVC Junction Boxes (Deep/ Surface)	Nos	57.3300	25.00	1,439.62	1.13	1.000	1.13	1,439.62	0.74
D-08-ELE-F-015	PVC Bend (25mm/20mm)	Nos	76.4400	15.00	1,146.60	0.90	1.000	0.90	1,146.60	0.59
D-08-ELE-F-020	Solvent Cement (100ml)	Nos	2.5480	120.00	305.76	0.24	1.000	0.24	305.76	0.16
D-08-ELE-F-025	Insulation Tape (Assorted colors)	Nos	12.7400	30.00	382.20	0.30	1.000	0.30	382.20	0.20
D-08-ELE-F-030	Flexible Pipe (for drops)	Rft	38.2200	12.00	458.64	0.36	1.000	0.36	458.64	0.24

Group : 2 **Electrical Labor**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-31-ELE-020	L/C for Ele - Roof slab conduiting pipe laying works	Nos	6.3700	1,000.00	6,370.00	5.00	1.000	5.00	6,370.00	3.29
L-31-ELE-025	L/C for Ele - Wall Pipe and Mettal box fixing works	Nos	16.9442	1,000.00	16,944.20	13.30	1.000	13.30	16,944.20	8.75
L-31-ELE-030	L/C for Ele - Wiring works	Nos	12.7400	1,000.00	12,740.00	10.00	1.000	10.00	12,740.00	6.58
L-31-ELE-035	L/C for Ele - Swtiches & socket assamble and fixing works	Nos	10.5742	1,000.00	10,574.20	8.30	1.000	8.30	10,574.20	5.46
L-31-ELE-040	L/C for Ele - DB Board fixing & Wiring works	Nos	4.2042	1,000.00	4,204.20	3.30	1.000	3.30	4,204.20	2.17
L-31-ELE-045	L/C for Ele - Service connection and Testing works	Nos	4.2042	1,000.00	4,204.20	3.30	1.000	3.30	4,204.20	2.17
L-31-ELE-050	L/C for Ele - Light, fan, motor and orther fitting works	Nos	4.2042	1,000.00	4,204.20	3.30	1.000	3.30	4,204.20	2.17
L-31-ELE-055	L/C for Ele - other miscellaneous works	Nos	4.2042	1,000.00	4,204.20	3.30	1.000	3.30	4,204.20	2.17

3130 1.4.9.2 SF-supply and fixing of plumbing Subcontract works 1,274.000 Sft 210(Net) 210(Gross) 2,67,540.00(Amt.) 1.89 %

SF-supply and fixing of plumbing Subcontract works

Group : 1 Plumbingwork subcontract-

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-00-SUB-005	Plumbing Work Subcontract Labour	Sft	1,274.0000	50.00	63,700.00	50.00	1.000	50.00	63,700.00	23.81
K-00-SUB-006	Plumbing Work Subcontract Material	Sft	1,274.0000	160.00	2,03,840.00	160.00	1.000	160.00	2,03,840.00	76.19

3150 THIRED/TERRAES FLOOR

3160 SUPER STRUCTURE RCC WORK

3170 1.5.1.1 TRF- RCC - M20 (1:1.5:3)For Column 46.126 Cft 1,385(Net) 1,385(Gross) 63,884.51(Amt.) 0.45 %

TRF- RCC - M20 (1:1.5:3)For Column

Group : 1 RCC LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-035	L/C for laying concrete for Column	Cft	46.1260	60.00	2,767.56	60.00	1.000	60.00	2,767.56	4.33

Group : 2 RCC MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	9.9171	335.00	3,322.46	72.03	1.000	72.03	3,322.46	5.20
A-02-AGG-02-004	M SAND (BLACK)	Cft	18.5934	55.00	1,022.61	22.17	1.000	22.17	1,022.61	1.60

A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	37.1868	45.00	1,673.45	36.28	1.000	36.28	1,673.45	2.62
A-04-CHM-003	ADMIXTURE	KG	2.9336	80.00	234.78	5.09	1.000	5.09	234.78	0.37

Group : 3 RCC MACHINE

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	0.1522	2,500.00	380.54	8.25	1.000	8.25	380.54	0.60
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.1522	500.00	76.11	1.65	1.000	1.65	76.11	0.12

Group : 4 RCC CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	46.1260	1.00	46.13	1.00	1.000	1.00	46.13	0.07
O-01-CUR-001	OH/C CURING WORK	LS	46.1260	3.00	138.38	3.00	1.000	3.00	138.38	0.22
O-03-CONS-001	OH/C CONSUMABLES	LS	46.1260	2.00	92.25	2.00	1.000	2.00	92.25	0.14

Group : 5 Shuttering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-002	L/c- Column Shuttering	Sft	207.5670	17.00	3,528.64	76.50	1.000	76.50	3,528.64	5.52

Group : 6 Shuttering material-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-005	S/c- Column Shuttering material Cost	Sft	207.5670	20.00	4,151.34	90.00	1.000	90.00	4,151.34	6.50

Group : 7 MACHINERY and CONSUMA

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%

O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	46.1260	1.00	46.13	1.00	1.000	1.00	46.13	0.07
O-03-CONS-001	OH/C CONSUMABLES	LS	46.1260	2.00	92.25	2.00	1.000	2.00	92.25	0.14

Group : 8 STEEL MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	426.6655	80.00	34,133.24	740.00	1.000	740.00	34,133.24	53.43
A-03-REF-03	BINDING WIRE	KG	12.8000	100.00	1,280.00	27.75	1.000	27.75	1,280.00	2.00
A-05-COV-011	COVER BLOCK	NO	106.6664	2.00	213.56	4.63	1.000	4.63	213.56	0.33

Group : 9 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	426.6655	25.00	10,666.64	231.25	1.000	231.25	10,666.64	16.70

3180 1.5.1.2 TRF- RCC - M20 (1:1.5:3)For Lintel - 6" 27.377 Cft 685(Net) 685(Gross) 18,753.25(Amt.) 0.13 %

TRF- RCC - M20 (1:1.5:3)For Lintel - 6"

Group : 1 RCC MACHINE

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	0.0903	2,500.00	225.86	8.25	1.000	8.25	225.86	1.20
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.0903	500.00	45.17	1.65	1.000	1.65	45.17	0.24

Group : 2 RCC LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-065	L/c for laying concrete for Lintel	Cft	27.3770	45.00	1,231.97	45.00	1.000	45.00	1,231.97	6.57

Aathiv builds and designs

Group : 3 **RCC MATERIAL**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	5.8861	335.00	1,971.97	72.03	1.000	72.03	1,971.97	10.52
A-02-AGG-02-004	M SAND (BLACK)	Cft	11.0357	55.00	606.95	22.17	1.000	22.17	606.95	3.24
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	22.0713	45.00	993.24	36.28	1.000	36.28	993.24	5.30
A-04-CHM-003	ADMIXTURE	KG	1.7412	80.00	139.35	5.09	1.000	5.09	139.35	0.74

Group : 4 **RCC CONSUMABLES**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	27.3770	1.00	27.38	1.00	1.000	1.00	27.38	0.15
O-01-CUR-001	OH/C CURING WORK	LS	27.3770	3.00	82.13	3.00	1.000	3.00	82.13	0.44
O-03-CONS-001	OH/C CONSUMABLES	LS	27.3770	2.00	54.75	2.00	1.000	2.00	54.75	0.29

Group : 5 **Shuttering Labour-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-065	L/c- Lintel Shuttering	Sft	68.4425	25.00	1,711.06	62.50	1.000	62.50	1,711.06	9.12

Group : 6 **Shuttering material-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-025	S/c- Lintel Shuttering material Cost	Sft	68.4425	25.00	1,711.06	62.50	1.000	62.50	1,711.06	9.12

Group : 7 **STEEL MATERIAL**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	91.7130	80.00	7,337.04	268.00	1.000	268.00	7,337.04	39.12

A-03-REF-03	BINDING WIRE	KG	2.7514	100.00	275.14	10.05	1.000	10.05	275.14	1.47
A-05-COV-011	COVER BLOCK	NO	22.9282	2.00	45.99	1.68	1.000	1.68	45.99	0.25

Group : 8 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	91.7130	25.00	2,292.82	83.75	1.000	83.75	2,292.82	12.23

3190 1.5.1.3 TRF- RCC M20 (1:1.5:3) For parapet coping concrete 37.502 Cft 464(Net) 464(Gross) 17,400.93(Amt.) 0.12 %

TRF- RCC M20 (1:1.5:3) For parapet coping concrete

Group : 1 RCC LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-042	L/c for laying concrete for Basement belt	Cft	37.5020	50.00	1,875.10	50.00	1.000	50.00	1,875.10	10.78

Group : 2 RCC MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	8.0629	335.00	2,701.27	72.03	1.000	72.03	2,701.27	15.52
A-02-AGG-02-004	M SAND (BLACK)	Cft	15.1171	55.00	831.42	22.17	1.000	22.17	831.42	4.78
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	30.2341	45.00	1,360.57	36.28	1.000	36.28	1,360.57	7.82
A-04-CHM-003	ADMIXTURE	KG	2.3851	80.00	190.89	5.09	1.000	5.09	190.89	1.10

Group : 3 RCC MACHINE

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%

R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	0.1238	2,500.00	309.39	8.25	1.000	8.25	309.39	1.78
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.1238	500.00	61.88	1.65	1.000	1.65	61.88	0.36

Group : 4 RCC CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	37.5020	1.00	37.50	1.00	1.000	1.00	37.50	0.22
O-01-CUR-001	OH/C CURING WORK	LS	37.5020	3.00	112.51	3.00	1.000	3.00	112.51	0.65
O-03-CONS-001	OH/C CONSUMABLES	LS	37.5020	2.00	75.00	2.00	1.000	2.00	75.00	0.43

Group : 5 Shuttering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-004	L/c- Earth/Plinth beam Shuttering	Sft	93.7550	20.00	1,875.10	50.00	1.000	50.00	1,875.10	10.78

Group : 6 Shuttering material-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-015	S/c- Earth/Plinth beam Shuttering material Cost	Sft	93.7550	20.00	1,875.10	50.00	1.000	50.00	1,875.10	10.78

Group : 7 STEEL MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	56.2530	80.00	4,500.24	120.00	1.000	120.00	4,500.24	25.86
A-03-REF-03	BINDING WIRE	KG	1.6876	100.00	168.76	4.50	1.000	4.50	168.76	0.97
A-05-COV-011	COVER BLOCK	NO	9.3755	2.00	18.75	0.50	1.000	0.50	18.75	0.11

Group : 8 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	56.2530	25.00	1,406.33	37.50	1.000	37.50	1,406.33	8.08

3200 1.5.1.4 TRF- RCC - M20 (1:1.5:3)For Loft & Sunshade 32.000 Sft 217(Net) 217(Gross) 6,944.00(Amt.) 0.05 %

GF- RCC - M20 (1:1.5:3)For Kitchen Table top,Low roof,Loft and Sunshade

Group : 1 RCC MACHINE

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-003	Rental charges of Concrete mixer for Concreting work	N/day	0.0256	2,500.00	64.00	2.00	1.000	2.00	64.00	0.92
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.0256	500.00	12.80	0.40	1.000	0.40	12.80	0.18

Group : 2 RCC LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-065	L/c for laying concrete for Lintel	Cft	32.0000	45.00	1,440.00	45.00	1.000	45.00	1,440.00	20.74

Group : 3 RCC MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	1.7216	335.00	576.64	18.02	1.000	18.02	576.64	8.30
A-02-AGG-02-004	M SAND (BLACK)	Cft	3.2256	55.00	177.28	5.54	1.000	5.54	177.28	2.55
A-02-AGG-01-004	3/4" (20MM) AGGREGATE	Cft	6.4512	45.00	290.24	9.07	1.000	9.07	290.24	4.18
A-04-CHM-003	ADMIXTURE	KG	0.5088	80.00	40.64	1.27	1.000	1.27	40.64	0.59

Group : 4 RCC CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	32.0000	1.00	32.00	1.00	1.000	1.00	32.00	0.46
O-01-CUR-001	OH/C CURING WORK	LS	32.0000	3.00	96.00	3.00	1.000	3.00	96.00	1.38
O-03-CONS-001	OH/C CONSUMABLES	LS	32.0000	2.00	64.00	2.00	1.000	2.00	64.00	0.92

Group : 5 Shuttering material-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-030	S/c- Loft / sunshade /kitchen table Shuttering material Cost	Sft	32.0000	25.00	800.00	25.00	1.000	25.00	800.00	11.52

Group : 6 Shuttering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-037	L/c- Loft / sunshade /kitchen table Shuttering	Sft	32.0000	23.00	736.00	23.00	1.000	23.00	736.00	10.60

Group : 7 STEEL MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	24.0000	80.00	1,920.00	60.00	1.000	60.00	1,920.00	27.65
A-03-REF-03	BINDING WIRE	KG	0.7200	100.00	72.00	2.25	1.000	2.25	72.00	1.04
A-05-COV-011	COVER BLOCK	NO	6.0000	2.00	12.16	0.38	1.000	0.38	12.16	0.18

Group : 8 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	24.0000	25.00	600.00	18.75	1.000	18.75	600.00	8.64

3202 1.5.1.5 TRF - RCC - M20 Roof Beam using RMC 82.127 Cft 895(Net) 895(Gross) 73,503.67(Amt.) 0.52 %

Aathiv builds and designs

TRF - RCC - M20 Roof Beam using RMC

Group : 1 Shuttering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-105	L/c- Roof Beam Shuttering	Sft	279.2318	17.00	4,746.94	57.80	1.000	57.80	4,746.94	6.46

Group : 2 Shuttering material-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-040	S/c- Roof beam Shuttering material Cost	Sft	279.2318	30.00	8,376.95	102.00	1.000	102.00	8,376.95	11.40

Group : 3 STEEL MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	410.6350	80.00	32,850.80	400.00	1.000	400.00	32,850.80	44.69
A-03-REF-03	BINDING WIRE	KG	12.3191	100.00	1,231.91	15.00	1.000	15.00	1,231.91	1.68
A-05-COV-011	COVER BLOCK	NO	102.6588	2.00	205.32	2.50	1.000	2.50	205.32	0.28

Group : 4 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	410.6350	25.00	10,265.88	125.00	1.000	125.00	10,265.88	13.97

Group : 5 RCC LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-180	L/C for RMC Concrete laying using Pump	Cft	82.1270	15.00	1,231.91	15.00	1.000	15.00	1,231.91	1.68

Group : 6 RCC RMC MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-02-RMC-01-031	READYMIX CONCRETE M 20 GRADE	Cft	82.1270	160.00	13,140.32	160.00	1.000	160.00	13,140.32	17.88

M-01-PUM-02	CONCRETE PUMP	Cft	82.1270	5.00	410.64	5.00	1.000	5.00	410.64	0.56

Group : 7 RCC MACHINERY

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.2710	500.00	135.51	1.65	1.000	1.65	135.51	0.18

Group : 8 RCC CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	82.1270	1.00	82.13	1.00	1.000	1.00	82.13	0.11
O-01-CUR-001	OH/C CURING WORK	LS	82.1270	3.00	246.38	3.00	1.000	3.00	246.38	0.34
O-03-CONS-001	OH/C CONSUMABLES	LS	82.1270	2.00	164.25	2.00	1.000	2.00	164.25	0.22
O-03-CONS-005	OH/C Lead and Lift	LS	82.1270	5.00	410.64	5.00	1.000	5.00	410.64	0.56

3205 1.5.1.6 TRF- RCC - M20 Roof slab using RMC 180.759 Cft 563(Net) 563(Gross) 1,01,767.32(Amt.) 0.72 %

TRF- RCC - M20 Roof slab using RMC

Group : 1 Shuttering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-SHU-100	L/c- Roof Slab Shuttering	Sft	440.8712	25.00	11,022.68	60.98	1.000	60.98	11,022.68	10.83

Group : 2 Shuttering material-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-05-SHU-045	S/c- Roof Slab Shuttering material Cost	Sft	440.8712	20.00	8,817.42	48.78	1.000	48.78	8,817.42	8.66

Group : 3 STEEL MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-03-REF-02	TMT STEEL FE 500	KG	433.8216	80.00	34,705.73	192.00	1.000	192.00	34,705.73	34.10
A-03-REF-03	BINDING WIRE	KG	13.0146	100.00	1,301.46	7.20	1.000	7.20	1,301.46	1.28
A-05-COV-011	COVER BLOCK	NO	108.4554	2.00	216.91	1.20	1.000	1.20	216.91	0.21

Group : 4 STEEL LABOUR-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-REF-005	L/C for reinforcement work	KG	433.8216	25.00	10,845.54	60.00	1.000	60.00	10,845.54	10.66

Group : 5 RCC LABOUR -L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-02-CON-180	L/C for RMC Concrete laying using Pump	Cft	180.7590	15.00	2,711.38	15.00	1.000	15.00	2,711.38	2.66

Group : 6 RCC RMC MATERIAL

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-02-RMC-01-031	READYMIX CONCRETE M 20 GRADE	Cft	180.7590	160.00	28,921.44	160.00	1.000	160.00	28,921.44	28.42
M-01-PUM-02	CONCRETE PUMP	Cft	180.7590	5.00	903.80	5.00	1.000	5.00	903.80	0.89

Group : 7 RCC MACHINERY

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
R-02-CON-002	Rental charges of Vibrator for Concreting work	N/day	0.5965	500.00	298.25	1.65	1.000	1.65	298.25	0.29

Group : 8 RCC CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	180.7590	1.00	180.76	1.00	1.000	1.00	180.76	0.18

O-01-CUR-001	OH/C CURING WORK	LS	180.7590	3.00	542.28	3.00	1.000	3.00	542.28	0.53
O-03-CONS-001	OH/C CONSUMABLES	LS	180.7590	2.00	361.52	2.00	1.000	2.00	361.52	0.36
O-03-CONS-005	OH/C Lead and Lift	LS	180.7590	5.00	903.80	5.00	1.000	5.00	903.80	0.89

3208 **MASONRY WORK**

3210 **1.5.2.1** **TRF- 9" Brick work - Red brick with CM 1:6 Upto Roof level** **626.635 Cft** **267(Net)** **267(Gross)** **1,67,311.54(Amt.)** **1.18 %**

TRF- 9" Brick work - Red brick with CM 1:6 Upto Roof level

Group : 1 **MATERIAL**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	32.9610	335.00	11,041.31	17.62	1.000	17.62	11,041.31	6.60
A-02-AGG-02-004	M SAND (BLACK)	Cft	288.4401	55.00	15,866.40	25.32	1.000	25.32	15,866.40	9.48
A-02-BRK-02-006	RED BRICK (9" X 3" X 4")	NO	8,772.8900	12.00	1,05,274.68	168.00	1.000	168.00	1,05,274.68	62.92

Group : 2 **LABOUR -L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-04-MAS-155	L/c for 9" brick masonry	Cft	626.6350	50.00	31,331.75	50.00	1.000	50.00	31,331.75	18.73

Group : 3 **CONSUMABLES**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-01-CUR-001	OH/C CURING WORK	LS	626.6350	3.00	1,879.91	3.00	1.000	3.00	1,879.91	1.12

O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	626.6350	1.00	626.64	1.00	1.000	1.00	626.64	0.37
O-03-CONS-001	OH/C CONSUMABLES	LS	626.6350	2.00	1,253.27	2.00	1.000	2.00	1,253.27	0.75

3225 **PLASTREING WORK**

3240 **1.5.3.1** **TRF-Celing Plastering - 12mm thik - 1:4** **379.910 Sft** **47(Net)** **47(Gross)** **17,855.77(Amt.)** **0.13 %**

TRF-Celing Plastering - 12mm thik - 1:4

Group : 1 **CELING PLASTERING LABO**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-05-INT-010	L/c for Internal ceiling plaster	Sft	379.9100	25.00	9,497.75	25.00	1.000	25.00	9,497.75	53.19
L-07-MIS-035	L/c for pointing for plastering work	Sft	379.9100	3.00	1,139.73	3.00	1.000	3.00	1,139.73	6.38

Group : 2 **CELING PLASTERING MATE**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	5.2428	335.00	1,755.18	4.62	1.000	4.62	1,755.18	9.83
A-02-AGG-02-006	P SAND (PLASTER)	Cft	32.7862	65.00	2,131.30	5.61	1.000	5.61	2,131.30	11.94

Group : 3 **CONSUMABLES**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-01-CUR-001	OH/C CURING WORK	LS	379.9100	3.00	1,139.73	3.00	1.000	3.00	1,139.73	6.38
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	379.9100	1.00	379.91	1.00	1.000	1.00	379.91	2.13
O-03-CONS-001	OH/C CONSUMABLES	LS	379.9100	2.00	759.82	2.00	1.000	2.00	759.82	4.26

R-01-SCA-005	Providing and fixing of Scaffolding Cost	Sft	379.9100	3.00	1,139.73	3.00	1.000	3.00	1,139.73	6.38

3250 1.5.3.2 TRF-Internal Plastering - 18mm thik - 1:5 805.350 Sft 44(Net) 44(Gross) 35,435.40(Amt.) 0.25 %

TRF-Internal Plastering - 18mm thik - 1:5

Group : 1 WALL PLASTERING LABOU

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-05-INT-015	L/c for Internal Wall plaster	Sft	805.3500	23.00	18,523.05	23.00	1.000	23.00	18,523.05	52.27

Group : 2 WALL PLASTERING MATER

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	11.5165	335.00	3,857.63	4.79	1.000	4.79	3,857.63	10.89
A-02-AGG-02-006	P SAND (PLASTER)	Cft	86.4141	65.00	5,613.29	6.97	1.000	6.97	5,613.29	15.84

Group : 3 CONSUMABLES

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-01-CUR-001	OH/C CURING WORK	LS	805.3500	3.00	2,416.05	3.00	1.000	3.00	2,416.05	6.82
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	805.3500	1.00	805.35	1.00	1.000	1.00	805.35	2.27
R-01-SCA-005	Providing and fixing of Scaffolding Cost	Sft	805.3500	3.00	2,416.05	3.00	1.000	3.00	2,416.05	6.82
O-03-CONS-001	OH/C CONSUMABLES	LS	805.3500	2.00	1,610.70	2.00	1.000	2.00	1,610.70	4.55

3260 1.5.3.3 TRF-External Plastering - 18mm thik - 1:5 1,562.250 Sft 46(Net) 46(Gross) 71,863.50(Amt.) 0.51 %

TRF-External Plastering - 18mm thik - 1:5

Group : 1 **WALL PLASTERING LABOU**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-06-EXT-005	L/c for external plaster	Sft	1,562.2500	25.00	39,056.25	25.00	1.000	25.00	39,056.25	54.35

Group : 2 **WALL PLASTERING MATER**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
A-01-CEM-01-001	CEMENT	BAG	22.3402	335.00	7,483.18	4.79	1.000	4.79	7,483.18	10.41
A-02-AGG-02-006	P SAND (PLASTER)	Cft	167.6294	65.00	10,888.88	6.97	1.000	6.97	10,888.88	15.15

Group : 3 **CONSUMABLES**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-01-CUR-001	OH/C CURING WORK	LS	1,562.2500	3.00	4,686.75	3.00	1.000	3.00	4,686.75	6.52
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	1,562.2500	1.00	1,562.25	1.00	1.000	1.00	1,562.25	2.17
O-03-CONS-001	OH/C CONSUMABLES	LS	1,562.2500	2.00	3,124.50	2.00	1.000	2.00	3,124.50	4.35
R-01-SCA-005	Providing and fixing of Scaffolding Cost	Sft	1,562.2500	3.00	4,686.75	3.00	1.000	3.00	4,686.75	6.52

3270 **JOINERY WORKS**

3280 **1.5.4.1** **TRF-UPVC Winodw with safey grill** **118.500 Sft** **695(Net)** **695(Gross)** **82,357.50(Amt.)** **0.58 %**

TRF-UPVC Winodw with safey grill

Group : 1 **UPVC works**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%

K-16-A-01	Supply & Fixing of UPVC Sliding window	Sft	118.5000	470.00	55,695.00	470.00	1.000	470.00	55,695.00	67.63

Group : 2 MS Grill window/door/Vent S

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-30-FAB-040	Providing & fabricating and fixing work for M.S. Grill	Kg	177.7500	150.00	26,662.50	225.00	1.000	225.00	26,662.50	32.37

3285 1.5.4.2 TRF- UPVC Sliding Door 35.000 Sft 550.00(Net) 550.00(Gross) 19,250.00(Amt.) 0.14 %

TRF- UPVC Sliding Door

Group : 1 Door

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-16-C-05	Supply & Fixing of UPVC Sliding DOOR	Sft	35.0000	550.00	19,250.00	550.00	1.000	550.00	19,250.00	100.00

3290 GRILL WORKS

3300 1.5.5.1 TRF-Grill Door 21.000 Sft 425(Net) 425(Gross) 8,925.00(Amt.) 0.06 %

TRF-Grill Door

Group : 1 MS Grill window/door/Vent S

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-30-FAB-050	Providing & fabricating and fixing work for M.S. Trap door	Kg	52.5000	170.00	8,925.00	425.00	1.000	425.00	8,925.00	100.00

3310 PAINTING WORKS

3320 1.5.6.1 TRF-Inner celing(White wash - 2 coat, Primer-1 coat, Emul -2 380.000 Sft 21(Net) 21(Gross) 7,980.00(Amt.) 0.06 %

GF-Inner celing (White wash - 2 coat, Primer-1 coat, Emultion - 2 coat)

Group : 1 In.Paint Material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PT-001	White cement	Kg	20.9000	17.00	357.20	0.94	1.000	0.94	357.20	4.48
B-03-PT-002	Interior Primer	Ltr	3.2300	120.00	387.60	1.02	1.000	1.02	387.60	4.86
B-03-PT-004	Interior Emultion	Ltr	6.9540	500.00	3,477.00	9.15	1.000	9.15	3,477.00	43.57

Group : 2 In.Paint Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-11-INT-001	L/c for Int.paint White cement per coat	Sft	380.0000	2.10	798.00	2.10	1.000	2.10	798.00	10.00
L-11-INT-004	L/c for In.Paint Celing primer per coat	Sft	380.0000	2.10	798.00	2.10	1.000	2.10	798.00	10.00
L-11-INT-015	L/c for In.Paint Celing Emultion per coat	Sft	760.0000	2.30	1,748.00	4.60	1.000	4.60	1,748.00	21.90
L-07-MIS-040	Labour charges for Celing Surface Cleaning work	Sft	380.0000	1.00	380.00	1.00	1.000	1.00	380.00	4.76

Group : 3 In.paint Accessories

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PTH-010	4" Brush	NO	0.4180	250.00	106.40	0.28	1.000	0.28	106.40	1.33
B-03-PTO-007	Waste cloth	Kg	0.4180	80.00	34.20	0.09	1.000	0.09	34.20	0.43
B-03-PTH-045	Crack putty plate	NO	0.3800	25.00	11.40	0.03	1.000	0.03	11.40	0.14
B-03-PTH-060	6" Putty plate	NO	0.1140	85.00	11.40	0.03	1.000	0.03	11.40	0.14

3330 1.5.6.2 TRF-inner wall (Putty - 2 coat, Primer-1 coat, Emultion - 2 844.000 Sft 30(Net) 30(Gross) 25,320.00(Amt.) 0.18 %

GF-inner wall (Putty - 2 coat, Primer-1 coat, Emultion - 2 coat)

Aathiv builds and designs

Group : 1 **In.Paint Material**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PT-006	Interior wall putty	kg	84.4000	25.00	2,110.00	2.50	1.000	2.50	2,110.00	8.33
B-03-PT-002	Interior Primer	Ltr	7.1740	120.00	860.88	1.02	1.000	1.02	860.88	3.40
B-03-PT-004	Interior Emultion	Ltr	15.4452	500.00	7,722.60	9.15	1.000	9.15	7,722.60	30.50

Group : 2 **In.Paint Labour-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-11-INT-030	L/c for In.Paint Wall putty per coat	Sft	1,688.0000	2.50	4,220.00	5.00	1.000	5.00	4,220.00	16.67
L-11-INT-005	L/c for Int.paint Wall primer per coat	Sft	844.0000	2.10	1,772.40	2.10	1.000	2.10	1,772.40	7.00
L-11-INT-020	L/c for In.Paint Wall Emultion per coat	Sft	1,688.0000	2.30	3,882.40	4.60	1.000	4.60	3,882.40	15.33
L-07-MIS-045	Labour charges for Wall Surface Cleaning work	Sft	844.0000	1.00	844.00	1.00	1.000	1.00	844.00	3.33

Group : 3 **In.paint Accessories**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PTH-010	4" Brush	NO	0.9284	250.00	236.32	0.28	1.000	0.28	236.32	0.93
B-03-PTH-035	9" Roller	NO	0.5064	260.00	135.04	0.16	1.000	0.16	135.04	0.53
B-03-PTH-045	Crack putty plate	NO	0.8440	25.00	25.32	0.03	1.000	0.03	25.32	0.10
B-03-PTH-070	12" Putty plate	NO	0.2532	130.00	33.76	0.04	1.000	0.04	33.76	0.13
B-03-PTH-065	8" Putty plate	NO	0.2532	100.00	25.32	0.03	1.000	0.03	25.32	0.10
B-03-PTH-060	6" Putty plate	NO	0.2532	85.00	25.32	0.03	1.000	0.03	25.32	0.10
B-03-PTO-007	Waste cloth	Kg	0.9284	80.00	75.96	0.09	1.000	0.09	75.96	0.30
B-03-PTO-003	POLISH PAPER - Emerry sheet - 180	NO	4.2200	20.00	84.40	0.10	1.000	0.10	84.40	0.33
B-03-PTO-009	POP	Kg	0.8440	25.00	25.32	0.03	1.000	0.03	25.32	0.10

Group : 4 **Other**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	844.0000	1.00	844.00	1.00	1.000	1.00	844.00	3.33
R-01-SCA-005	Providing and fixing of Scaffolding Cost	Sft	844.0000	3.00	2,532.00	3.00	1.000	3.00	2,532.00	10.00

3340 **1.5.6.3** **TRF-Exterier wall (White wash - 2 coat, Primer-1 coat, - 2** **1,562.000 Sft** **31(Net)** **31(Gross)** **48,422.00(Amt.)** **0.34 %**

TRF-Exterier wall (White wash - 2 coat, Primer-1 coat, Emultion - 2 coat)

Group : 1 **Ext.Paint Material**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PT-001	White cement	Kg	85.9100	17.00	1,468.28	0.94	1.000	0.94	1,468.28	3.03
B-03-PT-003	Exterior Primer	Ltr	21.5556	200.00	4,311.12	2.76	1.000	2.76	4,311.12	8.90
B-03-PT-005	Exterior Emultion	Ltr	38.1128	600.00	22,867.68	14.64	1.000	14.64	22,867.68	47.23

Group : 2 **Ext.Paint Labour-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-11-EXT-001	L/c for Ext.paint White cement per coat	Sft	3,124.0000	2.15	6,716.60	4.30	1.000	4.30	6,716.60	13.87
L-11-EXT-005	L/c for Ext.paint Wall primer per coat	Sft	1,562.0000	2.15	3,358.30	2.15	1.000	2.15	3,358.30	6.94
L-11-EXT-015	L/c for Ext.paint Emultion per coat	Sft	3,124.0000	2.20	6,872.80	4.40	1.000	4.40	6,872.80	14.19
L-07-MIS-045	Labour charges for Wall Surface Cleaning work	Sft	1,562.0000	1.00	1,562.00	1.00	1.000	1.00	1,562.00	3.23

Group : 3 **Ext.paint Accessories**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%

B-03-PTH-010	4" Brush	NO	1.7182	250.00	437.36	0.28	1.000	0.28	437.36	0.90
B-03-PTH-045	Crack putty plate	NO	1.5620	25.00	46.86	0.03	1.000	0.03	46.86	0.10
B-03-PTH-060	6" Putty plate	NO	0.4686	85.00	46.86	0.03	1.000	0.03	46.86	0.10
B-03-PTO-007	Waste cloth	Kg	1.7182	80.00	140.58	0.09	1.000	0.09	140.58	0.29
B-03-PTO-009	POP	Kg	1.5620	25.00	46.86	0.03	1.000	0.03	46.86	0.10

3350 1.5.6.4 TRF-Wood /Grill painting (Primer-1 + stn.enamal-2) 160.500 Sft 26(Net) 26(Gross) 4,173.00(Amt.) 0.03 %

TRF-Wood /Grill painting (Primer-1 +stn.enamal-2)

Group : 1 Wood paint Material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PT-009	Wood primer	Lit	1.3322	120.00	160.50	1.00	1.000	1.00	160.50	3.85
B-03-PT-011	Enamal Paint	Lit	2.2952	300.00	688.55	4.29	1.000	4.29	688.55	16.50
B-03-PTO-005	THINNER	LTR	2.2952	90.00	207.05	1.29	1.000	1.29	207.05	4.96

Group : 2 Wood paint Labor-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-11-INT-006	L/c for In.Paint Wood primer per coat	Sft	160.5000	5.25	842.63	5.25	1.000	5.25	842.63	20.19
L-11-INT-040	L/c for In.Paint Enamal paint (door/window two side) 1 c	Sft	321.0000	7.00	2,247.00	14.00	1.000	14.00	2,247.00	53.85

Group : 3 Grill Painting Accessories

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-03-PTO-004	POLISH PAPER - Emerry sheet - 220	NO	0.8025	20.00	16.05	0.10	1.000	0.10	16.05	0.38

B-03-PTO-007	Waste cloth	Kg	0.0803	80.00	6.42	0.04	1.000	0.04	6.42	0.15
B-03-PTH-001	2" Brush	NO	0.0803	100.00	8.03	0.05	1.000	0.05	8.03	0.19
B-03-PTH-005	3" Brush	NO	0.0803	180.00	14.45	0.09	1.000	0.09	14.45	0.35

3370 ELECTRICAL & PLUMBING WORKS

3380 1.5.7.1 TRF-supply and fixing of Electrical Subcontract works 300.875 Sft 100(Net) 100(Gross) 30,087.50(Amt.) 0.21 %

TRF-supply and fixing of Electrical Subcontract works

Group : 1 Electrical work subcontract-

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-00-SUB-003	Electrical Work Subcontract Labour	Sft	300.8750	50.00	15,043.75	50.00	1.000	50.00	15,043.75	50.00
K-00-SUB-004	Electrical Work Subcontract Material	Sft	300.8750	50.00	15,043.75	50.00	1.000	50.00	15,043.75	50.00

5000 WEATHERING COURSE WORKS

5010 1.5.8.1 TRF-Weathering coarse with Brick Batts 302.188 Cft 139(Net) 144(Gross) 43,515.07(Amt.) 0.31 %

TRF-Screed concrete with power trawel finishing for wethering floor

Group : 1 Wethering Material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
E-10-MIS-065	LIME POWDER	Cft	114.8314	70.00	8,038.20	26.60	1.000	26.60	8,038.20	18.47
A-02-BRK-02-005	BRICK BATS (Brick jally)	Cft	344.4943	50.00	17,224.72	57.00	1.000	57.00	17,224.72	39.58

Group : 2 Wethering Labour-L

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-10-WETHER-01	L/c for Wethering corse surki concrete laying with lifting	Cft	302.1880	35.00	10,576.58	35.00	1.000	35.00	10,576.58	24.31
L-10-WETHER-02	L/c for Wethering corse Brick bats Broken charges	Cft	302.1880	20.00	6,043.76	20.00	1.000	20.00	6,043.76	13.89

Additional cost: Floor lifting Charges 10.00 % 5.50 1,662.03 3.82

5020 1.5.8.2 TRF-Water proof for Terrace flooring 1,208.750 Sft 17(Net) 17(Gross) 20,548.75(Amt.) 0.15 %

TRF-Water proof for Terrace flooring

Group : 1 Sub contract Water proofing

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-09-BBC-008	Providing & applying waterproofing treatment for Terrace	Sft	1,329.6250	15.00	19,944.38	16.50	1.000	16.50	19,944.38	97.06

5030 1.5.8.3 TRF-Cool Roof tile flooring for Terrace 1,208.750 Sft 155(Net) 155(Gross) 1,87,356.25(Amt.) 1.32 %

TRF-Cool Roof tile flooring for Terrace

Group : 1 Flooring Material

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
B-01-MIS-005	Cool Roof Tile (White)	Sft	1,329.6250	100.00	1,32,962.50	110.00	1.000	110.00	1,32,962.50	70.97
A-01-CEM-01-001	CEMENT	BAG	40.7349	335.00	13,646.79	11.29	1.000	11.29	13,646.79	7.28
A-02-AGG-02-004	M SAND (BLACK)	Cft	203.6744	55.00	11,205.11	9.27	1.000	9.27	11,205.11	5.98
A-04-CHM-048	Jiont grouting filler for Grainte and tile works	KG	19.0983	45.00	858.21	0.71	1.000	0.71	858.21	0.46

Group : 2 **Flooring Labour-L**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-10-VIT-001	L/c for vertified tile laying work	Sft	1,208.7500	20.00	24,175.00	20.00	1.000	20.00	24,175.00	12.90
L-10-MIS-002	L/c for Pointing and Clening in flooring surface	Sft	1,208.7500	3.00	3,626.25	3.00	1.000	3.00	3,626.25	1.94
O-02-SUN-001	OH/C SUNDRISE & TOOLS	LS	1,208.7500	1.00	1,208.75	1.00	1.000	1.00	1,208.75	0.65

5040 **1.5.8.4** **TRF-Sintex Tank** **4,000.000 liter** **6(Net)** **6(Gross)** **24,000.00(Amt.)** **0.17 %**

GF-1500 litr Capacity Sintex Tank

Group : 1 **Over head tank**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-32-MIS-070	WATER TANK (Sintex)	Liter	4,000.0000	6.00	24,000.00	6.00	1.000	6.00	24,000.00	100.00

5050 **ADDITIONAL WORKS**

5060 **2.1** **SUMP - 10000 LIT** **10,000.000 LIT** **20.00(Net)** **20.00(Gross)** **2,00,000.00(Amt.)** **1.41 %**

SUMP - 10000 LIT

Group : 1 **SUMP**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-32-MIS-080	Sump/Septic/Overhead TANK - 9"(BW+RCC)	Lit	10,000.0000	20.00	2,00,000.00	20.00	1.000	20.00	2,00,000.00	100.00

5065 **2.2** **Bio septic tank** **1,000.000 Lit** **50.00(Net)** **50.00(Gross)** **50,000.00(Amt.)** **0.35 %**

Bio septic tank

Group : 1 **Bio tank**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-32-MIS-100	9"-BW SUMP/SEPTIC TANK	Litr	1,000.0000	50.00	50,000.00	50.00	1.000	50.00	50,000.00	100.00

5067 **2.3** **Soak pit** **3.000 nos** **19,950.00(Net)** **19,950.00(Gross)** **59,850.00(Amt.)** **0.42 %**

Soak pit

Group : 1 **Soak pit**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-32-MIS-065	Erection of 3' Well Ring for Rainwater Harversting	Nos	21.0000	850.00	17,850.00	5,950.00	1.000	5,950.00	17,850.00	29.82
K-32-MIS-060	Supply of 3' Well Ring for Rainwater Harversting	Nos	21.0000	2,000.00	42,000.00	14,000.00	1.000	14,000.00	42,000.00	70.18

5070 **2.4** **COMPOUND WALL** **60.000 RFT** **2,700.00(Net)** **2,700.00(Gross)** **1,62,000.00(Amt.)** **1.14 %**

COMPOUND WALL

Group : 1 **CW**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
K-32-MIS-110	Compound wall Work	Rft	60.0000	2,700.00	1,62,000.00	2,700.00	1.000	2,700.00	1,62,000.00	100.00

5072 **2.5** **Main Gate** **48.000 Sft** **1,700(Net)** **1,700(Gross)** **81,600.00(Amt.)** **0.58 %**

Main Gate

Group : 1 **MS Grill window/door/Vent S**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%

K-30-FAB-050	Providing & fabricating and fixing work for M.S. Trap door	Kg	480.0000	170.00	81,600.00	1,700.00	1.000	1,700.00	81,600.00	100.00

5100 **2.6** **Bathroom shower cubicle** **3.000 Ls** **0.00(Net) 35,000.00(Gross) 1,05,000.00(Amt.) 0.74 %**

Bathroom shower cubicle

Forced gross price independent of the price calculation: 35,000.00 INR

5110 **2.7** **Elevation and Fabrication** **1.000 Ls** **0.00(Net),00,000.00(Gross) 4,00,000.00(Amt.) 2.83 %**

Elevation and Fabrication

Forced gross price independent of the price calculation: 4,00,000.00 INR

5500 **PMC FEE**

6000 **3.1** **PMC Consusult Fee** **1.000 LS** **,00,000.00(Net),00,000.00(Gross) 0,00,000.00(Amt.) 14.13 %**

PMC Consusult Fee

Group : 1 **PMC Consusult Fee**

Resource ID	Resource name	Unit	Qty/W.I	Price	Net Amount	Net rate /unit	Margin	Gross rate/unit	Gross Amount	%
L-99-DEP-065	Supply of Supervisor	Day	1.0000	20,00,000.00	20,00,000.00	20,00,000.00	1.000	20,00,000.00	20,00,000.00	100.00